

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	653 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	20.84 SMI		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	17,818 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	525 SY		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,276 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	6,096 TON		
0008	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	14,826 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,774 TON		
0010	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	182,350 SY		
0011	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	15 EA		
0012	2830000000-N	858	ADJUSTMENT OF MANHOLES	14 EA		
0013	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	22 EA		
0014	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	91,528 LF		
0015	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	61,277 LF		
0016	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	188 LF		
0017	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	226 LF		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	4,963 LF		
001E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	805 LF		
002C	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	42 EA		
0021	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	78 EA		
0022	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	311,186 LF		
002E	6084000000-E	1660	SEEDING & MULCHING	4.87 ACR		
0024	6110000000-E	SP	RESIDENTIAL SEEDING	3.7 ACR		
002E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	20 LF		
002E	7312000000-N	1716	JUNCTION BOX (*****) (STANDARD)	1 EA		
0027	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,500 LF		
002E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	20 LF		

0954/Dec13/Q708233.41/D105362100000/E28

Total Amount Of Bid For Entire Project :

Contract No: C201996

County: Orange

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General