8-4309

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

STATE PROJECT REFERENCE NO.	SHEET NO.
B-4309	TCP-1

PLAN FOR PROPOSED TRAFFIC CONTROL, MARKING & DELINEATION

WARREN COUNTY

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS"-PROJECT SERVICES UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C., DATED JULY 2006 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

S	T	D		V	0	

TITLE

1101.03	TEMPORARY ROAD CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1110.01	STATIONARY WORK ZONE SIGNS
1145.01	BARRICADES
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE AND MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	PAVEMENT MARKER SPACING
1251.01	RAISED PAVEMENT MARKERS - TEMPORARY AND PERMANENT
1261.01	GUARDRAIL AND BARRIER DELINEATOR SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATOR TYPES
1262.01	GUARDRAIL END DELINEATION

INDEX OF SHEETS

SHEET NO.

TCP-1

TITLE

LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, INDEX OF SHEETS, LEGEND AND PAVEMENT MARKING SCHEDULE

TCP-2 PROJECT NOTES AND PHASING
TCP-3 OFF-SITE DETOUR ROUTE
TCP-4 OFF-SITE DETOUR SIGNING
SD-1 SPECIAL SIGN DESIGN

PAVEMENT MARKING SCHEDULE

PAY ITEM QUANTITY

BREAKDOWN TO

TOTAL QUANTITY

FINAL

PAVEMENT MARKINGS

PAINT(4")

PA WHITE EDGELINE (2X)
PI YELLOW DOUBLE CENTER (2X)

DESCRIPTION

SYMBOL

5200 LF 5200 LF

TOTAL 10400 LF

MARKERS

PERMANENT RAISED PAVEMENT MARKERS

A YELLOW & YELLOW

17 EA TOTAL

17 EA

NOTE: FOR EACH PAINT PAVEMENT MARKING ITEM, 1X IMPLIES A SINGLE APPLICATION, 2X IMPLIES TWO APPLICATIONS, AND 3X IMPLIES THREE APPLICATIONS.

[LEGEND]

GENERAL

✓ DIRECTION OF TRAFFIC FLOW

NORTH ARROW

PROPOSED PVMT. ----- EXIST. PVMT.

1

WORK AREA



REMOVAL OF EXISTING PAVEMENT

TRAFFIC CONTROL DEVICES

T TYPE I BARRICADE

TYPE III BARRICADE

▲ CONE

DRUM SKINNY DRUM

FLASHING ARROW PANEL (TYPE C)

- STATIONARY SIGN

PORTABLE SIGN

STATIONARY OR PORTABLE SIGN

CRASH CUSHION

<□ CHANGEABLE MESSAGE SIGN

TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)

* POLICE

■ FLAGGER


PAVEMENT MARKINGS

CRYSTAL/CRYSTAL PAVEMENT MARKER

◆ YELLOW/YELLOW PAVEMENT MARKER

CRYSTAL/RED PAVEMENT MARKER

PAVEMENT MARKING SYMBOLS



TIP PROJECT:

A1 W21C224I02

PROJECT NOTES

PROJ. REFERENCE NO. SHEET NO.

B-4309
TCP-2

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS, OR RESULT IN DUPLICATE, OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING OR REMOVAL OF DEVICES, AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

PAVEMENT EDGE DROP OFF REQUIREMENTS

A) BACKFILL AT A 6:1 SLOPE UP TO THE EDGE AND ELEVATION OF EXISTING PAVEMENT IN AREAS ADJACENT TO AN OPENED TRAVEL LANE THAT HAS AN EDGE OF PAVEMENT DROP-OFF AS FOLLOWS:

BACKFILL DROP-OFFS THAT EXCEED 2 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS OF 45 MPH OR GREATER.

BACKFILL DROP-OFFS THAT EXCEED 3 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS LESS THAN 45 MPH.

BACKFILL WITH SUITABLE COMPACTED MATERIAL, AS APPROVED BY THE ENGINEER, AT NO EXPENSE TO THE DEPARTMENT.

B) DO NOT EXCEED A DIFFERENCE OF 2 INCHES IN ELEVATION BETWEEN OPEN LANES OF TRAFFIC FOR NOMINAL LIFTS OF 1.5 INCHES. INSTALL ADVANCE WARNING "UNEVEN LANES" SIGNS (W8-11) 500' IN ADVANCE AND A MINIMUM OF EVERY HALF MILE THROUGHOUT THE UNEVEN AREA.

TRAFFIC PATTERN ALTERATIONS

C) NOTIFY THE ENGINEER TWENTY ONE (21) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

- D) INSTALL ADVANCE WORK ZONE WARNING SIGNS WHEN WORK IS WITHIN 40 FT FROM THE EDGE OF TRAVEL LANE AND NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- E) PROVIDE PERMANENT SIGNING.
- F) PROVIDE DETOUR SIGNING WITHIN AND OFF THE PROJECT LIMITS.
- G) COVER OR REMOVE ALL DETOUR SIGNS WITHIN AND OFF THE PROJECT LIMITS WHEN A DETOUR IS NOT IN OPERATION.
- H) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC CONTROL DEVICES

I) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.

PAVEMENT MARKINGS AND MARKERS

J) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME

MARKING

MARKER

SR1306

PAINT

RAISED REFLECTIVE

- K) PLACE TWO APPLICATIONS OF PAINT PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE. PLACE THE SECOND APPLICATION OF PAINT UPON SUFFICIENT DRYING TIME OF THE FIRST.
- L) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- M) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS BY THE END OF EACH DAY'S OPERATION.

LOCAL NOTES

- 1. COORDINATE ROAD CLOSING WITH WARREN COUNTY SCHOOLS AND EMERGENCY SERVICES. NOTIFY WARREN COUNTY EMERGENCY SERVICES ONE (1) MONTH PRIOR TO THE BEGINNING OF THE TEMPORARY ROAD CLOSURE.
- 2. INSTALL SIGNS BEFORE THE BARRICADES WHEN CLOSING THE ROADWAY TO TRAFFIC. REMOVE BARRICADES BEFORE THE SIGNS WHEN OPENING THE ROADWAY TO TRAFFIC. INSTALL/REMOVE SIGNS AND BARRICADES WITHIN THE SAME CALENDAR DAY.
- 3. ALL SIGN SPACING DIMENSIONS ARE APPROXIMATE, FIELD ADJUST AS NECESSARY OR AS DIRECTED.
- 4. MAINTAIN DRIVEWAY ACCESS WITHIN PROJECT LIMITS USING INCIDENTAL STONE.
- 5. USE FLAGGERS AS NEEDED TO MAINTAIN LOCAL TRAFFIC WITHIN ROAD CLOSURE. FLAGGING WILL BE INCIDENTAL TO THE COST OF THE CONTRACT.
- 6. REAPPLY PAVEMENT MARKINGS UP TO 100' BEYOND CONSTRUCTION LIMITS IF NEEDED TO REPAIR DAMAGE AND/OR TRACKING FROM CONSTRUCTION.


PHASING

- STEP 1 INSTALL SIGNS AND BARRICADES CLOSING SR 1306 TO THROUGH TRAFFIC AS SHOWN ON TCP-3, TCP-4 AND TCP-5 AND IN ACCORDANCE WITH ROADWAY STANDARD DRAWING 1101.03, SHEET 1 OF 9. (SEE LOCAL NOTES NO. 1, 2 and 3)
- STEP 2 CONSTRUCT THE FOLLOWING WITHIN THE ROAD CLOSURE: (SEE LOCAL NOTES NO. 4 AND 5)
 - -REMOVE THE EXISTING STRUCTURE
 - -CONSTRUCT THE PROPOSED STRUCTURE
 - -CONSTRUCT THE PROPOSED ROADWAY SECTION -L- UP TO BUT NOT INCLUDING THE FINAL LAYER OF SURFACE FROM STA. 10+00+/TO STA. 16+40+/- AND FROM STA. 17+35+/- TO STA. 23+00+/-
- STEP 3 PLACE THE FINAL LAYER OF SURFACE COURSE ON -L- FROM STA.

 10+00+/- TO STA. 23+00+/- AND APPLY THE FINAL PAVEMENT

 MARKINGS AND PAVEMENT MARKERS ON -L- FROM STA. 10+00+/- TO

 STA. 23+00+/-. (SEE LOCAL NOTE NO. 6)
- STEP 4 REMOVE ALL BARRICADES, ROAD CLOSED SIGNS AND DETOUR SIGNS FROM PROJECT AND OPEN SR 1306 TO THROUGH TRAFFIC. (SEE LOCAL NOTE NO. 2)



PROJECT NOTES

DATE: 09/07

DWG. BY: DWB

DESIGN BY: DWB

REVIEWED BY: JDK

OF HIGH


REVISIONS


\dfsroot0|\ProjStore\Proj\tipprojects-b\b4309\traffic\trafficcontrol\tcp\b-4309_tc_tcp_02, sette AT WZTC237500

PROJ. REFERENCE NO. B-4309 TCP-3 OFF-SITE DETOUR ROUTE 09/07

<u>1307</u> <u>1334</u> <u>1304</u> INSET A <u>1306</u> 1309 <u>1337</u> T B B 1340 BY BT 158 APPROVED: SOCIALLY DATE: 9/24/0 <u>1325</u>

DESIGN BY: DWB
REVIEWED BY: JDK





*BARRICADES USED TO CLOSE A ROADWAY SHALL EXTEND ACROSS THE ENTIRE ROADWAY. WHERE LOCAL TRAFFIC MUST BE MAINTAINED, THEY MAY BE PLACED IN A STAGGERED POSITION.

SEAL

SEAL

SEAL

OFF-SITE DETOUR SIGNING

SCALE: NONE
DATE: 09/07
DWG. BY: DWB
DESIGN BY: DWB
REVIEWED BY: JDK