

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** 10+87.86	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1.5 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	190 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0012	0342000000-E	310	*** SIDE DRAIN PIPE (48")	24 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	180 LF		
0014	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (84",TYPE B 0.168")	28 LF		
0015	0995000000-E	340	PIPE REMOVAL	140 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	135 TON		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	95 TON		
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	140 TON		
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	20 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	20 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	170 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
003C	2556000000-E	846	SHOULDER BERM GUTTER	125 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	37.5 LF		
0032	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	81.25 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1	EA	
0037	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	112.5	LF	
003E	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	37.5	LF	
003E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	2	EA	
004C	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2	EA	
0041	3649000000-E	876	RIP RAP, CLASS B	4	TON	
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	329	SY	
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	280	SF	
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	112	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20	SF	
004E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
0047	4430000000-N	1130	DRUMS	32	EA	
004E	4435000000-N	1135	CONES	30	EA	
004E	4445000000-E	1145	BARRICADES (TYPE III)	40	LF	
005C	4450000000-N	1150	FLAGGER	600	HR	
0051	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0052	4480000000-N	1165	TMIA	2	EA	
0053	4485000000-E	1170	PORTABLE CONCRETE BARRIER	310	LF	
0054	4516000000-N	1180	SKINNY DRUM	30	EA	

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	104	EA	
005E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,060	LF	
0057	4795000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (24") (IV)	17	LF	
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,096	LF	
005E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	92	LF	
006C	6000000000-E	1605	TEMPORARY SILT FENCE	410	LF	
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160	TON	
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	225	TON	
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	175	TON	
0064	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0067	6029000000-E	SP	SAFETY FENCE	200	LF	
006E	6030000000-E	1630	SILT EXCAVATION	380	CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	240	SY	
007C	6042000000-E	1632	1/4" HARDWARE CLOTH	80	LF	
0071	6070000000-N	SP	SPECIAL STILLING BASINS	2	EA	
0072	6084000000-E	1660	SEEDING & MULCHING	0.65	ACR	

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6087000000-E	1660	MOWING	0.5	ACR	
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	
007E	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0079	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	
008C	6126000000-E	SP	STREAMBANK REFORESTATION	0.02	ACR	
0081	7060000000-E	1705	SIGNAL CABLE	590	LF	
0082	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	6	EA	
0083	7264000000-E	1710	MESSENGER CABLE (3/8")	440	LF	
0084	7360000000-N	1720	WOOD POLE	5	EA	
008E	7372000000-N	1721	GUY ASSEMBLY	7	EA	
008E	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1	EA	
0087	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3	EA	
008E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	420	LF	
0089	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	840	LF	
009C	7636000000-N	1745	SIGN FOR SIGNALS	4	EA	
0091	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1	EA	

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	2		
				EA		

STRUCTURE ITEMS

0093	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (10+87.86-L-)	Lump Sum	L.S.	
0094	8096000000-E	SP	PILE EXCAVATION IN SOIL	80		
				LF		
0095	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	64		
				LF		
0096	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	36		
				CY		
0097	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (10+87.86-L-)	Lump Sum	L.S.	
0098	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,068		
				LB		
0099	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	200		
				LF		
0100	8433000000-E	SP	*** STEEL SHEET PILES (18")	770		
				SF		
0101	8468000000-E	460	ONE BAR METAL RAIL	39.81		
				LF		
0102	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" X 1'-8")	55.34		
				LF		
0103	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0104	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	332.06		
				LF		

Contract No: C201617

County: Cherokee

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General