

County : Granville

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+29.000) | Lump Sum | L.S. | |
| 0003 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0004 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0005 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 200 CY | | |
| 0006 | 0080000000-E | SP | CLASS IV SUBGRADE STABILIZA- TION | 100 TON | | |
| 0007 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 459 CY | | |
| 0008 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 100 CY | | |
| 0009 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 100 SY | | |
| 0010 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 40 TON | | |
| 0011 | 0343000000-E | 310 | 15" SIDE DRAIN PIPE | 24 LF | | |
| 0012 | 0344000000-E | 310 | 18" SIDE DRAIN PIPE | 24 LF | | |
| 0013 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 52 LF | | |
| 0014 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 188 LF | | |
| 0015 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 44 LF | | |
| 0016 | 0714000000-E | 310 | 18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 32 LF | | |
| 0017 | 0806000000-E | 310 | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 2 EA | | |
| 0018 | 0807000000-E | 310 | 18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK | 2 EA | | |

County : Granville

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|---------------|-----------|--------|
| 0019 | 0995000000-E | 340 | PIPE REMOVAL | 40 LF | | |
| 0020 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 50 TON | | |
| 0021 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 1,092 TON | | |
| 0022 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 690 TON | | |
| 0023 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 95 TON | | |
| 0024 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 21 EA | | |
| 0025 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 23 CY | | |
| 0026 | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 17 CY | | |
| 0027 | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 100 LF | | |
| 0028 | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 3 EA | | |
| 0029 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 1 EA | | |
| 0030 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 0031 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 6 EA | | |
| 0032 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 6 EA | | |
| 0033 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 630 LF | | |
| 0034 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 1,062.5 LF | | |
| 0035 | 3045000000-E | 862 | STEEL BM GUARDRAIL, SHOP CURVED | 50 LF | | |
| 0036 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 3 EA | | |
| 0037 | 3195000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE AT-1 | 1 EA | | |

County : Granville

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0038 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 3 EA | | |
| 0039 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 4 EA | | |
| 0040 | 3360000000-E | 863 | REMOVE EXISTING GUARDRAIL | 490 LF | | |
| 0041 | 3649000000-E | 876 | RIP RAP, CLASS B | 4 TON | | |
| 0042 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 544 SY | | |
| 0043 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 2 EA | | |
| 0044 | 4025000000-E | 901 | CONTRACTOR FURNISHED, TYPE *** SIGN (D) | 13.6 SF | | |
| 0045 | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 33 LF | | |
| 0046 | 4096000000-N | 904 | SIGN ERECTION, TYPE D | 2 EA | | |
| 0047 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U-CHANNEL | 12 EA | | |
| 0048 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 394 SF | | |
| 0049 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 94 SF | | |
| 0050 | 4430000000-N | 1130 | DRUMS | 10 EA | | |
| 0051 | 4435000000-N | 1135 | CONES | 10 EA | | |
| 0052 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 80 LF | | |
| 0053 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 12,400 LF | | |
| 0054 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 25 EA | | |
| 0055 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,490 LF | | |

County : Granville

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0056 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 105 TON | | |
| 0057 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 395 TON | | |
| 0058 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 510 TON | | |
| 0059 | 6015000000-E | 1615 | TEMPORARY MULCHING | 3 ACR | | |
| 0060 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 150 LB | | |
| 0061 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.5 TON | | |
| 0062 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 115 LF | | |
| 0063 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 2 EA | | |
| 0064 | 6029000000-E | SP | SAFETY FENCE | 350 LF | | |
| 0065 | 6030000000-E | 1630 | SILT EXCAVATION | 1,690 CY | | |
| 0066 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 1,450 SY | | |
| 0067 | 6037000000-E | SP | COIR FIBER MAT | 10 SY | | |
| 0068 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 80 SY | | |
| 0069 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 560 LF | | |
| 0070 | 6070000000-N | SP | SPECIAL STILLING BASINS | 8 EA | | |
| 0071 | 6071030000-E | SP | COIR FIBER BAFFLES | 280 LF | | |
| 0072 | 6071050000-E | SP | *** SKIMMER (1-1/2") | 1 EA | | |
| 0073 | 6084000000-E | 1660 | SEEDING & MULCHING | 3.5 ACR | | |
| 0074 | 6087000000-E | 1660 | MOWING | 2 ACR | | |

County : Granville

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|-------------------------------|-------------|-----------|--------|
| 0075 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0076 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0077 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 75 LB | | |
| 0078 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 2.5 TON | | |
| 0079 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2 HR | | |
| 0080 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 27 EA | | |
| 0081 | 6123000000-E | 1670 | REFORESTATION | 0.5 ACR | | |

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|-----|---|-------------|------|--|
| 0082 | 8017000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+29.00-L-) | Lump Sum | L.S. | |
| 0083 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+29.00-L-) | Lump Sum | L.S. | |
| 0084 | 8096000000-E | SP | PILE EXCAVATION IN SOIL | 42 LF | | |
| 0085 | 8097000000-E | SP | PILE EXCAVATION NOT IN SOIL | 18 LF | | |
| 0086 | 8105560000-E | SP | 4'-0" DIA DRILLED PIERS IN SO IL | 24 LF | | |
| 0087 | 8105660000-E | SP | 4'-0" DIA DRILLED PIERS NOT IN SOIL | 41 LF | | |
| 0088 | 8113000000-N | SP | SID INSPECTION | 1 EA | | |
| 0089 | 8115000000-N | SP | CROSSHOLE SONIC LOGGING | 2 EA | | |
| 0090 | 8119000000-E | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION | 780 CY | | |
| 0091 | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 8,239 SF | | |

County : Granville

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0092 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 7,597 SF | | |
| 0093 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 160.9 CY | | |
| 0094 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (20+29.00-L-) | Lump Sum | L.S. | |
| 0095 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 28,606 LB | | |
| 0096 | 8238000000-E | 425 | SPIRAL COLUMN REINFORCING STEEL (BRIDGE) | 2,972 LB | | |
| 0097 | 8265000000-E | 430 | 54" PRESTRESSED CONCRETE GIR- DERS | 891.17 LF | | |
| 0098 | 8364000000-E | 450 | HP12X53 STEEL PILES | 430 LF | | |
| 0099 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 454.56 LF | | |
| 0100 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 1,320 TON | | |
| 0101 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 1,465 SY | | |
| 0102 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0103 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |

0949/Jan08/Q79798.98/D460503400000/E103

Total Amount Of Bid For Entire Project :

Contract No: C201585

County: Granville

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General