

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+35.000)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	50 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	188 LF		
0014	0345000000-E	310	24" SIDE DRAIN PIPE	40 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0016	0995000000-E	340	PIPE REMOVAL	148 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	1,056 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	450 TON		
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	250 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	800 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	80 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2264000000-E	840	PIPE PLUGS	0.1 CY		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0032	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1 LF		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0034	2556000000-E	846	SHOULDER BERM GUTTER	23 LF		
0035	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0036	3030000000-E	862	STEEL BM GUARDRAIL	275 LF		
0037	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	150 LF		
0038	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0039	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0040	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0041	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0042	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	275 LF		
0043	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	100 LF		
0044	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	2 EA		
0045	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4 EA		
0046	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0047	3628000000-E	876	RIP RAP, CLASS I	30 TON		
0048	3649000000-E	876	RIP RAP, CLASS B	80 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	425 SY		
0050	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48 SF		
0051	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0052	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	92 SF		
0053	4430000000-N	1130	DRUMS	50 EA		
0054	4435000000-N	1135	CONES	50 EA		
0055	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0056	4450000000-N	1150	FLAGGER	640 HR		
0057	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	136 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	30,048 LF		
0059	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	13 EA		
0060	6000000000-E	1605	TEMPORARY SILT FENCE	3,230 LF		
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105 TON		
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	785 TON		
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	215 TON		
0064	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0065	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0066	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0067	6024000000-E	1622	TEMPORARY SLOPE DRAINS	90 LF		
0068	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
0069	6029000000-E	SP	SAFETY FENCE	300 LF		
0070	6030000000-E	1630	SILT EXCAVATION	2,800 CY		
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	600 SY		
0072	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,385 SY		
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0074	6071030000-E	SP	COIR FIBER BAFFLES	600 LF		
0075	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0076	6087000000-E	1660	MOWING	1 ACR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0078	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0079	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0080	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0081	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0083	6123000000-E	1670	REFORESTATION	0.25 ACR		
STRUCTURE ITEMS						
0084	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (15+35.00-L-)	Lump Sum	L.S.	
0085	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+35.00-L-)	Lump Sum	L.S.	
0086	8096000000-E	SP	PILE EXCAVATION IN SOIL	30 LF		
0087	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	105 LF		
0088	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+35.00-L-)	Lump Sum	L.S.	
0089	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,933 SF		
0090	8161000000-E	420	GROOVING BRIDGE FLOORS	3,986 SF		
0091	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	43.4 CY		
0092	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+35.00-L-)	Lump Sum	L.S.	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,875 LB		
0094	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	120,700 LS		
0095	8364000000-E	450	HP12X53 STEEL PILES	270 LF		
0096	8503000000-E	460	CONCRETE BARRIER RAIL	220 LF		
0097	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	397 TON		
0098	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	441 SY		
0099	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1149/Feb04/Q184027.25/D410984230000/E98

Total Amount Of Bid For Entire Project :