

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	1,500 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	500 TON		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,625 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	200 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	30 TON		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	40 LF		
0012	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	184 LF		
0013	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (90", 0.109")	48 LF		
0014	0995000000-E	340	PIPE REMOVAL	232 LF		
0015	1077000000-E	SP	#57 STONE	30 TON		
0016	1121000000-E	520	AGGREGATE BASE COURSE	416 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	215 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	225 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	24 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	168 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	126 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	750 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	24 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	575 LF		
0028	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0032	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	375 LF		
0033	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0034	3649000000-E	876	RIP RAP, CLASS B	11 TON		
0035	3651000000-E	SP	BOULDERS	85 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	222 SY		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	104 SF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144	SF	
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	56	SF	
0040	4430000000-N	1130	DRUMS	41	EA	
0041	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0042	4450000000-N	1150	FLAGGER	480	HR	
0043	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,736	LF	
0044	6000000000-E	1605	TEMPORARY SILT FENCE	1,050	LF	
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	40	TON	
0046	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	170	TON	
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	140	TON	
0048	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0050	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0051	6029000000-E	SP	SAFETY FENCE	1,200	LF	
0052	6030000000-E	1630	SILT EXCAVATION	600	CY	
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000	SY	
0054	6037000000-E	SP	COIR FIBER MAT	25	SY	
0055	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	185	SY	
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	330	LF	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6069000000-E	1638	STILLING BASINS	35 CY		
0058	6071030000-E	SP	COIR FIBER BAFFLES	180 LF		
0059	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0060	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0061	6087000000-E	1660	MOWING	1 ACR		
0062	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0063	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0064	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0065	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0066	6111000000-E	SP	IMPERVIOUS DIKE	145 LF		
0067	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0068	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0069	6126000000-E	SP	STREAMBANK REFORESTATION	0.3 ACR		
<b>CULVERT ITEMS</b>						
0070	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+65.00-L-)	Lump Sum	L.S.	
0071	8126000000-N	414	CULVERT EXCAVATION, STA ***** (13+65.00-L-)	Lump Sum	L.S.	
0072	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	79 TON		
0073	8196000000-E	420	CLASS A CONCRETE (CULVERT)	133.9 CY		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8245000000-E	425	REINFORCING STEEL (CULVERT)	22,068 LB		

0816/Jan08/Q42970.45/D287103280000/E74

Total Amount Of Bid For Entire Project :

**Contract No: C201618**

**County: Henderson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General