

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1")	12,800 SY		
0003	1330000000-E	607	INCIDENTAL MILLING	22,900 SY		
0004	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	50 TON		
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	17,106 TON		
0006	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	10,454 TON		
0007	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	25,747 TON		
000E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,700 TON		
0009	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	627 TON		
001C	2830000000-N	858	ADJUSTMENT OF MANHOLES	39 EA		
0011	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	14 EA		
0012	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0013	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1 EA		
0014	4480000000-N	1165	TMIA	1 EA		
0015	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	132,607 LF		
0016	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	139,833 LF		
0017	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,550 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	1,930 LF		
001E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	514 LF		
002C	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	145 EA		
0021	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	200 LF		
1019/Jan15/Q370220.0/D67212100000/E21			Total Amount Of Bid For Entire Project :			

Contract No: C201999

County: Johnston

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General