

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+62.50)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	850 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0010	0660000000-E	310	****BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (15", 0.064")	48 LF		
0011	0680000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE A ***** THICK (15", 0.064")	4 EA		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	230 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	215 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
0015	2022000000-E	815	SUBDRAIN EXCAVATION	30 CY		
0016	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0017	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3	EA	
001E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
002C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
0022	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2	EA	
0023	2556000000-E	846	SHOULDER BERM GUTTER	40	LF	
0024	3030000000-E	862	STEEL BM GUARDRAIL	375	LF	
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0027	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
002E	3649000000-E	876	RIP RAP, CLASS B	5	TON	
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	160	SY	
003C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	304	SF	
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114	SF	
0032	4445000000-E	1145	BARRICADES (TYPE III)	136	LF	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	1,050	LF	
0034	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50	TON	

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	35	TON	
0037	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
003E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
003E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
004C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	75	LF	
0041	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0042	6029000000-E	SP	SAFETY FENCE	200	LF	
004E	6030000000-E	1630	SILT EXCAVATION	40	CY	
0044	6036000000-E	1631	MATTING FOR EROSION CONTROL	120	SY	
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	100	LF	
004E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	100	SY	
0047	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	
004E	6087000000-E	1660	MOWING	1	ACR	
004E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
005C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0051	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0052	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0054	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
005E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+62.50-L-)	Lump Sum	L.S.	
005E	8112730000-N	SP	PDA TESTING	1 EA		
0057	8112740000-N	SP	PDA ASSISTANCE	1 EA		
005E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+62.50-L-)	Lump Sum	L.S.	
005E	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	39.8 CY		
006C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+62.50-L-)	Lump Sum	L.S.	
0061	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	5,894 LB		
0062	8364000000-E	450	HP12X53 STEEL PILES	1,040 LF		
0063	8393000000-N	450	PILE REDRIVES	16 EA		
0064	8503000000-E	460	CONCRETE BARRIER RAIL	175.44 LF		
006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	186 TON		
006E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	207 SY		
0067	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
006E	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,052.62 LF		

Contract No: C201549

County: Perquimans

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General