

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+47.000 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	321 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	100 CY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	160 TON		
0011	0345000000-E	310	24" SIDE DRAIN PIPE	288 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	276 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3 EA		
0014	0995000000-E	340	PIPE REMOVAL	18 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	150 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	125 TON		
0017	1245000000-E	SP	SHOULDER RECONSTRUCTION	7 SMI		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,600 TON		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	8,060 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	639 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	70 TON		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	30 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9 EA		
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.3 LF		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0031	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	340 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	400 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0037	3360000000-E	863	REMOVE EXISTING GUARDRAIL	100 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3649000000-E	876	RIP RAP, CLASS B	54 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	219 SY		
0040	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	22 SF		
0041	4082000000-E	903	SUPPORTS, WOOD	54 LF		
0042	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0043	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	5 EA		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,092 SF		
0045	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	288 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	89 SF		
0047	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1 EA		
0048	4430000000-N	1130	DRUMS	160 EA		
0049	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0050	4455000000-N	1150	FLAGGER	45 MD		
0051	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,400 LF		
0052	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	175 LF		
0053	4715000000-E	1205	THERMOPLASTIC RUMBLE STRIP (4" 240 MILS)	230 LF		
0054	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (TYPE 3)	225 LF		
0055	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	227,530 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	720	LF	
0057	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	240	LF	
0058	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	576	LF	
0059	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	12	EA	
0060	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	24	EA	
0061	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	230	LF	
0062	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	12	LF	
0063	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	288	EA	
0064	6000000000-E	1605	TEMPORARY SILT FENCE	850	LF	
0065	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0066	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	135	TON	
0067	6012000000-E	1610	SEDIMENT CONTROL STONE	65	TON	
0068	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0069	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0070	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0071	6024000000-E	1622	TEMPORARY SLOPE DRAINS	90	LF	
0072	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0073	6029000000-E	SP	SAFETY FENCE	300	LF	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6030000000-E	1630	SILT EXCAVATION	210	CY	
0075	6036000000-E	1631	MATTING FOR EROSION CONTROL	175	SY	
0076	6042000000-E	1632	1/4" HARDWARE CLOTH	150	LF	
0077	6084000000-E	1660	SEEDING & MULCHING	2	ACR	
0078	6087000000-E	1660	MOWING	1.5	ACR	
0079	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0080	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5	TON	
0083	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0084	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0085	6123000000-E	1670	REFORESTATION	0.1	ACR	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0086	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	592	LF	
AA1						
0087	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	352	LF	
AA1						

*** OR ***

0088	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	592	LF	
AA2						
0089	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	352	LF	
AA2						

*** OR ***

0090	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	592	LF	
AA3						

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	352 LF		

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0092	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+47.00-L-)	Lump Sum	L.S.	
0093	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0094	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22+47.00-L-)	Lump Sum	L.S.	
0095	8156000000-E	SP	CONCRETE WEARING SURFACE	3,178 SF		
0096	8161000000-E	420	GROOVING BRIDGE FLOORS	4,322 SF		
0097	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	39.4 CY		
0098	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+47.00-L-)	Lump Sum	L.S.	
0099	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,830 LB		
0100	8364000000-E	450	HP12X53 STEEL PILES	1,150 LF		
0101	8393000000-N	450	PILE REDRIVES	8 EA		
0102	8503000000-E	460	CONCRETE BARRIER RAIL	195.44 LF		
0103	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	272 TON		
0104	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	302 SY		
0105	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0106	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,172.63 LF		

1319/Jan03/Q270513.37/D441062440000/E107

Total Amount Of Bid For Entire Project :

Contract No: C201587

County: Pitt

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General