

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+42.500 -L-)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+04.010 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	490 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	700 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	25 TON		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	60 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0014	0995000000-E	340	PIPE REMOVAL	60 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,080 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	300 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	755 TON		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	110 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	26 EA		
0022	2264000000-E	840	PIPE PLUGS	0.13 CY		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0024	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3.7 LF		
0025	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0026	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	46 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	775 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0030	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0032	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0033	3566000000-E	867	WOVEN WIRE FENCE RESET	700 LF		
0034	3649000000-E	876	RIP RAP, CLASS B	103 TON		
0035	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,212 SY		
0036	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0039	4450000000-N	1150	FLAGGER	100 HR		
0040	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,836 LF		
0041	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,836 LF		
0042	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	28 EA		
0043	5709600000-E	1520	12" FORCE MAIN SEWER	67 LF		
0044	5804000000-E	1530	ABANDON 12" UTILITY PIPE	177 LF		
0045	6000000000-E	1605	TEMPORARY SILT FENCE	2,195 LF		
0046	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	365 TON		
0048	6012000000-E	1610	SEDIMENT CONTROL STONE	315 TON		
0049	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0050	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0052	6024000000-E	1622	TEMPORARY SLOPE DRAINS	45 LF		
0053	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0054	6029000000-E	SP	SAFETY FENCE	500 LF		
0055	6030000000-E	1630	SILT EXCAVATION	1,595 CY		
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,600 SY		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6037000000-E	SP	COIR FIBER MAT	15	SY	
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	140	SY	
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	40	LF	
0060	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
0061	6071030000-E	SP	COIR FIBER BAFFLES	530	LF	
0062	6071050000-E	SP	*** SKIMMER (2")	2	EA	
0063	6084000000-E	1660	SEEDING & MULCHING	7.5	ACR	
0064	6087000000-E	1660	MOWING	3	ACR	
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125	LB	
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5	TON	
0069	6114000000-N	SP	SPECIALIZED HAND MOWING	4	HR	
0070	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24	EA	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0071	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	8	LF	
AA1						
0072	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	28	LF	
AA1						
0073	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	12	LF	
AA1						

*** OR ***

0074	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	8	LF	
AA2						

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	28 LF		
0076 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	12 LF		
*** OR ***						
0077 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	8 LF		
0078 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	28 LF		
0079 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (36". 0.064")	12 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0080	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+42.50-L-)	Lump Sum	L.S.	
0081	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+42.50-L-)	Lump Sum	L.S.	
0082	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+04.00-L-)	Lump Sum	L.S.	
0083	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	134.7 LF		
0084	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	15.8 LF		
0085	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	58.7 LF		
0086	8113000000-N	SP	SID INSPECTION	2 EA		
0087	8114000000-N	SP	SPT TESTING	4 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0089	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+42.50-L-)	Lump Sum	L.S.	
0090	8156000000-E	SP	CONCRETE WEARING SURFACE	4,100 SF		
0091	8161000000-E	420	GROOVING BRIDGE FLOORS	5,123 SF		
0092	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	114.1 CY		
0093	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+42.50-L-)	Lump Sum	L.S.	
0094	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+04.00-L-)	Lump Sum	L.S.	
0095	8217000000-E	425	REINFORCING STEEL (BRIDGE)	28,630 LB		
0096	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,154 LB		
0097	8364000000-E	450	HP12X53 STEEL PILES	690 LF		
0098	8391000000-N	450	STEEL PILE POINTS	7 EA		
0099	8475000000-E	460	TWO BAR METAL RAIL	228.46 LF		
0100	8503000000-E	460	CONCRETE BARRIER RAIL	188.25 LF		
0101	8517000000-E	460	1'-**X ***** CONCRETE PARAPET (1'-2" X 2'-11")	244.8 LF		
0102	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	540 TON		
0103	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	594 SY		
0104	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0105	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,128 LF		
0107	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,465.38 LF		

1015/Jan04/Q70132.77/D492965320000/E107

Total Amount Of Bid For Entire Project :

Contract No: C201772

County: Randolph

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General