

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+00.000)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	60 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0014	1121000000-E	520	AGGREGATE BASE COURSE	35 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	225 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	220 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	490 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	45 TON		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	84 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	962.5 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0031	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0032	3628000000-E	876	RIP RAP, CLASS I	15 TON		
0033	3649000000-E	876	RIP RAP, CLASS B	75 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	310 SY		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	406 SF		
0036	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0037	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,600 LF		
0039	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	12 EA		
0040	6000000000-E	1605	TEMPORARY SILT FENCE	355 LF		
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	70 TON		
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	75 TON		
0044	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0045	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0046	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	25 LF		
0048	6029000000-E	SP	SAFETY FENCE	250 LF		
0049	6030000000-E	1630	SILT EXCAVATION	330 CY		
0050	6036000000-E	1631	MATTING FOR EROSION CONTROL	800 SY		
0051	6037000000-E	SP	COIR FIBER MAT	25 SY		
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	185 LF		
0053	6071030000-E	SP	COIR FIBER BAFFLES	105 LF		
0054	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0055	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0056	6087000000-E	1660	MOWING	0.5 ACR		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0058	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0059	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0060	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0061	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0062	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0063	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+00.00-L-)	Lump Sum	L.S.	
0064	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+00.00-L-)	Lump Sum	L.S.	
0065	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	50.4 CY		
0066	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+00.00-L-)	Lump Sum	L.S.	
0067	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,420 LB		
0068	8364000000-E	450	HP12X53 STEEL PILES	400 LF		
0069	8503000000-E	460	CONCRETE BARRIER RAIL	195.33 LF		
0070	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	170 TON		
0071	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	189 SY		
0072	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,074.33 LF		

0813/Jan08/Q24439.81/D307660380000/E73

Total Amount Of Bid For Entire Project :

Contract No: C201773

County: Rockingham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General