

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+92.50 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,400 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	325 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	76 CY		
0008	0141000000-E	240	BERM DITCH CONSTRUCTION	215 LF		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	70 TON		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	68 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	192 LF		
0014	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	72 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0016	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0017	1121000000-E	520	AGGREGATE BASE COURSE	1,056 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1275000000-E	600	PRIME COAT	750 GAL		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	45 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	340 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	24 EA		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	67.2 CY		
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	50.4 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0028	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0029	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0030	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0032	2354200000-N	840	FRAME WITH GRATE, STD 840.24	4 EA		
0033	2355000000-N	840	FRAME WITH GRATE, STD 840.29	1 EA		
0034	2556000000-E	846	SHOULDER BERM GUTTER	50 LF		
0035	2619000000-E	850	4" CONCRETE PAVED DITCH	22 SY		
0036	3030000000-E	862	STEEL BM GUARDRAIL	200 LF		
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0039	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	2 EA		
0040	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0041	3628000000-E	876	RIP RAP, CLASS I	15 TON		
0042	3649000000-E	876	RIP RAP, CLASS B	35 TON		
0043	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	395 SY		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	225 SF		
0045	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	58 SF		
0047	4430000000-N	1130	DRUMS	80 EA		
0048	4435000000-N	1135	CONES	25 EA		
0049	4445000000-E	1145	BARRICADES (TYPE III)	100 LF		
0050	4455000000-N	1150	FLAGGER	100 MD		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,100 LF		
0052	6000000000-E	1605	TEMPORARY SILT FENCE	1,010 LF		
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	175 TON		
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	385 TON		
0055	6012000000-E	1610	SEDIMENT CONTROL STONE	275 TON		
0056	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0058	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0059	6024000000-E	1622	TEMPORARY SLOPE DRAINS	45 LF		
0060	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0061	6029000000-E	SP	SAFETY FENCE	250 LF		
0062	6030000000-E	1630	SILT EXCAVATION	1,460 CY		
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0064	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	385 SY		
0065	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0066	6071030000-E	SP	COIR FIBER BAFFLES	330 LF		
0067	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0068	6087000000-E	1660	MOWING	1 ACR		
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0073	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0074	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0075	6123000000-E	1670	REFORESTATION	0.2 ACR		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0076 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	328 LF		
0077 AA1	0528000000-E	310	*** RC PIPE ELBOWS, CLASS III (15")	1 EA		
*** OR ***						
0078 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	328 LF		
0079 AA2	0992000000-E	SP	GENERIC PIPE ITEM 15" HDPE PIPE ELBOW	1 EA		
*** OR ***						
0080 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	328 LF		
0081 AA3	0992000000-E	SP	GENERIC PIPE ITEM 15" ALUM CORR STL PIPE ELBOW	1 EA		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0082	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+92.50-L-)	Lump Sum	L.S.	
0083	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+92.50-L-)	Lump Sum	L.S.	
0084	8105500000-E	SP	***-*** DIA DRILLED PIERS IN SOIL (4'-6")	29 LF		
0085	8105600000-E	SP	***-*** DIA DRILLED PIERS NOT IN SOIL (4'-6")	19 LF		
0086	8111000000-E	SP	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6")	32 LF		
0087	8113000000-N	SP	SID INSPECTION	1 EA		
0088	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	9,533 SF		
0090	8161000000-E	420	GROOVING BRIDGE FLOORS	8,497 SF		
0091	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	74.9 CY		
0092	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+92.50-L-)	Lump Sum	L.S.	
0093	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,784 LB		
0094	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,349 LB		
0095	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	390,635 LS		
0096	8364000000-E	450	HP12X53 STEEL PILES	430 LF		
0097	8503000000-E	460	CONCRETE BARRIER RAIL	556.73 LF		
0098	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	577 TON		
0099	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	643 SY		
0100	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0101	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0102	8860000000-N	SP	GENERIC STRUCTURE ITEM DISPOSAL OF THE TRUSS	Lump Sum	L.S.	

1605/Jan08/Q457835.93/D427369430000/E102

Total Amount Of Bid For Entire Project :

Contract No: C201729

County: Rutherford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General