

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+77.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	800 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	150 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0011	0995000000-E	340	PIPE REMOVAL	52 LF		
0012	1121000000-E	520	AGGREGATE BASE COURSE	54 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	290 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	190 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	280 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	90 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	70 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	400 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	12 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	38 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	231.25 LF		
0029	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	43.75 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0034	3628000000-E	876	RIP RAP, CLASS I	185 TON		
0035	3649000000-E	876	RIP RAP, CLASS B	16 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	860 SY		
0037	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	11.25 SF		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	27 LF		
0039	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0040	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	10 EA		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	302 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0043	4430000000-N	1130	DRUMS	10 EA		
0044	4435000000-N	1135	CONES	10 EA		
0045	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0046	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,560 LF		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	350 LF		
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	280 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	65 LF		
0055	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0056	6029000000-E	SP	SAFETY FENCE	285 LF		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6030000000-E	1630	SILT EXCAVATION	940	CY	
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,200	SY	
0059	6037000000-E	SP	COIR FIBER MAT	45	SY	
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	50	LF	
0061	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
0062	6071030000-E	SP	COIR FIBER BAFFLES	300	LF	
0063	6071050000-E	SP	*** SKIMMER (1-1/2")	4	EA	
0064	6071050000-E	SP	*** SKIMMER (2-1/2")	1	EA	
0065	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	
0066	6087000000-E	1660	MOWING	1	ACR	
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0069	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0070	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
0071	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0073	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	204	LF	
AA1						
0074	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	120	LF	
AA1						

*** OR ***

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0076 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48 LF		
0077 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	172 LF		
0078 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	72 LF		
*** OR ***						
0079 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0080 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48 LF		
0081 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	172 LF		
0082 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	72 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0083	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+77.50-L-)	Lump Sum	L.S.	
0084	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	31.5 LF		
0085	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	28 LF		
0086	8113000000-N	SP	SID INSPECTION	1 EA		
0087	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0088	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	530 CY		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,531 SF		
0090	8161000000-E	420	GROOVING BRIDGE FLOORS	5,709 SF		
0091	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	77.6 CY		
0092	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+77.50-L-)	Lump Sum	L.S.	
0093	8217000000-E	425	REINFORCING STEEL (BRIDGE)	19,031 LB		
0094	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,976 LB		
0095	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	707.09 LF		
0096	8364000000-E	450	HP12X53 STEEL PILES	265 LF		
0097	8475000000-E	460	TWO BAR METAL RAIL	271.67 LF		
0098	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2"x2'-6")	286.67 LF		
0099	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	370 TON		
0100	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	412 SY		
0101	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0102	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1027/Feb27/Q51918.53/D432824410000/E102

Total Amount Of Bid For Entire Project :

Contract No: C201811

County: Alamance

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General