

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+37.40)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (2+06.37)	Lump Sum	L.S.	
0004	0199000000-E	SP	TEMPORARY SHORING	980 SF		
0005	0248000000-N	SP	GENERIC GRADING ITEM EXCAVATION & EMBANKMENT	Lump Sum	L.S.	
0006	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0007	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	10 LF		
0008	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	45 LF		
0009	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	44 LF		
0010	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	40 LF		
0011	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (18", 0.064")	2 EA		
0012	1220000000-E	545	INCIDENTAL STONE BASE	10 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,100 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	957 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	79 TON		
0016	2154000000-N	820	METAL FUNNELS	1 EA		
0017	2165000000-E	820	12" FUNNEL DRAIN PIPE	30 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2176000000-E	820	12" FUNNEL DRAIN PIPE ELBOWS	2 EA		
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0020	2355000000-N	840	FRAME WITH GRATE, STD 840.29	3 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	250 LF		
0023	3030000000-E	862	STEEL BM GUARDRAIL	543.75 LF		
0024	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	265 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-83, SHOP CURVED)	1 EA		
0027	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0028	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
0030	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0031	3319000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-83	3 EA		
0032	3628000000-E	876	RIP RAP, CLASS I	180 TON		
0033	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	338 SF		
0034	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	32 SF		
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	156 SF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4430000000-N	1130	DRUMS	120 EA		
0037	4445000000-E	1145	BARRICADES (TYPE III)	88 LF		
0038	4450000000-N	1150	FLAGGER	650 HR		
0039	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0040	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0041	4485000000-E	1170	PORTABLE CONCRETE BARRIER	170 LF		
0042	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	80 LF		
0043	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	174 EA		
0044	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,220 LF		
0045	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,239 LF		
0046	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	48 LF		
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,500 LF		
0048	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	75 LF		
0049	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	4,000 LF		
0050	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	14 EA		
0051	4957000000-N	1264	OBJECT MARKERS (TYPE **) (III)	2 EA		
0052	6000000000-E	1605	TEMPORARY SILT FENCE	2,350 LF		
0053	6133000000-N	SP	GENERIC EROSION CONTROL ITEM EROSION CONTROL	Lump Sum	L.S.	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	7060000000-E	1705	SIGNAL CABLE	875 LF		
0055	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	6 EA		
0056	7252000000-E	1710	MESSENGER CABLE (1/4")	640 LF		
0057	7264000000-E	1710	MESSENGER CABLE (3/8")	225 LF		
0058	7360000000-N	1720	WOOD POLE	6 EA		
0059	7372000000-N	1721	GUY ASSEMBLY	9 EA		
0060	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0061	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3 EA		
0062	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	530 LF		
0063	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	860 LF		
0064	7636000000-N	1745	SIGN FOR SIGNALS	5 EA		
0065	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0066	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	3 EA		
0067	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+37.40)	Lump Sum	L.S.	
0068	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (2+06.37)	Lump Sum	L.S.	
0069	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (6+68.10)	Lump Sum	L.S.	
0070	8096000000-E	SP	PILE EXCAVATION IN SOIL	53 LF		
0071	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	53 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,567 SF		
0073	8156000000-E	SP	CONCRETE WEARING SURFACE	3,869 SF		
0074	8161000000-E	420	GROOVING BRIDGE FLOORS	6,260 SF		
0075	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+37.40)	Lump Sum	L.S.	
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (2+06.37)	Lump Sum	L.S.	
0077	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	106,100 LS		
0078	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	586 LF		
0079	8391000000-N	450	STEEL PILE POINTS	16 EA		
0080	8475000000-E	460	TWO BAR METAL RAIL	144 LF		
0081	8503000000-E	460	CONCRETE BARRIER RAIL	235.83 LF		
0082	8517000000-E	460	1'***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	160 LF		
0083	8594000000-E	876	RIP RAP, CLASS B	4 TON		
0084	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	500 TON		
0085	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0086	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0087	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,040 LF		
0088	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	
0717/Apr08/Q153621.58/D446138200000/E89			Total Amount Of Bid For Entire Project :			

Contract No **C202012**

County (ies): **Buncombe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

