

County : Chowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	9,925 CY		
0004	0106000000-E	230	BORROW EXCAVATION	2,220 CY		
000E	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	80 SY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	950 TON		
0007	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	12 LF		
000E	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	88 LF		
0009	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	124 LF		
001C	0995000000-E	340	PIPE REMOVAL	3,966 LF		
0011	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0012	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	25,700 SY		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.OB	3,600 TON		
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.OB	4,640 TON		
001E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,720 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	540 TON		

County : Chowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	150 TON		
001E	2209000000-E	838	ENDWALLS	22 CY		
002C	2253000000-E	840	PIPE COLLARS	5.7 CY		
0021	2264000000-E	840	PIPE PLUGS	0.23 CY		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	49 EA		
0023	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2.4 LF		
0024	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	23 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	7 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	6 EA		
0027	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	10 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
002E	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
003C	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	130 LF		
0031	2535000000-E	846	***X *** CONCRETE CURB (9" X 18")	700 LF		
0032	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	2,620 LF		
0033	2612000000-E	848	6" CONCRETE DRIVEWAY	370 SY		
0034	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	40 SY		

County : Chowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3649000000-E	876	RIP RAP, CLASS B	157 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	724 SY		
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	12,414 LF		
003E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	19,389 LF		
003E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	45 LF		
004C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	43 EA		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	31,803 LF		
0042	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	45 LF		
0043	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	43 EA		
0044	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	200 EA		
004E	5325600000-E	1510	6" WATER LINE	197 LF		
004E	5326200000-E	1510	12" WATER LINE	7,515 LF		
0047	5538000000-E	1515	4" VALVE	2 EA		
004E	5540000000-E	1515	6" VALVE	1 EA		
004E	5558000000-E	1515	12" VALVE	6 EA		
005C	5572000000-E	1515	10" TAPPING VALVE	2 EA		
0051	5648000000-N	1515	RELOCATE WATER METER	33 EA		
0052	5649000000-N	1515	RECONNECT WATER METER	4 EA		

County : Chowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	5672000000-N	1515	RELOCATE FIRE HYDRANT	5	EA	
0054	5678000000-E	1515	*** LINE STOP (10")	2	EA	
005E	5709300000-E	1520	6" FORCE MAIN SEWER	1,852	LF	
005E	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	55	LF	
0057	5872200000-E	1550	TRENCHLESS INSTALLATION OF 24" IN SOIL	40	LF	
005E	5882000000-N	SP	GENERIC UTILITY ITEM 2" AIR & VACCUUM RELEASE VALVE WITH 4' PRECAST MANHOLE	1	EA	
005E	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER, 1" & RPZ	1	EA	
006C	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER, 1"	7	EA	
0061	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER, 2"	3	EA	
0062	6000000000-E	1605	TEMPORARY SILT FENCE	705	LF	
0063	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	505	TON	
0064	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	410	TON	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	520	TON	
006E	6015000000-E	1615	TEMPORARY MULCHING	10	ACR	
0067	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	350	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5	TON	

County : Chowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6030000000-E	1630	SILT EXCAVATION	910	CY	
0070	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,485	SY	
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	340	LF	
0072	6084000000-E	1660	SEEDING & MULCHING	9.5	ACR	
0073	6087000000-E	1660	MOWING	6	ACR	
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	250	LB	
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	7	TON	
0078	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0079	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

***** BEGIN SCHEDULE AA *****
 ***** (2 ALTERNATES) *****

0080	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,188	LF	
AA1						
0081	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,532	LF	
AA1						
0082	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	484	LF	
AA1						
*** OR ***						
0083	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,058	LF	
AA2						
0084	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,396	LF	
AA2						
0085	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	424	LF	
AA2						

County : Chowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E AA2	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (15", 0.060")	1,130	LF	
0087 AA2	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (18", 0.060")	136	LF	
008E AA2	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (24", 0.075")	60	LF	

***** END SCHEDULE AA *****

0845/Mar17/Q149426.58/D307302100000/E88

Total Amount Of Bid For Entire Project :

Contract No **C202000**

County (ies): **Chowan**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General