



SYMBOL DESCRIPTION		PAY ITEM/ QUANTITY BREAKDOWN		QUANTITY TOTAL	
PAVEMENT MARKING LINES					
PAINT (4")					
PA	WHITE EDGELINE	10,403	FT.		
PD	MINI SKIP	20	FT.		
PI	YELLOW DOUBLE CENTER LINE	3968	FT.	TOTAL	14,391 FT.
PAINT (24")					
P4	STOPBARS	82	FT.	TOTAL	82 FT.
COLD APPLIED PLASTIC (TYPE IV REMOVABLE TAPE)					
CA-IV	WHITE EDGELINE	414	FT.		
CI-IV	YELLOW DOUBLE CENTER LINE	414	FT.	TOTAL	828 FT.
THERMOPLASTIC (4", 90 MILS)					
TA	WHITE EDGELINE	2070	FT.	TOTAL	2070 FT.
THERMOPLASTIC (4", 120 MILS)					
TI	YELLOW DOUBLE CENTER LINE	1820	FT.		
TD	MINI SKIP	7	FT.	TOTAL	1827 FT.
THERMOPLASTIC (24", 120 MILS)					
T2	STOPBARS	10	FT.	TOTAL	10 FT.
COLD APPLIED PLASTIC (TYPE 1)					
CA-I	WHITE EDGELINE	414	FT.		
CI-I	YELLOW DOUBLE CENTER LINE	414	FT.	TOTAL	828 FT.
PAVEMENT MARKERS					
TEMPORARY RAISED					
MH	CRYSTAL & CRYSTAL	220	EA.	TOTAL	220 EA.

16-MAY-2007 07:57
 \\dot\dfs\root0\p\proj\proj\B4103\TrafficControl\top\B-4103_TCP_-TC-8.dgn
 Jrspeice AT WZTC2424

APPROVED:	DATE: 12/06	FINAL PAVEMENT MARKING PLAN AND PAVEMENT MARKING SCHEDULE							
	SCALE: NONE								
	DATE: 12/06								
	DWG. BY: JS								
	DESIGN BY: JS								
REVIEWED BY: JWG		<table border="1"> <tr> <th colspan="2">REVISIONS</th> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </table>		REVISIONS					
REVISIONS									