

County : Greens, Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	24.4	SMI	
0003	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	12,177	TON	
0004	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	6,362	TON	
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	18,914	TON	
0006	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,957	TON	
0007	2830000000-N	858	ADJUSTMENT OF MANHOLES	2	EA	
0008	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2	EA	
0009	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	131,272	LF	
0010	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	80,820	LF	
0011	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	450	LF	
0012	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	14	EA	
0013	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	41	EA	
0014	6084000000-E	1660	SEEDING & MULCHING	30	ACR	

1411/Mar03/Q252066.4/D42597100000/E14

Total Amount Of Bid For Entire Project :

Contract No **C202051**

County (ies): **Greene & Lenoir**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General