

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26 + 50.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	750 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0106000000-E	230	BORROW EXCAVATION	23,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	180 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	700 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	158 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0014	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	96 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	104 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0017	0995000000-E	340	PIPE REMOVAL	289 LF		
0018	1220000000-E	545	INCIDENTAL STONE BASE	225 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,600	TON	
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,575	TON	
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,350	TON	
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	375	TON	
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	53	TON	
0024	2000000000-N	806	RIGHT OF WAY MARKERS	12	EA	
0025	2022000000-E	815	SUBDRAIN EXCAVATION	90	CY	
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	68	CY	
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	400	LF	
0028	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	12	EA	
0029	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0030	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0031	2220000000-E	838	REINFORCED ENDWALLS	5.9	CY	
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	14	EA	
0033	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	4	EA	
0034	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4	EA	
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
0037	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4 EA		
003E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,130 LF		
003E	2556000000-E	846	SHOULDER BERM GUTTER	218 LF		
004C	2612000000-E	848	6" CONCRETE DRIVEWAY	20 SY		
0041	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	3 EA		
0042	3030000000-E	862	STEEL BM GUARDRAIL	775 LF		
004E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0044	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
004E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
004E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
0047	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	62.5 LF		
004E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III MOD)	2 EA		
004E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
005C	3628000000-E	876	RIP RAP, CLASS I	110 TON		
0051	3635000000-E	876	RIP RAP, CLASS II	375 TON		
0052	3649000000-E	876	RIP RAP, CLASS B	159 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,425	SY	
0054	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2	EA	
005E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	32	SF	
005E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	47.75	SF	
0057	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	176	LF	
005E	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
005E	4102000000-N	904	SIGN ERECTION, TYPE E	8	EA	
006C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	13	EA	
0061	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	458	SF	
0062	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	208	SF	
0063	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	184	SF	
0064	4430000000-N	1130	DRUMS	60	EA	
006E	4435000000-N	1135	CONES	40	EA	
006E	4445000000-E	1145	BARRICADES (TYPE III)	112	LF	
0067	4455000000-N	1150	FLAGGER	120	MD	
006E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	40	EA	
006E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,200	LF	
007C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	6,915	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	200	LF	
0072	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	30	LF	
0073	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8	EA	
0074	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,000	LF	
0075	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	800	LF	
0076	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (III)	60	LF	
0077	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	46,270	LF	
0078	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	400	LF	
0079	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	120	LF	
0080	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	16	EA	
0081	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	200	LF	
0082	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	70	EA	
0083	5326200000-E	1510	12" WATER LINE	40	LF	
0084	5672000000-N	1515	RELOCATE FIRE HYDRANT	2	EA	
0085	5691900000-E	1520	24" SANITARY GRAVITY SEWER	171	LF	
0086	5776000000-E	1525	5' DIA UTILITY MANHOLE	2	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	4 LF		
008E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	25 LF		
008E	5813000000-E	1530	ABANDON 24" UTILITY PIPE	81 LF		
009C	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		
0091	6000000000-E	1605	TEMPORARY SILT FENCE	1,870 LF		
0092	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	165 TON		
0093	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	515 TON		
0094	6012000000-E	1610	SEDIMENT CONTROL STONE	525 TON		
009E	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
009E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0097	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
009E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
009E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
010C	6029000000-E	SP	SAFETY FENCE	500 LF		
0101	6030000000-E	1630	SILT EXCAVATION	1,370 CY		
0102	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,415 SY		
0103	6037000000-E	SP	COIR FIBER MAT	15 SY		
0104	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,110 SY		
010E	6042000000-E	1632	1/4" HARDWARE CLOTH	300 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	6070000000-N	SP	SPECIAL STILLING BASINS	12	EA	
0107	6071030000-E	SP	COIR FIBER BAFFLES	270	LF	
010E	6071050000-E	SP	*** SKIMMER (2")	1	EA	
010E	6071050000-E	SP	*** SKIMMER (2-1/2")	1	EA	
011C	6084000000-E	1660	SEEDING & MULCHING	6.5	ACR	
0111	6087000000-E	1660	MOWING	3	ACR	
0112	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0113	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0114	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125	LB	
011E	6108000000-E	1665	FERTILIZER TOPDRESSING	4.75	TON	
011E	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0117	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	
011E	6123000000-E	1670	REFORESTATION	0.1	ACR	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

011E AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	840	LF	
012C AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	248	LF	
0121 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	52	LF	

*** OR ***

0122 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	548	LF	
-------------	--------------	-----	---------------------------------	-----	----	--

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	292 LF		
0124 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	248 LF		
0125 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	52 LF		
*** OR ***						
0126 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	548 LF		
0127 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	292 LF		
0128 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	248 LF		
0129 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	52 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
013C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26 + 50.00-L-)	Lump Sum	L.S.	
0131	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	111.75 LF		
0132	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	32 LF		
0133	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	56.76 LF		
0134	8113000000-N	SP	SID INSPECTION	2 EA		
0135	8114000000-N	SP	SPT TESTING	6 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0136	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0137	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,075 CY		
0138	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,455 SF		
0139	8161000000-E	420	GROOVING BRIDGE FLOORS	8,322 SF		
0140	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	145.6 CY		
0141	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26 + 50.00-L)	Lump Sum	L.S.	
0142	8217000000-E	425	REINFORCING STEEL (BRIDGE)	29,867 LB		
0143	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,069 LB		
0144	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	988.25 LF		
0145	8364000000-E	450	HP12X53 STEEL PILES	450 LF		
0146	8482000000-E	460	THREE BAR METAL RAIL	159.49 LF		
0147	8503000000-E	460	CONCRETE BARRIER RAIL	167.7 LF		
0148	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,108 TON		
0149	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,230 SY		
0150	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0151	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0904/Feb28/Q171875.05/D628730010000/E151

Total Amount Of Bid For Entire Project :

Contract No: C201472

County: Wake

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General