

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0003	0106000000-E	230	BORROW EXCAVATION	400 CY		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	21 TON		
0005	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	40 LF		
0006	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (18", 0.060")	50 LF		
0007	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (24", 0.079")	110 LF		
0008	1220000000-E	545	INCIDENTAL STONE BASE	252 TON		
0009	1245000000-E	SP	SHOULDER RECONSTRUCTION	13.5 SMI		
0010	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	49,279 SY		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,685 TON		
0012	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	8,690 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	8,284 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	2,114 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,201 TON		
0016	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	26 TON		
0017	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (AGGREGATE BASE COURSE)	1,784 TON		

County : Washington

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (ASPHALT)	789 TON		
0019	1891000000-E	SP	GENERIC PAVING ITEM ASPHALT INTERLAYER REINFORCING SYSTEM	44,270 SY		
0020	1891000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (GEOGRID REINFORCEMENT MATER- IAL)	3,491 SY		
0021	1891000000-E	SP	GENERIC PAVING ITEM VARIABLE DEPTH MILLING (0" TO 6")	40,245 SY		
0022	2612000000-E	848	6" CONCRETE DRIVEWAY	15 SY		
0023	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0024	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0025	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	229,613 LF		
0026	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	452 EA		
0027	6000000000-E	1605	TEMPORARY SILT FENCE	2,499 LF		
0028	6012000000-E	1610	SEDIMENT CONTROL STONE	10 TON		
0029	6036000000-E	1631	MATTING FOR EROSION CONTROL	370 SY		
0030	6084000000-E	1660	SEEDING & MULCHING	8.01 ACR		
0031	1702000000-E	657	SEALING EXISTING PAVEMENT CRACKS & JOINTS	8,000 LB		

0721/Apr03/Q405720.51/D69080100000/E31

Total Amount Of Bid For Entire Project :

Contract No **C201095**

County (ies): **Washington**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)