

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+21 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0011	0804000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE B ***** THICK (15", 0.064")	1 EA		
0012	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	130 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	75 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	215 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0020	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0021	2355000000-N	840	FRAME WITH GRATE, STD 840.29	3 EA		
0022	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	145 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0028	3628000000-E	876	RIP RAP, CLASS I	190 TON		
0029	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	630 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	415 SF		
0032	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	112 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0034	4430000000-N	1130	DRUMS	15 EA		
0035	4435000000-N	1135	CONES	15 EA		
0036	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0037	4450000000-N	1150	FLAGGER	80 HR		
0038	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,050 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,050	LF	
0040	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	80	LF	
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,200	LF	
0042	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	160	LF	
0043	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10	EA	
0044	5326600000-E	1510	16" WATER LINE	408	LF	
0045	5558600000-E	1515	16" VALVE	1	EA	
0046	5666000000-E	1515	FIRE HYDRANT	1	EA	
0047	5691400000-E	1520	10" SANITARY GRAVITY SEWER	704	LF	
0048	5775000000-E	1525	4' DIA UTILITY MANHOLE	3	EA	
0049	5871900000-E	1550	TRENCHLESS INSTALLATION OF 16" IN SOIL	80	LF	
0050	5871910000-E	1550	TRENCHLESS INSTALLATION OF 16" NOT IN SOIL	80	LF	
0051	5882000000-N	SP	GENERIC UTILITY ITEM 20" STEEL ENCASEMENT PIPE, 0.500" THICK & CONC COLLARS	1	EA	
0052	5882000000-N	SP	GENERIC UTILITY ITEM 4' DIA PC CONC SEWER MANHOLE WITH A FLAT TOP, 0-6' DEPTH	1	EA	
0053	5882000000-N	SP	GENERIC UTILITY ITEM 4' DIA PC CONC SEWER MANHOLE WITH FLAT TOP & VENT, 0-6' DEPTH	1	EA	
0054	5888000000-E	SP	GENERIC UTILITY ITEM UTILITY MANHOLE WALL, 4' DIA	25	LF	
0055	6000000000-E	1605	TEMPORARY SILT FENCE	960	LF	

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	170 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0062	6029000000-E	SP	SAFETY FENCE	200 LF		
0063	6030000000-E	1630	SILT EXCAVATION	130 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	240 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0066	6070000000-N	SP	SPECIAL STILLING BASINS	6 EA		
0067	6071030000-E	SP	COIR FIBER BAFFLES	30 LF		
0068	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0069	6087000000-E	1660	MOWING	0.5 ACR		
0070	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0075	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	7060000000-E	1705	SIGNAL CABLE	540 LF		
0077	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	9 EA		
0078	7252000000-E	1710	MESSENGER CABLE (1/4")	2,700 LF		
0079	7264000000-E	1710	MESSENGER CABLE (3/8")	340 LF		
0080	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	10 LF		
0081	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	380 LF		
0082	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6 EA		
0083	7360000000-N	1720	WOOD POLE	3 EA		
0084	7372000000-N	1721	GUY ASSEMBLY	17 EA		
0085	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0086	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0087	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1 EA		
0088	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	400 LF		
0089	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	1,110 LF		
0090	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	2,920 LF		
0091	7552000000-N	1731	INTERCONNECT CENTER	1 EA		
0092	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	1 EA		
0093	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORATION KIT	1 EA		
0094	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIVER	1 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	
0096	7720000000-N	1751	CONTROLLER WITH CABINET (TYPE 170E, BASE MOUNTED)	1	EA	
0097	7744000000-N	1751	DETECTOR CARD (TYPE 170)	3	EA	
0098	7901010000-N	1753	CABINET BASE ADAPTER	1	EA	

***** BEGIN SCHEDULE AA *****
 ***** (4 ALTERNATES) *****

0099 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	216	LF	
*** OR ***						
0100 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	200	LF	
0101 AA2	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	16	LF	
*** OR ***						
0102 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	200	LF	
0103 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	16	LF	
*** OR ***						
0104 AA4	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	200	LF	
0105 AA4	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	16	LF	

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0106	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+21.00-L-)	Lump Sum	L.S.	
------	--------------	----	---	----------	------	--

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+21.00-L-)	Lump Sum	L.S.	
0108	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	59 LF		
0109	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	25 LF		
0110	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	54 LF		
0111	8113000000-N	SP	SID INSPECTION	1 EA		
0112	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0113	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+21.00-L-)	Lump Sum	L.S.	
0114	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	61.8 CY		
0115	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+21.00-L-)	Lump Sum	L.S.	
0116	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,493 LB		
0117	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,203 LB		
0118	8364000000-E	450	HP12X53 STEEL PILES	425 LF		
0119	8475000000-E	460	TWO BAR METAL RAIL	158.46 LF		
0120	8517000000-E	460	1'-**"X ***** CONCRETE PARA- PET (1'-2" X 2'-9")	174.8 LF		
0121	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	525 TON		
0122	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	585 SY		
0123	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,134.38 LF		

0709/Apr08/Q40597.94/D630989730000/E124

Total Amount Of Bid For Entire Project :

Contract No **C201834**

County (ies): **Durham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General