

County : Durham, Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	15 SY		
0003	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	15 LF		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	13.78 SMI		
0005	1330000000-E	607	INCIDENTAL MILLING	2,400 SY		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,790 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	24,299 TON		
0008	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,535 TON		
0009	1704000000-E	SP	PATCHING EXISTING PAVEMENT	650 TON		
0010	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0011	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0012	2619000000-E	850	4" CONCRETE PAVED DITCH	10 SY		
0013	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	320 SY		
0014	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	450 SY		
0015	2815000000-N	858	ADJUSTMENT OF DROP INLETS	2 EA		
0016	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0017	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0018	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		

County : Durham, Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4430000000-N	1130	DRUMS	100 EA		
0020	4480000000-N	1165	TMIA	2 EA		
0021	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	112,781 LF		
0022	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	20,515 LF		
0023	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	4,600 LF		
0024	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	458 LF		
0025	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	24 EA		
0026	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	139 EA		
0027	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3,100 EA		
0028	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0029	6084000000-E	1660	SEEDING & MULCHING	10.23 ACR		
0030	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	8,600 LF		
0031	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	8,600 LF		

1502/Apr18/Q190438.01/D104808100000/E31

Total Amount Of Bid For Entire Project :

**Contract No**     **C202059**

**County (ies):**    **Durham, Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General