

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17 + 10.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	15 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	120 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	175 TON		
0012	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	200 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	21 TON		
0014	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0015	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5 EA		
0016	2556000000-E	846	SHOULDER BERM GUTTER	90 LF		
0017	3030000000-E	862	STEEL BM GUARDRAIL	325 LF		
0018	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
002C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
0021	3649000000-E	876	RIP RAP, CLASS B	40	TON	
0022	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	300	SY	
0023	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	407	SF	
0024	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
002E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	83	SF	
002E	4435000000-N	1135	CONES	10	EA	
0027	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
002E	4455000000-N	1150	FLAGGER	30	MD	
002E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	10	EA	
003C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,400	LF	
0031	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10	EA	
0032	6000000000-E	1605	TEMPORARY SILT FENCE	740	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	80	TON	
0034	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120	TON	
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	110	TON	
003E	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
003E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
003E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
004C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0041	6029000000-E	SP	SAFETY FENCE	200 LF		
0042	6030000000-E	1630	SILT EXCAVATION	230 CY		
0043	6036000000-E	1631	MATTING FOR EROSION CONTROL	220 SY		
0044	6042000000-E	1632	1/4" HARDWARE CLOTH	240 LF		
004E	6071030000-E	SP	COIR FIBER BAFFLES	50 LF		
004E	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0047	6087000000-E	1660	MOWING	0.5 ACR		
004E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
004E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0051	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0052	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0053	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0054	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+10.00-L-)	Lump Sum	L.S.	
0055	8112730000-N	SP	PDA TESTING	1 EA		
0056	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0057	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+10.00-L-)	Lump Sum	L.S.	
005E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	33.5 CY		
0059	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+10.00-L-)	Lump Sum	L.S.	
006C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,448 LB		
0061	8364000000-E	450	HP12X53 STEEL PILES	630 LF		
0062	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	360 LF		
0063	8393000000-N	450	PILE REDRIVES	12 EA		
0064	8503000000-E	460	CONCRETE BARRIER RAIL	175.5 LF		
006E	8590000000-E	876	RIP RAP, CLASS ** (1, 2'-0" THICK)	138 TON		
0066	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	153 SY		
0067	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
006E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	963.88 LF		

Contract No **C201833**

County (ies): **Halifax**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General