

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	20,000 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 65.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	570 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	275 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	90 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	572 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	184 LF		
0015	0995000000-E	340	PIPE REMOVAL	30 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	96 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0018	1275000000-E	600	PRIME COAT	88 GAL		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	920	TON	
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	315	TON	
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	65	TON	
0022	2022000000-E	815	SUBDRAIN EXCAVATION	115	CY	
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85	CY	
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500	LF	
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15	EA	
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10	EA	
0029	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1	EA	
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	9	EA	
0031	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	530	LF	
0032	3030000000-E	862	STEEL BM GUARDRAIL	575	LF	
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	40	LF	
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0035	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2	EA	
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6	EA	

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
003E	3557000000-E	866	ADDITIONAL BARBED WIRE	100	LF	
003E	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	900	LF	
004C	3649000000-E	876	RIP RAP, CLASS B	20	TON	
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	225	SY	
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	174	SF	
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	186	SF	
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	56	SF	
004E	4430000000-N	1130	DRUMS	60	EA	
004E	4435000000-N	1135	CONES	20	EA	
0047	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
004E	4450000000-N	1150	FLAGGER	236	HR	
004E	4516000000-N	1180	SKINNY DRUM	10	EA	
005C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	21,000	LF	
0051	6000000000-E	1605	TEMPORARY SILT FENCE	930	LF	
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90	TON	
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	285	TON	
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	240	TON	

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
005E	6029000000-E	SP	SAFETY FENCE	350 LF		
005E	6030000000-E	1630	SILT EXCAVATION	540 CY		
006C	6036000000-E	1631	MATTING FOR EROSION CONTROL	850 SY		
0061	6037000000-E	SP	COIR FIBER MAT	10 SY		
0062	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	125 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	515 LF		
0064	6071030000-E	SP	COIR FIBER BAFFLES	25 LF		
006E	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		
0067	6087000000-E	1660	MOWING	2.5 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0072	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6123000000-E	1670	REFORESTATION	0.3 ACR		
STRUCTURE ITEMS						
007E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+65.00-L-)	Lump Sum	L.S.	
007E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+65.00-L-)	Lump Sum	L.S.	
0077	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,046 SF		
007E	8161000000-E	420	GROOVING BRIDGE FLOORS	3,067 SF		
0079	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	59.5 CY		
008C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+65.00-L-)	Lump Sum	L.S.	
0081	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,194 LB		
0082	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	97,900 LS		
008E	8364000000-E	450	HP12X53 STEEL PILES	195 LF		
0084	8391000000-N	450	STEEL PILE POINTS	14 EA		
008E	8503000000-E	460	CONCRETE BARRIER RAIL	194.92 LF		
008E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	202 TON		
0087	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	224 SY		
008E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
<hr/>						
1055/Mar28/Q168207.47/D377466180000/E89			Total Amount Of Bid For Entire Project :			

Contract No **C201839**

County (ies): **Haywood**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General