

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+29.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	78 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	194 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	56 LF		
0012	0995000000-E	340	PIPE REMOVAL	52 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0014	1245000000-E	SP	SHOULDER RECONSTRUCTION	6.6 SMI		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,161 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	250 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,755 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	227 TON		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0023	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	1 EA		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	34 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	412.5 LF		
0029	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	125 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0033	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0034	3649000000-E	876	RIP RAP, CLASS B	14 TON		
0035	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	190 SY		
0036	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	339 SF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57	SF	
0039	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	30	DAY	
0040	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
0041	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,536	LF	
0042	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,460	LF	
0043	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (3)	380	LF	
0044	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	100,000	LF	
0045	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	48	LF	
0046	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4	EA	
0047	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	166	EA	
0048	5325600000-E	1510	6" WATER LINE	200	LF	
0049	5325800000-E	1510	8" WATER LINE	670	LF	
0050	5540000000-E	1515	6" VALVE	1	EA	
0051	5546000000-E	1515	8" VALVE	2	EA	
0052	5871000000-E	1550	TRENCHLESS INSTALLATION OF *** IN SOIL (8")	277	LF	
0053	5871010000-E	1550	TRENCHLESS INSTALLATION OF *** NOT IN SOIL (8")	277	LF	
0054	6000000000-E	1605	TEMPORARY SILT FENCE	560	LF	

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	60 TON		
0056	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	160 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
0058	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0059	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0060	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0062	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0063	6029000000-E	SP	SAFETY FENCE	250 LF		
0064	6030000000-E	1630	SILT EXCAVATION	570 CY		
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	510 SY		
0066	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0067	6071030000-E	SP	COIR FIBER BAFFLES	250 LF		
0068	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0069	6087000000-E	1660	MOWING	1 ACR		
0070	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0076	6123000000-E	1670	REFORESTATION	0.25 ACR		
STRUCTURE ITEMS						
0077	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+29.50-L-)	Lump Sum	L.S.	
0078	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0079	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	554 CY		
0080	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,669 SF		
0081	8161000000-E	420	GROOVING BRIDGE FLOORS	4,549 SF		
0082	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	41.6 CY		
0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+29.50-L-)	Lump Sum	L.S.	
0084	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,646 LB		
0085	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	106,300 LS		
0086	8294000000-N	442	PAINTING OF STRUCTURAL STEEL (16+29.50-L-)	Lump Sum	L.S.	
0087	8364000000-E	450	HP12X53 STEEL PILES	630 LF		
0088	8393000000-N	450	PILE REDRIVES	12 EA		
0089	8503000000-E	460	CONCRETE BARRIER RAIL	190 LF		
0090	8590000000-E	876	RIP RAP, CLASS ** (I)	97 TON		
0091	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	108 SY		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1016/Apr02/Q236295.45/D417661280000/E92

Total Amount Of Bid For Entire Project :

Contract No **C201762**

County (ies): **Lenoir**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General