

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	8,500 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	450 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,100 TON		
0008	0106000000-E	230	BORROW EXCAVATION	7,600 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,350 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,480 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	76 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	1,100 LF		
0013	0345000000-E	310	24" SIDE DRAIN PIPE	84 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	452 LF		
0015	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	488 LF		
0016	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	72 LF		
0017	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	160 LF		
0018	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	80 LF		
0019	0995000000-E	340	PIPE REMOVAL	1,465 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0021	1110000000-E	510	STABILIZER AGGREGATE	400 TON		
0022	1220000000-E	545	INCIDENTAL STONE BASE	700 TON		
0023	1330000000-E	607	INCIDENTAL MILLING	1,600 SY		
0024	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,315 TON		
0025	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,990 TON		
0026	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,530 TON		
0027	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	911 TON		
0028	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	560 TON		
0029	2209000000-E	838	ENDWALLS	36.8 CY		
0030	2253000000-E	840	PIPE COLLARS	6.8 CY		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0032	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
0033	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0034	2535000000-E	846	***X *** CONCRETE CURB (8" X 12")	45 LF		
0035	2612000000-E	848	6" CONCRETE DRIVEWAY	740 SY		
0036	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	50 SY		
0037	2830000000-N	858	ADJUSTMENT OF MANHOLES	14 EA		
0038	3030000000-E	862	STEEL BM GUARDRAIL	87.5 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0040	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0041	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0042	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0043	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0044	3435000000-N	SP	GENERIC GUARDRAIL ITEM 25' CLEAR SPAN GUARDRAIL SECTION	1 EA		
0045	3628000000-E	876	RIP RAP, CLASS I	100 TON		
0046	3649000000-E	876	RIP RAP, CLASS B	105 TON		
0047	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	500 SY		
0048	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	376 SF		
0049	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	320 SF		
0050	4430000000-N	1130	DRUMS	350 EA		
0051	4435000000-N	1135	CONES	200 EA		
0052	4445000000-E	1145	BARRICADES (TYPE III)	864 LF		
0053	4450000000-N	1150	FLAGGER	2,800 HR		
0054	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0055	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	4 EA		
0056	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	270 LF		
0057	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	270 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	4505000000-E	1170	RESET PORTABLE CONCRETE BARRIER (ANCHORED)	250 LF		
0059	4506000000-E	1170	RESET PORTABLE CONCRETE BARRIER (DRAINAGE)	250 LF		
0060	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	362 EA		
0061	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	20,339 LF		
0062	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	26,588 LF		
0063	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	168 LF		
0064	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	72 LF		
0065	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
0066	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	78 EA		
0067	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	93,854 LF		
0068	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	336 LF		
0069	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	72 LF		
0070	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	12 EA		
0071	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	78 EA		
0072	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	362 EA		
0073	5325600000-E	1510	6" WATER LINE	125 LF		
0074	5325800000-E	1510	8" WATER LINE	3,860 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	5326200000-E	1510	12" WATER LINE	6,950 LF		
0076	5540000000-E	1515	6" VALVE	8 EA		
0077	5546000000-E	1515	8" VALVE	10 EA		
0078	5558000000-E	1515	12" VALVE	7 EA		
0079	5648000000-N	1515	RELOCATE WATER METER	24 EA		
0080	5666000000-E	1515	FIRE HYDRANT	8 EA		
0081	5801000000-E	1530	ABANDON 8" UTILITY PIPE	3,860 LF		
0082	5804000000-E	1530	ABANDON 12" UTILITY PIPE	6,920 LF		
0083	5815500000-N	1530	REMOVE FIRE HYDRANT	8 EA		
0084	5912000000-N	SP	GENERIC UTILITY ITEM 12" WATER METER ASSEMBLY & NEW METER VAULT	Lump Sum	L.S.	
0085	6000000000-E	1605	TEMPORARY SILT FENCE	5,100 LF		
0086	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120 TON		
0087	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,350 TON		
0088	6012000000-E	1610	SEDIMENT CONTROL STONE	135 TON		
0089	6015000000-E	1615	TEMPORARY MULCHING	13.4 ACR		
0090	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	670 LB		
0091	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.7 TON		
0092	6029000000-E	SP	SAFETY FENCE	1,000 LF		
0093	6030000000-E	1630	SILT EXCAVATION	900 CY		
0094	6033000000-E	1631	SYNTHETIC ROVING	650 SY		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095	6036000000-E	1631	MATTING FOR EROSION CONTROL	650 SY		
0096	6042000000-E	1632	1/4" HARDWARE CLOTH	200 LF		
0097	6045000000-E	SP	*** TEMPORARY PIPE (36")	400 LF		
0098	6070000000-N	SP	SPECIAL STILLING BASINS	2 EA		
0099	6084000000-E	1660	SEEDING & MULCHING	13.4 ACR		
0100	6087000000-E	1660	MOWING	13.4 ACR		
0101	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		
0102	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.2 TON		
0103	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0104	6108000000-E	1665	FERTILIZER TOPDRESSING	3.4 TON		
0105	6111000000-E	SP	IMPERVIOUS DIKE	230 LF		
0106	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	20 EA		
0107	8126000000-N	414	CULVERT EXCAVATION, STA ***** (13+03.07)	Lump Sum	L.S.	
0108	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	26 TON		
0109	8196000000-E	420	CLASS A CONCRETE (CULVERT)	61.1 CY		
0110	8245000000-E	425	REINFORCING STEEL (CULVERT)	7,879 LB		
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
AA1	0111 0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	472 LF		
*** OR ***						
AA2	0112 0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	296 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0113 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	176	LF	
----- *** OR ***						
0114 AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	296	LF	
0115 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.079")	176	LF	

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

1154/Apr11/Q239616.1/D42332860000/E115

Total Amount Of Bid For Entire Project :

**Contract No**     **C201803**

**County (ies):**   **Robeson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General