

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	22,420 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22 + 62.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,200 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	620 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	47 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	44 LF		
0013	0420000000-E	310	66" RC PIPE CULVERTS, CLASS III	368 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	32 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0016	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	680 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	360	TON	
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	53	TON	
002C	2000000000-N	806	RIGHT OF WAY MARKERS	19	EA	
0021	2022000000-E	815	SUBDRAIN EXCAVATION	112	CY	
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84	CY	
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500	LF	
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15	EA	
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0027	2220000000-E	838	REINFORCED ENDWALLS	11.1	CY	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
003C	2556000000-E	846	SHOULDER BERM GUTTER	50	LF	
0031	2995000000-N	SP	GENERIC DRAINAGE ITEM SPECIAL JUNCTION BOX	1	EA	
0032	3030000000-E	862	STEEL BM GUARDRAIL	575	LF	
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3628000000-E	876	RIP RAP, CLASS I	75	TON	
0037	3649000000-E	876	RIP RAP, CLASS B	10	TON	
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	480	SY	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	409	SF	
004C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	149	SF	
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	126	SF	
0042	4430000000-N	1130	DRUMS	50	EA	
0043	4435000000-N	1135	CONES	30	EA	
0044	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
004E	4455000000-N	1150	FLAGGER	100	MD	
004E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0047	4480000000-N	1165	TMIA	1	EA	
004E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	180	LF	
004E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	32	EA	
005C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,544	LF	
0051	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,544	LF	
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,176	LF	
0053	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	32	EA	
0054	6000000000-E	1605	TEMPORARY SILT FENCE	1,930	LF	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	350 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	330 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
006C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	70 LF		
0062	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0063	6029000000-E	SP	SAFETY FENCE	500 LF		
0064	6030000000-E	1630	SILT EXCAVATION	1,725 CY		
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000 SY		
006E	6037000000-E	SP	COIR FIBER MAT	45 SY		
0067	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	80 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	480 LF		
006E	6070000000-N	SP	SPECIAL STILLING BASINS	2 EA		
007C	6071010000-E	SP	WATTLE	75 LF		
0071	6071020000-E	SP	POLYACRYLAMIDE (PAM)	18 LB		
0072	6071030000-E	SP	COIR FIBER BAFFLES	460 LF		
0073	6071050000-E	SP	*** SKIMMER (1-1/2")	10 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6071050000-E	SP	*** SKIMMER (2")	1 EA		
007E	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
007E	6087000000-E	1660	MOWING	1.5 ACR		
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
008C	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0081	6111000000-E	SP	IMPERVIOUS DIKE	360 LF		
0082	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
008E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0084	6123000000-E	1670	REFORESTATION	0.5 ACR		

**STRUCTURE ITEMS**

008E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22 + 62.50-L-)	Lump Sum	L.S.	
008E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 62.50-L-)	Lump Sum	L.S.	
0087	8096000000-E	SP	PILE EXCAVATION IN SOIL	92 LF		
008E	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	92 LF		
008E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,795 SF		
009C	8161000000-E	420	GROOVING BRIDGE FLOORS	6,460 SF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	104.8 CY		
0092	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+62.50-L-)	Lump Sum	L.S.	
0093	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,270 LB		
0094	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	333,200 LS		
009E	8364000000-E	450	HP12X53 STEEL PILES	375 LF		
009E	8391000000-N	450	STEEL PILE POINTS	30 EA		
0097	8503000000-E	460	CONCRETE BARRIER RAIL	364.56 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	280 TON		
009E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	310 SY		
010C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0101	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0747/May09/Q415910.96/D456876260000/E101			<b>Total Amount Of Bid For Entire Project :</b>			

**Contract No**     **C201812**

**County (ies):**   **Burke**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General