

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	30 TON		
0005	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	824 LF		
0006	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	60 LF		
0007	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	456 LF		
0008	0528000000-E	310	*** RC PIPE ELBOWS, CLASS III (30")	1 EA		
0009	0995000000-E	340	PIPE REMOVAL	577 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0011	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 6")	28,850 SY		
0012	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	500 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,610 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	181 TON		
0015	2253000000-E	840	PIPE COLLARS	0.4 CY		
0016	2264000000-E	840	PIPE PLUGS	0.4 CY		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	79 EA		

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	9	LF	
001E	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	1	EA	
002C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	10	EA	
0021	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	23	EA	
0022	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	29	EA	
002E	2396000000-N	840	FRAME WITH COVER, STD 840.54	2	EA	
0024	2535000000-E	846	***X *** CONCRETE CURB (8" X 12")	690	LF	
002E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	6,200	LF	
002E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	9,220	LF	
0027	2591000000-E	848	4" CONCRETE SIDEWALK	7,650	SY	
002E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	90	EA	
002E	2612000000-E	848	6" CONCRETE DRIVEWAY	900	SY	
003C	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	530	SY	
0031	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2	EA	
0032	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1	EA	
003E	2830000000-N	858	ADJUSTMENT OF MANHOLES	95	EA	
0034	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	49	EA	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	744	SF	

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4430000000-N	1130	DRUMS	175	EA	
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	26,755	LF	
003E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	5,406	LF	
003E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	626	LF	
004C	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	46	EA	
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	200	TON	
0042	6042000000-E	1632	1/4" HARDWARE CLOTH	2,240	LF	
0043	6084000000-E	1660	SEEDING & MULCHING	0.7	ACR	
0044	7060000000-E	1705	SIGNAL CABLE	4,550	LF	
004E	7096000000-E	1705	VEHICLE SIGNAL HEAD (8", 3 SECTION)	36	EA	
004E	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	11	EA	
0047	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	2	EA	
004E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	3	EA	
004E	7204000000-N	SP	LOUVER	8	EA	
005C	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	160	LF	
0051	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	300	LF	
0052	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	985	LF	
0053	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	26	EA	

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,060	LF	
005E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	930	LF	
005E	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	10	EA	
0057	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	6	EA	
005E	7613000000-N	SP	SOIL TEST	16	EA	
005E	7614100000-E	SP	DRILLED PIER FOUNDATION	108	CY	
006C	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	2	EA	
0061	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	16	EA	
0062	7636000000-N	1745	SIGN FOR SIGNALS	9	EA	
006E	7675000000-N	SP	LED BLANKOUT SIGN	2	EA	
0064	7980000000-N	SP	GENERIC SIGNAL ITEM RELOCATE EXISTING CONTROLLERS WITH CABINETS	4	EA	

1050/May07/Q104609.5/D26256960000/E64

Total Amount Of Bid For Entire Project :

Contract No **C201846**

County (ies): **Craven**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General