

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	2,040 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+13.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	23 TON		
0009	0342000000-E	310	*** SIDE DRAIN PIPE (30")	20 LF		
0010	0345000000-E	310	24" SIDE DRAIN PIPE	20 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	60 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	80 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0015	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	330 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	215 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	29 TON		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0020	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	190 LF		
0023	3030000000-E	862	STEEL BM GUARDRAIL	362.5 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0026	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0027	3628000000-E	876	RIP RAP, CLASS I	50 TON		
0028	3649000000-E	876	RIP RAP, CLASS B	12 TON		
0029	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	375 SY		
0030	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	395 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0032	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0033	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,000 LF		
0034	6000000000-E	1605	TEMPORARY SILT FENCE	600 LF		
0035	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105 TON		
0036	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	115 TON		
0037	6012000000-E	1610	SEDIMENT CONTROL STONE	120 TON		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0039	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0040	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.25 TON		
0041	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0042	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0043	6029000000-E	SP	SAFETY FENCE	455 LF		
0044	6030000000-E	1630	SILT EXCAVATION	310 CY		
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	815 SY		
0046	6037000000-E	SP	COIR FIBER MAT	25 SY		
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	265 LF		
0048	6071030000-E	SP	COIR FIBER BAFFLES	90 LF		
0049	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0050	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0051	6087000000-E	1660	MOWING	1 ACR		
0052	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0053	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0054	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0055	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0056	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0058	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+13.50-L-)	Lump Sum	L.S.	
0059	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+13.50-L-)	Lump Sum	L.S.	
0060	8084000000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ***** (1, 18+13.50-L-)	Lump Sum	L.S.	
0061	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	857 CY		
0062	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,210 SF		
0063	8161000000-E	420	GROOVING BRIDGE FLOORS	4,233 SF		
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	78.9 CY		
0065	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+13.50-L-)	Lump Sum	L.S.	
0066	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,323 LB		
0067	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	148,785 LS		
0068	8364000000-E	450	HP12X53 STEEL PILES	540 LF		
0069	8503000000-E	460	CONCRETE BARRIER RAIL	245.83 LF		
0070	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	120 TON		
0071	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	134 SY		
0072	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
--------	-------------	-------	-------------	----------	-----------	--------

0073	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
------	--------------	----	---------------------	----------	------	--

1434/May09/Q183477.73/D338214180000/E73

Total Amount Of Bid For Entire Project :

Contract No **C201785**

County (ies): **Iredell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General