

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (13+50.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	4,650 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	62 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	63 TON		
0011	0342000000-E	310	*** SIDE DRAIN PIPE (30")	40 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3 EA		
0014	0995000000-E	340	PIPE REMOVAL	29 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	32 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	545 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	675 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	69 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	22 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
0030	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	405 LF		
0032	2612000000-E	848	6" CONCRETE DRIVEWAY	120 SY		
0033	3030000000-E	862	STEEL BM GUARDRAIL	1,187.5 LF		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	87.5 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0036	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	10 TON		
004C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	451 SY		
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0042	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	45 LF		
0043	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0044	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	7 EA		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	592 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	188 SF		
004E	4445000000-E	1145	BARRICADES (TYPE III)	144 LF		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,200 LF		
005C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	19 EA		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	1,440 LF		
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	220 TON		
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.5 TON		
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	270 LF		
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	8 EA		
006C	6029000000-E	SP	SAFETY FENCE	420 LF		
0061	6030000000-E	1630	SILT EXCAVATION	770 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,070 SY		
0063	6037000000-E	SP	COIR FIBER MAT	50 SY		
0064	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	160 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
006E	6071030000-E	SP	COIR FIBER BAFFLES	300 LF		
0067	6071050000-E	SP	*** SKIMMER (1-1/2")	8 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
006E	6087000000-E	1660	MOWING	2 ACR		
007C	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	4	HR	
0075	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24	EA	
0076	6123000000-E	1670	REFORESTATION	0.2	ACR	

***** BEGIN SCHEDULE AA *****
***** (3 ALTERNATES) *****

0077	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	472	LF	
------	--------------	-----	---------------------------------	-----	----	--

*** OR ***

0078	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	128	LF	
------	--------------	-----	---------------------------------	-----	----	--

0079	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	344	LF	
------	--------------	----	-------------------------------	-----	----	--

*** OR ***

0080	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	128	LF	
------	--------------	-----	---------------------------------	-----	----	--

0081	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	344	LF	
------	--------------	----	--	-----	----	--

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0082	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+50.00-L-)	Lump Sum	L.S.	
------	--------------	-----	--	----------	------	--

0083	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+47.50-L-)	Lump Sum	L.S.	
------	--------------	-----	--	----------	------	--

0084	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (13+50.00-L-)	Lump Sum	L.S.	
------	--------------	-----	--	----------	------	--

0085	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+47.50-L-)	Lump Sum	L.S.	
------	--------------	-----	--	----------	------	--

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	79.2 CY		
0087	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+50.00-L-)	Lump Sum	L.S.	
008E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+47.50-L-)	Lump Sum	L.S.	
008E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,752 LB		
009C	8364000000-E	450	HP12X53 STEEL PILES	1,300 LF		
0091	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	180 LF		
0092	8393000000-N	450	PILE REDRIVES	20 EA		
009E	8503000000-E	460	CONCRETE BARRIER RAIL	400.69 LF		
0094	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	923 TON		
009E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,027 SY		
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0097	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,074.62 LF		
009E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,231.5 LF		

1240/May09/Q48684.86/D410231580000/E98

Total Amount Of Bid For Entire Project :

Contract No **C202108**

County (ies): **Nash**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General