



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

July 3, 2008

Addendum No. 2

RE: Contract ID: C202107

WBS# 34445.4.1, 34445.4.2 (Combined Proposal No. 3)

Madison, Yancey Counties (R-2518A, R-2518B)

US-19 From I-26 in Madison County to
SR-1336 (Jack's Creek Road)

July 15, 2008 Letting

To Whom It May Concern:

Reference is made to the proposal form recently furnished to you on this project.

The following revisions have been made to the proposal:

On Page No. 5 the project special provision entitled "Note To Contractor" has been revised.
Please void Page No. 5 in your proposal and staple the revised Page No. 5 thereto.

On Page No. 123 the project special provision entitled "Seeding Equipment" has been revised
and moved to new Page No. 123-A. Please void Page No. 123 in your proposal and staple revised
Page No. 123 and new Page No. 123-A thereto.

Sincerely,

A handwritten signature in black ink, appearing to read "R. A. Garris".

R. A. Garris, PE
Contract Officer

RAG/jag
Attachments

Page 2

RE: Contract ID: C202107

Madison, Yancey Counties (R-2518A, R-2518B)

Cc: Mr. W. S. Varnedoe, PE
Mr. E. C. Powell, PE
Mr. J. J. Swain, Jr., PE
Ms. D.M. Barbour, PE
Mr. Art McMillan, PE
Mr. J. V. Barbour, PE
Mr. Mark Staley (2)
Mr. Robert Memory
Mr. R. E. Davenport, Jr., PE
Ms. Norma Smith
Ms. Marsha Sample
Mr. Ronnie Higgins
Mr. Larry Strickland
Ms. Lori Strickland
Project File (2)

The documents listed below are available to the Contractor on the NCDOT web site at the following address: <http://dotw-xfer01.dot.state.nc.us/dsplan/2008%20Highway%20Letting/>

- The Biological Opinion dated March 14, 2008
- Stream Mitigation Plan R-2518B
- Stream Mitigation Guidelines
- Foundation Recommendations for Pavement Design (R-2518A & R-2518B)

MAJOR CONTRACT ITEMS:

(2-19-02)

M1 G28

The following listed items are the major contract items for this contract (See Articles 101 and 104-5 of the *2006 Metric Standard Specifications*):

Line #	Description
84	Asphalt Concrete Intermediate Course, Type I19.0C
	And
306	Unclassified Excavation
	or
311	Unclassified Excavation

SPECIALTY ITEMS:

(7-1-95)

M1 G37

Items listed below will be the specialty items for this contract (See Article 108-6 of the *2006 Metric Standard Specifications*).

Line #	Description
137 - 152, 160	Guardrail
153 - 159	Fencing
169 - 175	Signing
201 - 204	Long-Life Pavement Markings
207	Permanent Pavement Markers
209 - 216	Utility Construction
217 - 254	Erosion Control
255 - 256	Reforestation
257 - 260	On-Site Mitigation
261 - 280	Signals
347 - 352	Drilled Piers

FUEL PRICE ADJUSTMENT:

(11-15-05) (Rev 11-21-06)

M1 G43

Revise the *2006 Metric Standard Specifications* as follows:

Page 1-78, Article 109-8 Fuel Price Adjustment is amended to add the following as the first paragraph:

REFORESTATION:**123****Description**

Reforestation will be planted within areas of pavement removal and along the outside borders of the road, or planted in other areas as directed. See the plan sheets and Reforestation Detail Sheet.

All non-maintained riparian buffers impacted by the placement of temporary fill or clearing activities shall be restored to the preconstruction contours and revegetated with native woody species.

The entire *Reforestation* operation shall comply with the requirements of Section 1670 of the *Standard Specifications*.

Materials

Reforestation shall be bare root seedlings 305mm-457mm tall.

Construction Methods

Reforestation shall be planted as soon as practical following permanent *Seeding and Mulching*. The seedlings shall be planted in a 4.9-meter wide swath adjacent to mowing pattern line, or as directed.

Root dip: The roots of reforestation seedlings shall be coated with a slurry of water, and either a fine clay (kaolin) or a superabsorbent that is designated as a bare root dip. The type, mixture ratio, method of application, and the time of application shall be submitted to the Engineer for approval.

With the approval of the Engineer, seedlings may be coated before delivery to the job or at the time of planting, but at no time shall the roots of the seedlings be allowed to dry out. The roots shall be moistened immediately prior to planting.

Seasonal Limitations: *Reforestation* shall be planted from November 15 through March 15.

Measurement and Payment

Reforestation will be measured and paid for in accordance with Article 1670-17 of the *Standard Specifications*.

123-A**SEEDING EQUIPMENT:**

Due to the size and environmental sensitivity of this project, the contractor shall retain sufficient equipment and materials onsite to perform seeding, mulching and matting operations on a continuous basis. Since seeding, mulching and matting operations will be performed in a continuous manner, no additional payments shall be made for the requirements of this section

The contractor may utilize equipment from the project during inactive times to perform work on other projects, as directed.