

County : Beaufort, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+00.53)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	3,300 CY		
0007	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	5 EA		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	91 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,900 SY		
0010	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	300 CY		
0011	0241000000-E	SP	GENERIC GRADING ITEM FABRIC FOR EMBANKMENT STABILIZATION	3,700 SY		
0012	0255000000-E	SP	GENERIC GRADING ITEM LIGHTWEIGHT AGGREGATE	3,600 TON		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	18 TON		
0014	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	64 LF		
0016	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	64 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0018	0995000000-E	340	PIPE REMOVAL	61 LF		

County : Beaufort, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	148 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	662 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	753 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	74 TON		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0031	2355000000-N	840	FRAME WITH GRATE, STD 840.29	4 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	54 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0037	3649000000-E	876	RIP RAP, CLASS B	5 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	245 SY		
0039	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	13.6 SF		
0040	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	29 SF		
0041	4082000000-E	903	SUPPORTS, WOOD	132 LF		
0042	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0043	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
0044	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	11 EA		
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	294 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	107 SF		
0047	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0048	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	4,700 LF		
0049	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	16 EA		
0050	6000000000-E	1605	TEMPORARY SILT FENCE	1,380 LF		
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	160 TON		
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	90 TON		
0054	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	90 LF		
0058	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0059	6029000000-E	SP	SAFETY FENCE	250 LF		
0060	6030000000-E	1630	SILT EXCAVATION	365 CY		
0061	6036000000-E	1631	MATTING FOR EROSION CONTROL	225 SY		
0062	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		
0063	6071030000-E	SP	COIR FIBER BAFFLES	115 LF		
0064	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
0065	6087000000-E	1660	MOWING	1.5 ACR		
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0070	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0072	6123000000-E	1670	REFORESTATION	0.1 ACR		
0073	6129000000-E	1670	WETLAND REFORESTATION	0.05 ACR		
0074	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	0.14 ACR		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	0.14 ACR		
STRUCTURE ITEMS						
0076	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22+00.00-L-)	Lump Sum	L.S.	
0077	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+00.00-L-)	Lump Sum	L.S.	
0078	8112730000-N	SP	PDA TESTING	2 EA		
0079	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0080	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	2,150 CY		
0081	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	170.2 CY		
0082	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+00.00-L-)	Lump Sum	L.S.	
0083	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,607 LB		
0084	8364000000-E	450	HP12X53 STEEL PILES	925 LF		
0085	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24 X 0.5)	3,360 LF		
0086	8393000000-N	450	PILE REDRIVES	35 EA		
0087	8475000000-E	460	TWO BAR METAL RAIL	862.63 LF		
0088	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-11 1/4")	877.63 LF		
0089	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	391 TON		

County : Beaufort, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	457 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	5,691.56 LF		
0093	8897000000-N	SP	GENERIC STRUCTURE ITEM PREDRILLING OF PILES	28 EA		
0803/June12/Q67121.05/D407109200000/E93			Total Amount Of Bid For Entire Project :			

Contract No **C201732**

County (ies): **Beaufort & Pitt**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)