

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (25+70.53)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	150 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	1,100 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	45 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	44 LF		
0012	0986000000-E	SP	GENERIC PIPE ITEM 8" PVC PIPE	40 LF		
0013	0995000000-E	340	PIPE REMOVAL	44 LF		
0014	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0015	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	315 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,000 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	310 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	715 TON		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	183 TON		
0021	1704000000-E	SP	PATCHING EXISTING PAVEMENT	100 TON		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2.4 LF		
0030	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0033	2474000000-N	SP	GENERIC DRAINAGE ITEM INFILTRATION BASIN	Lump Sum	L.S.	
0034	2556000000-E	846	SHOULDER BERM GUTTER	65 LF		
0035	3030000000-E	862	STEEL BM GUARDRAIL	525 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,150 LF		
0040	3649000000-E	876	RIP RAP, CLASS B	32 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	259 SY		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	670 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0044	4430000000-N	1130	DRUMS	23 EA		
0045	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0046	4455000000-N	1150	FLAGGER	60 MD		
0047	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,298 LF		
0048	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,298 LF		
0049	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (3, PERMANENT WET REFLECTIVE)	1,208 LF		
0050	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,852 LF		
0051	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	12 EA		
0052	5326200000-E	1510	12" WATER LINE	998 LF		
0053	5558000000-E	1515	12" VALVE	2 EA		
0054	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0055	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0056	5804000000-E	1530	ABANDON 12" UTILITY PIPE	890 LF		
0057	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	200 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	185 LF		
0059	6000000000-E	1605	TEMPORARY SILT FENCE	1,440 LF		
0060	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	130 TON		
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0063	6015000000-E	1615	TEMPORARY MULCHING	5.5 ACR		
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0065	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0066	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0067	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0068	6029000000-E	SP	SAFETY FENCE	420 LF		
0069	6030000000-E	1630	SILT EXCAVATION	400 CY		
0070	6036000000-E	1631	MATTING FOR EROSION CONTROL	370 SY		
0071	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	450 SY		
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0073	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	140 SY		
0074	6071030000-E	SP	COIR FIBER BAFFLES	220 LF		
0075	6084000000-E	1660	SEEDING & MULCHING	5.5 ACR		
0076	6087000000-E	1660	MOWING	3.5 ACR		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0078	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0079	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		
0080	6108000000-E	1665	FERTILIZER TOPDRESSING	4 TON		
0081	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0083	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	0.298 ACR		
0084	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	0.298 ACR		
0085	6135000000-E	SP	GENERIC EROSION CONTROL ITEM WETLAND GRASS PLANTING	0.151 ACR		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0086 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	324 LF		
*** OR ***						
0087 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	300 LF		
0088 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	24 LF		
*** OR ***						
0089 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	300 LF		
0090 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	24 LF		

***** END SCHEDULE AA *****

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0091	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25+70.00-L)	Lump Sum	L.S.	
0092	8112730000-N	SP	PDA TESTING	2 EA		
0093	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0094	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	2,600 CY		
0095	8156000000-E	SP	CONCRETE WEARING SURFACE	11,803 SF		
0096	8161000000-E	420	GROOVING BRIDGE FLOORS	12,554 SF		
0097	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	105.8 CY		
0098	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25+70.00-L-)	Lump Sum	L.S.	
0099	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	16,982 LB		
0100	8329000000-E	450	12" PRESTRESSED CONC PILES	440 LF		
0101	8333000000-E	450	16" PRESTRESSED CONC PILES	800 LF		
0102	8393000000-N	450	PILE REDRIVES	20 EA		
0103	8475000000-E	460	TWO BAR METAL RAIL	582.5 LF		
0104	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 3'-0")	597.5 LF		
0105	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	424 TON		
0106	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	471 SY		
0107	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0108	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	2,723 LF		
0110	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,452.5 LF		
1316/Jun05/Q95338.947/D486201510000/E110			Total Amount Of Bid For Entire Project :			

Contract No **C201848**

County (ies): **Brunswick**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General