

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	36,600 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	16 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	346.5 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	170 TON		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	124 LF		
0013	0804000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE B ***** THICK (15", 0.064")	6 EA		
0014	0987000000-E	310	GENERIC PIPE ITEM TEMPORARY 15" PLASTIC CORR. PIPE	76 LF		
0015	0995000000-E	340	PIPE REMOVAL	585 LF		
0016	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	6,000 TON		
0018	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	2,000 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	2,000 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	260 TON		
0021	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	95 TON		
0022	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	110 TON		
0023	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	3,240 LF		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	23 EA		
0031	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	13.3 LF		
0032	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0033	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	12 EA		
0034	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	8 EA		
0035	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0036	2556000000-E	846	SHOULDER BERM GUTTER	2,050 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2619000000-E	850	4" CONCRETE PAVED DITCH	150 SY		
0038	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	980 SY		
0039	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	25 LF		
0040	2875000000-N	859	CONVERT EXISTING CATCH BASIN TO DROP INLET	1 EA		
0041	2893000000-N	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE COVER	2 EA		
0042	3030000000-E	862	STEEL BM GUARDRAIL	2,650 LF		
0043	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0044	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	3 EA		
0045	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0046	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	1 EA		
0047	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	5 EA		
0048	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,425 LF		
0049	3649000000-E	876	RIP RAP, CLASS B	20 TON		
0050	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	280 SY		
0051	4048000000-E	902	REINFORCED CONCRETE SIGN FOUN- DATIONS	2 CY		
0052	4057000000-E	SP	OVERHEAD FOOTING	36 CY		
0053	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	431 LB		
0054	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	779 LB		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	420 LF		
0056	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (11+00-L-)	Lump Sum	L.S.	
0057	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (21+80 -L-)	Lump Sum	L.S.	
0058	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (34+50 -L-)	Lump Sum	L.S.	
0059	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
0060	4102000000-N	904	SIGN ERECTION, TYPE E	11 EA		
0061	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	4 EA		
0062	4127500000-N	SP	LRS LIGHTING SYSTEM FOR OVERHEAD SIGN ASSEMBLY AT STA ***** (11+00-L-)	Lump Sum	L.S.	
0063	4127500000-N	SP	LRS LIGHTING SYSTEM FOR OVERHEAD SIGN ASSEMBLY AT STA ***** (21+50-L-)	Lump Sum	L.S.	
0064	4127500000-N	SP	LRS LIGHTING SYSTEM FOR OVERHEAD SIGN ASSEMBLY AT STA ***** (34+50-L-)	Lump Sum	L.S.	
0065	4149000000-N	907	DISPOSAL OF SIGN SYSTEM, OVERHEAD	2 EA		
0066	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	5 EA		
0067	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	20 EA		
0068	4234000000-N	907	DISPOSAL OF SIGN, A OR B (OVERHEAD)	1 EA		
0069	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	350 SF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	520	SF	
0071	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	160	SF	
0072	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3	EA	
0073	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	3	EA	
0074	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	27	DAY	
0075	4430000000-N	1130	DRUMS	160	EA	
0076	4445000000-E	1145	BARRICADES (TYPE III)	180	LF	
0077	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0078	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
0079	4480000000-N	1165	TMIA	2	EA	
0080	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,400	LF	
0081	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	1,400	LF	
0082	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	760	LF	
0083	4506000000-E	1170	RESET PORTABLE CONCRETE BARRIER (DRAINAGE)	760	LF	
0084	4510000000-N	SP	POLICE	20	HR	
0085	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	170	EA	
0086	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	3,913	LF	
0087	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	723	LF	
0088	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	2,400	LF	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16 EA		
0090	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8 EA		
0091	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (4)	2,926 LF		
0092	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	10,438 LF		
0093	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	3,950 LF		
0094	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	32 EA		
0095	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	16 EA		
0096	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (STANDARD GLASS BEADS)	583 LF		
0097	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	170 EA		
0098	5015000000-E	1401	120' HIGH MOUNT STANDARD	1 EA		
0099	5020000000-N	1401	PORTABLE DRIVE UNIT	1 EA		
0100	5025000000-E	1402	HIGH MOUNT FOUNDATIONS	9.4 CY		
0101	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	8 EA		
0102	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3#1/0, USE)	50 LF		
0103	5145000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (240/480 VOLT)	1 EA		
0104	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	375 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0105	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	260 LF		
0106	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	65 LF		
0107	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	720 LF		
0108	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	250 LF		
0109	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	3,350 LF		
0110	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	8 EA		
0111	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC30)	3 EA		
0112	5270000000-N	SP	GENERIC LIGHTING ITEM RELOCATE LIGHT STANDARD	1 EA		
0113	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE CONTROL SYS	1 EA		
0114	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE HIGH MAST	1 EA		
0115	5270000000-N	SP	GENERIC LIGHTING ITEM TRANSFORMER PANEL, 3KVA	1 EA		
0116	6000000000-E	1605	TEMPORARY SILT FENCE	3,600 LF		
0117	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	330 TON		
0118	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	410 TON		
0119	6012000000-E	1610	SEDIMENT CONTROL STONE	450 TON		
0120	6015000000-E	1615	TEMPORARY MULCHING	5.5 ACR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0122	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0123	6024000000-E	1622	TEMPORARY SLOPE DRAINS	90 LF		
0124	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
0125	6030000000-E	1630	SILT EXCAVATION	1,500 CY		
0126	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500 SY		
0127	6042000000-E	1632	1/4" HARDWARE CLOTH	360 LF		
0128	6071030000-E	SP	COIR FIBER BAFFLES	225 LF		
0129	6084000000-E	1660	SEEDING & MULCHING	7.5 ACR		
0130	6087000000-E	1660	MOWING	5 ACR		
0131	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0132	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0133	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0134	6108000000-E	1665	FERTILIZER TOPDRESSING	5.5 TON		
0135	6114000000-N	SP	SPECIALIZED HAND MOWING	6 HR		
0136	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0137	7279000000-E	1715	TRACER WIRE	200 LF		
0138	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 1.25")	200 LF		
0139	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	5 EA		
0140	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	1 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0141	7613000000-N	SP	SOIL TEST	1	EA	
0142	7614100000-E	SP	DRILLED PIER FOUNDATION	4	CY	
0143	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	1	EA	
0144	7980000000-N	SP	GENERIC SIGNAL ITEM CCTV FOUNDATION DESIGN	1	EA	
0145	7980000000-N	SP	GENERIC SIGNAL ITEM CCTV METAL POLE	1	EA	
0146	7980000000-N	SP	GENERIC SIGNAL ITEM MODIFY ELECTRIC SERVICE	1	EA	
0147	7980000000-N	SP	GENERIC SIGNAL ITEM RELOCATE CCTV ASSEMBLY	1	EA	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0148	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	852	LF	
AA1						
0149	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	256	LF	
AA1						
0150	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	312	LF	
AA1						
*** OR ***						
0151	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	568	LF	
AA2						
0152	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	284	LF	
AA2						
0153	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	256	LF	
AA2						
0154	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	312	LF	
AA2						
*** OR ***						
0155	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	568	LF	
AA3						

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0156 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15")	284 LF		
0157 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18")	256 LF		
0158 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24")	312 LF		

**** END SCHEDULE AA ****

WALL ITEMS

0159	8801000000-E	SP	MSE RETAINING WALL	7,101 SF		
------	--------------	----	--------------------	-------------	--	--

STRUCTURE ITEMS

0160	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (31+81.71-L-)	Lump Sum	L.S.	
0161	8096000000-E	SP	PILE EXCAVATION IN SOIL	186 LF		
0162	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	54 LF		
0163	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	15,130 SF		
0164	8161000000-E	420	GROOVING BRIDGE FLOORS	16,030 SF		
0165	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	193 CY		
0166	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (31+81.71-L-)	Lump Sum	L.S.	
0167	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,497 LB		
0168	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	1,218,200 LS		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0169	8384000000-E	450	HP14X73 STEEL PILES	1,440 LF		
0170	8503000000-E	460	CONCRETE BARRIER RAIL	494.04 LF		
0171	8531000000-E	462	4" SLOPE PROTECTION	53 SY		
0172	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0173	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1405/Jun05/Q1400585.74/D731208930000/E173			Total Amount Of Bid For Entire Project :			

Contract No **C201876**

County (ies): **Guilford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General