

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

STATE PROJECT REFERENCE NO. SHEET NO.

B-4132

TCP-1

PLAN FOR PROPOSED
TRAFFIC CONTROL, MARKING & DELINEATION

HALIFAX COUNTY

B-4132

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS"-
PROJECT SERVICES UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C.,
DATED JULY 2006 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE
CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.03	TEMPORARY ROAD CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1110.01	STATIONARY WORK ZONE SIGNS
1145.01	BARRICADES - TYPE III
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE AND MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	PAVEMENT MARKER SPACING
1251.01	RAISED PAVEMENT MARKERS - TEMPORARY AND PERMANENT
1261.01	GUARDRAIL AND BARRIER DELINEATOR SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATOR TYPES
1262.01	GUARDRAIL END DELINEATION

INDEX OF SHEETS

SHEET NO.	TITLE
TCP-1	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, INDEX OF SHEETS, LEGEND, AND PAVEMENT MARKING SCHEDULE
TCP-2	PROJECT NOTES, LOCAL NOTES, AND PHASING
TCP-3 & 4	OFF-SITE DETOUR

LEGEND

GENERAL

- DIRECTION OF TRAFFIC FLOW
- NORTH ARROW
- PROPOSED PVMT. EXIST. PVMT.
- WORK AREA
- REMOVAL OF EXISTING PAVEMENT

TRAFFIC CONTROL DEVICES

- TYPE I BARRICADE
- TYPE II BARRICADE
- TYPE III BARRICADE
- CONE
- DRUM SKINNY DRUM
- FLASHING ARROW PANEL (TYPE C)
- STATIONARY SIGN
- PORTABLE SIGN
- STATIONARY OR PORTABLE SIGN
- CRASH CUSHION
- CHANGEABLE MESSAGE SIGN
- TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
- POLICE
- FLAGGER

PAVEMENT MARKINGS

- CRYSTAL/CRYSTAL PAVEMENT MARKER
- YELLOW/YELLOW PAVEMENT MARKER
- CRYSTAL/RED PAVEMENT MARKER
- PAVEMENT MARKING SYMBOLS

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY	BREAKDOWN	TOTAL QUANTITY
PAVEMENT MARKINGS					
VA	WHITE EDGELINE	1630	LF		
VI	YELLOW DOUBLE CENTER	1630	LF		
				TOTAL	3260 LF
PAVEMENT MARKERS					
MA	YELLOW & YELLOW	10	EA		
				TOTAL	10 EA

31-MAR-2008 08:42 \\dot\gfsr\oot\01\Proj\Store\Proj\Hiprojects-b\4132\Traffic\Trafficcontrol\top\b-4132-tc-top-01.dgn dwb\issette AT WZTC237500

TIP PROJECT:

APPROVED:
DATE: 3/31/08

SEAL

PLAN PREPARED BY: N.C.D.O.T. WORK ZONE TRAFFIC CONTROL UNIT

J. S. BOURNE, P.E. TRAFFIC CONTROL ENGINEER

J. S. KITE, P.E. TRAFFIC CONTROL PROJECT ENGINEER

J. D. KUSE, P.E. TRAFFIC CONTROL PROJECT DESIGN ENGINEER

D. W. BISSETTE, P.E. TRAFFIC CONTROL DESIGN ENGINEER / TECHNICIAN

PROJECT NOTES

PROJ. REFERENCE NO.	SHEET NO.
B-4132	TCP-2

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS, OR RESULT IN DUPLICATE, OR UNDESIRABLE OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING OR REMOVAL OF DEVICES, AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

PAVEMENT EDGE DROP OFF REQUIREMENTS

A) BACKFILL AT A 6:1 SLOPE UP TO THE EDGE AND ELEVATION OF EXISTING PAVEMENT IN AREAS ADJACENT TO AN OPENED TRAVEL LANE THAT HAS AN EDGE OF PAVEMENT DROP-OFF AS FOLLOWS:

BACKFILL DROP-OFFS THAT EXCEED 2 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS OF 45 MPH OR GREATER.

BACKFILL DROP-OFFS THAT EXCEED 3 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS LESS THAN 45 MPH.

BACKFILL WITH SUITABLE COMPACTED MATERIAL, AS APPROVED BY THE ENGINEER, AT NO EXPENSE TO THE DEPARTMENT.

B) DO NOT EXCEED A DIFFERENCE OF 2 INCHES IN ELEVATION BETWEEN OPEN LANES OF TRAFFIC FOR NOMINAL LIFTS OF 1.5 INCHES. INSTALL ADVANCE WARNING "UNEVEN LANES" SIGNS (W8-11) IN ADVANCE AND A MINIMUM OF EVERY HALF MILE THROUGHOUT THE UNEVEN AREA.

TRAFFIC PATTERN ALTERATIONS

C) NOTIFY THE ENGINEER TWENTY ONE (21) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

D) INSTALL ADVANCE WORK ZONE WARNING SIGNS NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.

E) PROVIDE PERMANENT SIGNING.

F) PROVIDE DETOUR SIGNING WITHIN AND OFF THE PROJECT LIMITS.

G) COVER OR REMOVE ALL DETOUR SIGNS WITHIN AND OFF THE PROJECT LIMITS WHEN A DETOUR IS NOT IN OPERATION.

H) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC CONTROL DEVICES

I) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.

PAVEMENT MARKINGS AND MARKERS

J) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
NC 561	POLYUREA	RAISED REFLECTIVE

K) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.




LOCAL NOTES

1. PROVIDE ADVANCED NOTICE OF ROAD CLOSURE FOR NC 561 TO HALIFAX COUNTY EMERGENCY MANAGEMENT SERVICES AND TO THE HALIFAX COUNTY SCHOOL TRANSPORTATION OFFICE IN ORDER FOR THEM TO FACILITATE THEIR SERVICES DURING CONSTRUCTION.
2. INSTALL SIGNS BEFORE THE BARRICADES WHEN CLOSING THE ROADWAY TO TRAFFIC. REMOVE BARRICADES BEFORE THE SIGNS WHEN OPENING THE ROADWAY TO TRAFFIC. INSTALL/REMOVE SIGNS AND BARRICADES WITHIN THE SAME CALENDAR DAY.
3. ALL SIGN SPACING DIMENSIONS ARE APPROXIMATE, FIELD ADJUST AS NECESSARY OR AS DIRECTED.
4. MAINTAIN DRIVEWAY ACCESS WITHIN PROJECT LIMITS USING INCIDENTAL STONE.
5. USE FLAGGERS AS NEEDED TO MAINTAIN LOCAL TRAFFIC WITHIN ROAD CLOSURE. FLAGGING WILL BE INCIDENTAL TO THE COST OF THE CONTRACT.
6. REAPPLY PAVEMENT MARKINGS UP TO 100' BEYOND CONSTRUCTION LIMITS IF NEEDED TO REPAIR DAMAGE AND/OR TRACKING FROM CONSTRUCTION.

PHASING



- STEP 1 INSTALL SIGNS AND BARRICADES CLOSING NC 561 TO THROUGH TRAFFIC AS SHOWN ON TCP-3 AND TCP-4 AND IN ACCORDANCE WITH ROADWAY STANDARD DRAWING 1101.03, SHEET 1 OF 9 AND ROADWAY STANDARD DRAWING 1145.01, SHEET 1 OF 1. (SEE LOCAL NOTES NO. 1, 2 AND 3)
- STEP 2 CONSTRUCT THE FOLLOWING WITHIN THE ROAD CLOSURE: (SEE LOCAL NOTES NO. 4 AND 5)
 - REMOVE THE EXISTING STRUCTURE
 - CONSTRUCT THE PROPOSED STRUCTURE
 - CONSTRUCT THE PROPOSED ROADWAY SECTION -L- UP TO BUT NOT INCLUDING THE FINAL LAYER OF SURFACE FROM STA. 12+35+/- TO STA. 15+95+/- AND FROM STA. 17+00+/- TO STA. 20+50+/-
- STEP 3 PLACE THE FINAL LAYER OF SURFACE COURSE FROM STA. 12+35+/- TO STA. 15+95+/- AND FROM STA. 17+00+/- TO STA. 20+50+/- AND APPLY THE FINAL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON -L- FROM STA. 12+35+/- TO STA. 20+50+/- . (SEE LOCAL NOTE NO. 6)
- STEP 4 REMOVE ALL BARRICADES, ROAD CLOSED SIGNS AND DETOUR SIGNS AND OPEN SR 1151 TO THROUGH TRAFFIC. (SEE LOCAL NOTE NO. 2)




3-MAR-2008 08:45 \\dot\dfs\dot\proj\projstore\proj\tip\projects\b\4132\traffic\trafficcontrol\tcp\b-4132.tc.tcp.02.dgn AT WZTC237500 dwbissette

APPROVED: 	DATE: 3/31/08	PROJECT NOTES	
	SCALE: NONE		REVISIONS
	DATE: 03/08		
	DWG. BY: DWB		
	DESIGN BY: DWB		
REVIEWED BY: JDK			



31-MAR-2008 08:50
 \\dot\dfsroot\01\ProjStore\Proj\Tpp\projects-b\4132\traffic\trafficcontrol\top\b-4132-tc-top_03.dgn
 dwbiessette AT WZTC237500

APPROVED: 	DATE: 3/31/08	OFF-SITE DETOUR									
											
SCALE: NONE DATE: 03/08 DWG. BY: DWB DESIGN BY: DWB REVIEWED BY: JDK		<table border="1"> <thead> <tr> <th colspan="2">REVISIONS</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </tbody> </table>		REVISIONS							
REVISIONS											



*BARRICADES USED TO CLOSE A ROADWAY SHALL EXTEND ACROSS THE ENTIRE ROADWAY. WHERE LOCAL TRAFFIC MUST BE MAINTAINED, THEY MAY BE PLACED IN A STAGGERED POSITION.

APPROVED:	DATE: 3/31/08	OFF-SITE DETOUR																					
<table border="1"> <tr> <td>SCALE:</td> <td>NONE</td> <td rowspan="4" style="text-align: center;"> </td> <td rowspan="4"> <table border="1"> <tr><th colspan="2">REVISIONS</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table> </td> </tr> <tr> <td>DATE:</td> <td>03/08</td> </tr> <tr> <td>DESIGN BY:</td> <td>DWB</td> </tr> <tr> <td>REVIEWED BY:</td> <td>JDK</td> </tr> </table>		SCALE:	NONE		<table border="1"> <tr><th colspan="2">REVISIONS</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>	REVISIONS								DATE:	03/08	DESIGN BY:	DWB	REVIEWED BY:	JDK	<table border="1"> <tr> <td>CADD FILE</td> <td> </td> </tr> </table>		CADD FILE	
SCALE:	NONE		<table border="1"> <tr><th colspan="2">REVISIONS</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>			REVISIONS																	
REVISIONS																							
DATE:	03/08																						
DESIGN BY:	DWB																						
REVIEWED BY:	JDK																						
CADD FILE																							

31-MAR-2008 09:05
 \\dot\dfs\0010\ProjStore\Proj\Tpp\projects-b\4132\tr\aff\tr\aff\control\top\b-4132-fc-top_04.dgn
 AT WZTC237500
 dwbissette