

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+47.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	144 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0014	0995000000-E	340	PIPE REMOVAL	20 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	334 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	368 TON		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	39 TON		
001E	2000000000-N	806	RIGHT OF WAY MARKERS	19 EA		
002C	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	117 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
003C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	51 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	266 SY		
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	14 LF		
003E	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	9	EA	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	287	SF	
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144	SF	
004C	4445000000-E	1145	BARRICADES (TYPE III)	112	LF	
0041	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	3,260	LF	
0042	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10	EA	
0043	5325800000-E	1510	8" WATER LINE	396	LF	
0044	5801000000-E	1530	ABANDON 8" UTILITY PIPE	379	LF	
004E	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	150	LF	
004E	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	100	LF	
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,170	LF	
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180	TON	
005C	6012000000-E	1610	SEDIMENT CONTROL STONE	60	TON	
0051	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
005E	6029000000-E	SP	SAFETY FENCE	250	LF	
0057	6030000000-E	1630	SILT EXCAVATION	390	CY	
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	730	SY	
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	40	LF	
006C	6071030000-E	SP	COIR FIBER BAFFLES	180	LF	
0061	6084000000-E	1660	SEEDING & MULCHING	2	ACR	
0062	6087000000-E	1660	MOWING	1.5	ACR	
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5	TON	
0067	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

STRUCTURE ITEMS

006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+47.50 -L-)	Lump Sum	L.S.	
007C	8112730000-N	SP	PDA TESTING	1	EA	
0071	8112740000-N	SP	PDA ASSISTANCE	1	EA	

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+47.50 -L-)	Lump Sum	L.S.	
0073	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,789 SF		
0074	8161000000-E	420	GROOVING BRIDGE FLOORS	3,884 SF		
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	46.6 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+47.50 -L-)	Lump Sum	L.S.	
0077	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,546 LB		
0078	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	184,450 LS		
0079	8364000000-E	450	HP12X53 STEEL PILES	1,200 LF		
0080	8393000000-N	450	PILE REDRIVES	8 EA		
0081	8503000000-E	460	CONCRETE BARRIER RAIL	210 LF		
0082	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	330 TON		
0083	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	370 SY		
0084	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1555/May29/Q211879.35/D375702410000/E84

Total Amount Of Bid For Entire Project :

Contract No **C201869**

County (ies): **Halifax**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General