

**PROJECT SPECIAL PROVISIONS**

**ROADWAY**

**FIELD OFFICE (Lump Sum):**

(6-1-07)

SPI

**Description**

This work consists of furnishing, erecting, equipping, and maintaining a field office for the exclusive use of Department Engineers and Inspectors at a location on the project approved by the Engineer. Provide a field office that complies with the current A.D.A. Design and Accessibility Standards, the National Electric Code, local, state, and federal regulations, and the following:

**Procedures**

The field office and equipment shall remain the property of the Contractor upon completion of the contract. The field office must be separated from buildings and trailers used by the Contractor and be erected and functional as an initial operation. Failure to have the field office functional when work first begins on the project will result in withholding payment of the Contractor's monthly progress estimate. The field office must be operational throughout the duration of the project and be removed upon completion and final acceptance of the project.

Provide a field office that is weatherproof, tightly floored and roofed, constructed with an air space above the ceiling for ventilation, supported above the ground, has a width of at least 10 feet, and the floor-to-ceiling height that is at least 7 feet 6 inches. Provide inside walls and a ceiling that are constructed of plywood, masonite, gypsum board, or other suitable materials. Have the exterior walls, ceiling, and floor insulated.

Provide a field office with a minimum floor space of 500 square feet and that is equipped with the following:

<b><u>Number</u></b>	<b><u>Item</u></b>
1	Double-pedestal desk (approximately 60 by 34 inches, at least 2,000 square inches).
1	Plan and drafting table (approximately 30 by 96 inches) with adjustable stool.
1	Computer table having a minimum size of 48 by 30 by 29 inches.
1	Plan rack for 24 by 36 inch drawings with 6 plan clamps.
1	Printing calculator.
2	2-drawer fire protection file, 15 inch drawer width, minimum UL rating of Class 350.
6	Office chairs with a minimum of two having casters.
2	Wastebaskets.
1	Pencil sharpener.
1	Copy machine (8 inch x 11 inch copies)
1	Telephone.
1	Fax Machine.
1	Answering machine.

**Windows and Doors**

Provide a field office with at least three windows, with blinds, each having an area of at least 540 square inches, capable of being easily opened and secured from the inside and having at least two exterior passage doors. Provide doors at least 30 inches in width and 78 inches in height. Provide screens for windows and doors. Equip exterior passage door(s) with lock(s), and furnish at least two keys to the Engineer or inspector.

**Steps**

Provide accessibility in compliance with the current A. D. A. Design and Accessibility Standards, and the State Building Code and maintain them free from obstructions.

**Storage Facility For Nuclear Gage**

Furnish the field office with an outside storage facility for the Department's nuclear gage. The storage facility shall not be located within 10 feet of any other structure including the field office.

**Lighting, Heating, and Air Conditioning**

The field office must have satisfactory lighting, electrical outlets, heating equipment, an exhaust fan, and an air conditioner connected to an operational power source. Provide at least one of the light fixtures that is a fluorescent light situated over the plan and drafting table. Furnish electrical current and fuel for heating equipment.

**Fire Extinguishers**

Furnish and maintain one fire extinguisher for each required exterior passage door. Fire extinguisher(s) may be chemical or dry powder. UL Classification 10-B:C (minimum), suitable for Type A:B:C: fires. Mount and maintain fire extinguisher(s) in accordance with OSHA Safety and Health Standards.

**Toilets**

Provide a toilet conforming to the requirements of the state and local boards of health or other bodies or courts having jurisdiction in the area. When separate facilities for men and women are not available, place a sign with the words "Rest Room" (with letters at least 1 inch in height) over the doorway, and provide an adequate positive locking system on the inside of the doorway. Maintain responsibility for the water and sewer connections or the installation and connection of a water well and septic tank and drain field. These facilities must conform to all local and state permits.

**Utilities**

Except for telephone service, make arrangement for necessary utility connections, maintain utilities, pay utility service fees and bills, and make arrangements for final disconnection of utilities. Furnish a telephone in each field office and permit the work necessary to install it.

**Storage Facility for Test Equipment**

Provide the field office with a storage facility, separate from the office for storage of test equipment, other than the nuclear gage. Provide a facility that has a minimum floor space of 64 square feet, is weatherproof, tightly floored and roofed, and has a tamper resistant key operated lock.

**Miscellaneous Items**

The field office must also include the following:

1. A certification that the office is free of asbestos and other hazardous materials.
2. A broom, dust pan, mop and bucket, and general cleaning supplies.
3. Provide and maintain an all weather parking area for six vehicles, including graveled access to the paved surface.

**Measurement and Payment**

Payment at the contract lump sum bid price for *Field Office* will be full compensation for all work covered by this provision including but not limited to furnishing, erecting, maintaining, and removing the field office as outlined in this provision.

Installation and service fees for the telephone will be paid for by the Department.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Field Office	Lump Sum

**CLEARING AND GRUBBING – METHOD II:**

(9-17-02) (Rev 3-18-08)

M2 R01

Perform clearing on this project to the limits established by Method “II” shown on Standard No. 200.02 of the *2006 Metric Roadway Standard Drawings*.

Revise the *2006 Metric Standard Specifications* as follows:

**Page 2-2, Article 200-3, Clearing, add the following as the 6th paragraph:**

At bridge sites, clear the entire width of the right of way beginning at a station 1 m back of the beginning extremity of the structure and ending at a station 1 m beyond the ending extremity of the structure.

**CLASS VII ROCK EMBANKMENT CONSTRUCTION****1.0 GENERAL**

Construct rock embankments using Class VII Select Material in accordance with Section 235 of the *Standard Specifications*, the detail shown on the wall plans and the following provisions:

**2.0 MATERIALS**

Use earth material, project derived Class VII Select Material, and Class VI Select Material to construct the rock embankments as detailed in the plans and located between Station 100+80-L- and 103+80-L-, or as directed by the Engineer.

The rock shall meet the following requirements:

- a. Class VII in accordance with Article 1016-3 of the *Standard Specifications*.
- b. No rippable rock will be permitted in the embankments.
- c. Density requirements will not apply to Class VII roadway embankment construction.

The Class VI Select Material shall meet the requirements of Section 1016-3, Class VI; or material meeting gradation requirements standard size 57 in of Table 1005-1 as described in section 1005 and 1006.

**3.0 COMPENSATION**

No additional compensation will be made for any requirements for furnishing and placing Class VII or earth materials as the cost of such work shall be included in the contract unit price per cubic meter for *Unclassified Excavation*.

The quantity to be paid for will be the actual number of metric tons of Class VI Select Material that has been incorporated into the completed and accepted work. The material will be measured by being weighed in trucks on certified platform scales or other certified weighing devices. This work includes but is not limited to furnishing, hauling, handling, placing, compacting and maintaining the Class VI material for the rock embankment.

Separation Fabric for Rock Embankment, will be Type 2 Fabric as described in Section 1056, Table 1056-1 will be measured and paid for as square meters, as measured along the surface of the ground that has been acceptably placed. No separate measurement will be made for overlapping fabric, sewing seams or bonding. Work includes but is not limited to furnishing, hauling, placing, and sewing the fabric and furnishing and placing wire staples.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Class VI Material for Rock Embankment	Metric Ton
Separation Fabric for Rock Embankment	Sq. Meter

### **ROCK BLASTING:**

**(SPECIAL)**

#### **Description**

This project special provision governs fracturing rock for excavation and constructing stable rock cut slopes using controlled, production and trench blasting. Controlled blasting is used to form a certain slope by limiting the effects of blasting with cushion or trim blasting. Another type of controlled blasting known as presplitting is not addressed by this provision. Production blasting is used to fracture rock in manageable sizes for excavation. Trench blasting is used to create trenches in rock for utilities and pipes and construct open ditches. This provision also addresses secondary blasting and blasting adjacent to highway structures in lieu of Article 410-11 of the *Standard Specifications*.

Exercise care when using bulk ammonium nitrate and fuel oil (ANFO) near open water to prevent ANFO from leaching into lakes, streams, creeks and rivers. Control blasting to avoid damaging public and private property. Contain flyrock in the construction limits or perform blasting such that no flyrock occurs if required in the "Project Requirements" section of this provision. When blasting in the vicinity of an open travelway, have equipment standing by to remove material that interferes with traffic flow.

Perform rock blasting, develop blast plans, provide explosive materials, drill, load and stem holes, record drilling, conduct blast surveys, monitor blasts and submit drilling records, surveys and reports in accordance with the Contract and accepted submittals.

#### **Project Requirements**

At a minimum, conduct pre-blast surveys for any building, residence or utility when the maximum charge per delay ( $W_{max}$ ) and the distance to the subject structure (D) may result in a peak particle velocity (PPV) equal to or greater than 0.4 in/sec (10 mm/sec) using the formulas in the "Peak Particle Velocity and Scaled Distance" section of this provision.

Blasting is subject to the "USBM Alternative Blasting Level Criteria" from the ISEE Blasters' Handbook, 17<sup>th</sup> Edition for not-to-exceed limits. Warning levels for vibration are 0.25 in/sec

(6 mm/sec) less than the not-to-exceed limits. For air-overpressure (noise), blasting is subject to a not-to-exceed limit of 133 dBL and a warning level of 120 dBL.

Design and perform rock blasting such that no flyrock occurs. If flyrock occurs, the Engineer may suspend blasting operations in accordance with Article 108-7 of the Standard Specifications and require test blasts and a revised general blast plan.

### **Definitions**

*Air-Overpressure or Air Blast (Noise)* – The pulsating pressure changes above and below ambient air pressure generated by an explosion. Air-overpressure “linear scale” measurements include low frequency noise with a 2 hertz (Hz) response and are expressed in units of decibels-L (dBL).

*Blast Pattern* – A plan of blast hole locations or an expression of the burden and spacing distance and their relationship to each other.

*Burden* – The amount of rock broken by an explosive charge measured as the distance between the blast hole and the nearest free face.

*Charge per Delay (W)* – The sum of all charge weights firing within any 8 milliseconds (ms) time period. For example, if two 10 lb (4.5 kg) charges fire at 100 ms and one 15 lb (6.8 kg) charge fires at 105 ms, the charge per delay would be 35 lbs (15.8 kg).

*Cushion or Trim Blasting* – A controlled blasting technique in which a line of blast holes along a rock face are detonated during the last delay period of the blast. The main burden is moved from the face by production blast holes leaving only a small burden to be removed by the line of blast holes at the face. Charges in these holes are lighter than charges in the production blast holes.

*Deck Loading (Decking)* – A method of loading blast holes in which two or more explosive charges, called decks or deck charges, are loaded in the same hole separated by stemming or an air cushion.

*Delay Blasting* – The practice of initiating individual explosive decks, blast holes or rows of holes at predetermined time intervals using delays or delay detonators as compared to firing all blast holes simultaneously.

*Flyrock* – Rocks propelled through the air by the force of an explosion.

*Free Face* – A rock surface exposed to air or water that provides room for expansion upon fragmentation.

*Magazine* – Any building, structure or container, approved for storage of explosive materials other than an explosive manufacturing building.

*Misfire* – An event where all or some charges in a blast fail (do not detonate) when initiated or a term for any portion of explosive materials that fail to detonate as planned.

*Peak Particle Velocity (PPV)* – The maximum ground vibration velocity measured in the vertical, longitudinal or transverse direction. PPV measurement units are expressed in inches or millimeters per second (in/sec or mm/sec).

*Scaled Distance (Ds)* – A calculated value in units of  $\text{ft}/\text{lb}^{0.5}$  ( $\text{m}/\text{kg}^{0.5}$ ) describing relative vibration energy based on distance to a structure (D) and charge per delay (W). Ds is equal to D divided by the square root of W,  $D_s = D / W^{0.5}$  or  $W = (D / D_s)^2$ .

*Spacing* – The distance between blast holes in a row. In production blasting, the distance is measured parallel to the free face and perpendicular to the burden.

*Stemming* – Crushed stone placed in the unloaded collar area of blast holes for the purpose of confining explosive charges and limiting rock movement and air-overpressure.

*Subdrilling* – The portion of a blast hole that is drilled below or beyond the desired excavation depth or limit. Subdrilling is generally required to prevent the occurrence of high or tight areas of unfractured rock between blast holes.

## Regulations

Comply with all the latest applicable Federal, State and local codes, laws, rules and regulations as well as professional society standards for the storage, transportation and use of explosives. These include but are not limited to the following:

- The Occupational Safety and Health (OSH) Act of 1970 and the Construction Safety Act (CSA) of 1969, as amended
- Safe Explosives Act, Title XI, Subtitle C of Public Law 107-296; Interim Final Rule
- Title 29, U. S. Code, Section 651 et seq., including safety and health regulations for construction
- Title 27, Code of Federal Regulations (27 CFR), Part 555, U. S. Department of Justice, Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF)
- Organized Crime Control Act of 1970, Title XI, Public Law 91-452, as amended
- Title 49, Code of Federal Regulations (49 CFR), Parts 105-177 (DOT RSPA) & Parts 301-399 (DOT FHA)
- Title 29, Code of Federal Regulations (29 CFR), Parts 1910 & 1926, N. C. Department of Labor, Division of Occupational Safety and Health
- The Mining Act of 1971, North Carolina General Statute, Chapter 74, Article 7, as amended
- Fire Code of North Carolina, Section 105.6.15 Explosives
- Administrative Rules, 13 NCAC 06.0521 – 13 NCAC 06.0526, N. C. Department of Labor
- “A Guide to the Safe Storage of Explosive Materials” and “North Carolina Occupational Safety and Health Standards in Construction for Blasting & Use of Explosives”, N. C. Department of Labor

Keep a copy of all regulations listed above at the project site.

Non-regulatory Industry Support Organizations:

- Blast Monitoring Equipment Operation Standards (1999), Vibration Subcommittee of the International Society of Explosive Engineers (ISEE)

- Institute of Makers of Explosives (IME) Safety Library Publications (SLPs)

In case of conflict, the more stringent regulation applies.

### Submittals

In lieu of a blasting plan in accordance with Article 107-11 of the *Standard Specifications*, the following submittals are required for rock blasting.

- Blasting Contractor Personnel and Experience including Blasting Consultant, if applicable
- General Blast Plan including Blast Monitoring Consultant, if applicable
- Site Specific Blast Plans including Pre-blast Surveys
- Post-blast Reports including Drilling Records, Blast Monitoring Report and Blast Damage Report, when necessary

For the site specific blast plans and post-blast reports, submit two hard copies of each to the Resident Engineer. After completing all blasting for a cut, structure or an excavation, submit electronic copies (pdf or jpg format on CD or DVD) of all site specific blast plans and post-blast reports.

Allow 30 calendar days upon receipt by the Department for the review and acceptance of the Blasting Contractor personnel and experience and general blast plan. Provide these submittals in both electronic and hard copy form in accordance with the following:

Submit one hard copy to the Resident Engineer. At the same time, submit a second hard copy and an electronic copy (pdf or jpg format on CD or DVD) directly to the Geotechnical Engineering Unit at the following addresses:

**For projects in Divisions 1-7, use the following Eastern Regional Office addresses:**

Via US mail:  
 Eastern Regional Geotechnical Manager  
 North Carolina Department of  
 Transportation  
 Geotechnical Engineering Unit  
 Eastern Regional Office  
 1570 Mail Service Center  
 Raleigh, NC 27699-1570

Via other delivery service:  
 Eastern Regional Geotechnical Manager  
 North Carolina Department of  
 Transportation  
 Geotechnical Engineering Unit  
 Eastern Regional Office  
 3301 Jones Sausage Road, Suite 100  
 Garner, NC 27529

**For projects in Divisions 8-14, use the following Western Regional Office addresses:**

Via US mail:  
 Western Regional Geotechnical Manager  
 North Carolina Department of  
 Transportation  
 Geotechnical Engineering Unit  
 Western Regional Office  
 5253 Z Max Boulevard  
 Harrisburg, NC 28075

Via other delivery service:  
 Western Region Geotechnical Manager  
 North Carolina Department of  
 Transportation  
 Geotechnical Engineering Unit  
 Western Regional Office  
 5253 Z Max Boulevard  
 Harrisburg, NC 28075



The Engineer may suspend blasting operations in accordance with Article 108-7 of the *Standard Specifications* if submittals are illegible, incomplete or not provided.

**(A) Blasting Contractor Personnel and Experience**

The Engineer may waive this submittal if a Blasting Consultant is not required and the Blasting Contractor and Blaster-in-Charge for this project were previously accepted within the last year for another NCDOT project with subsurface conditions and blasting of a scope and complexity similar to that anticipated for this project.

Obtain acceptance of the Blasting Contractor personnel and experience before submitting a general blast plan.

**(1) Blasting Contractor**

Use a Blasting Contractor prequalified by the NCDOT Construction Unit for rock blasting work (work code 070). Submit documentation that the Blasting Contractor has successfully completed at least 5 blasting projects within the last 3 years with subsurface conditions and blasting of a scope and complexity similar to that anticipated for this project. Documentation should include the General Contractor and Owner's name and current contact information with descriptions of each past project.

**(2) Blaster-in-Charge**

The Blaster-in-Charge has total authority over the handling, use and security of explosives and is responsible for coordinating, planning and supervising explosives use. The Blaster-in-Charge is also responsible for designing blasts and preparing blast plans when a Blasting Consultant is not required and for monitoring blasts when a Blast Monitoring Consultant is not required. Either the Blaster-in-Charge or an alternate Blaster-in-Charge is required to be on-site during blasting.

Submit documentation that the Blaster-in-Charge and any alternate Blasters-in-Charge have a minimum of 5 years experience in blasting with past projects of scope and complexity similar to that anticipated for this project. Documentation should include resumes, references, certifications, project lists, experience descriptions and details, etc. If there is a change in the Blaster-in-Charge, discontinue explosives use until a new Blaster-in-Charge is submitted and accepted.

**(3) Blasting Consultant**

When a Blasting Consultant is required in the "Project Requirements" section of this provision, use an independent consultant prequalified by the NCDOT Construction Unit for the rock blasting evaluation & design discipline (disc code

00304). Employees of the Contractor, any affiliated companies or product suppliers are not allowed to be independent consultants.

Submit documentation that the Blasting Consultant is registered as a Professional Engineer in North Carolina and has at least 10 years experience in designing blasts and preparing blast plans for projects with subsurface conditions and blasting of a scope and complexity similar to that anticipated for this project. Documentation should include resumes, references, certifications, project lists, experience descriptions and details, etc.

**(B) Blast Plans**

Blast plans are required to be signed by the Blaster-in-Charge (and Blasting Consultant, if applicable). Review and acceptance of blast plans does not relieve the Contractor of responsibility for the blast results or liability in accordance with Articles 107-11 and 107-12 of the *Standard Specifications*.

**(1) General Blast Plan**

Submit a general blast plan before beginning drilling, when revised drilling or blasting methods are proposed or as directed by the Engineer. At a minimum, include the following in the plan:

- Work procedures and safety precautions for the storage, transportation, handling and detonation of explosives
- Explosive products and devices for dry and wet blast holes including explosives, primers and detonators with material safety data sheets
- Drilling equipment and methods for maintaining blast hole alignment
- Typical plan, profile and sectional views for both production and controlled blasting showing hole diameter, depth, inclination and spacing, maximum blast limits, burden, subdrill depth and maximum charge per delay
- Initiation and delay methods and delay times
- Site specific blast plan format
- Blast hole drill log format
- Pre-blast survey criteria and method
- Blast monitoring report format and equipment including calibration information
- Post-blast report format
- Blast Monitoring Consultant, if applicable
- Test blast locations when required

Do not deliver explosives to the project site until the general blast plan is reviewed and accepted.

**(2) Site Specific Blast Plan**

After the general blast plan is accepted, submit a site specific blast plan at least 24 hours in advance of each blast. Site specific blast plans may be waived for non-

critical blasts as determined by the Engineer. The following is required for the plan:

- Scaled drawings of the blast area with cross-sections showing the beginning and ending stations, hole diameter, depth, inclination, spacing, burden, subdrill depth and free face location and any joints, bedding planes, weathered zones, voids or other significant rock structure that may influence the blast
- A loading pattern diagram showing the location and amount of each type of explosive including primers and detonators
- The locations and depths of stemming, column heights and maximum charge per delay for each type of loading
- A delay and initiation diagram showing delay pattern, sequence and times
- Pre-blast surveys (once per structure; not required when submitted for a prior blast)

For site specific blast plans do not exceed the maximum charge per delay accepted in the general blast plan or submit a revised general blast plan to increase the maximum charge per delay allowed.

**(C) Pre-blast Surveys and Post-blast Reports**

**(1) Blast Monitoring Consultant**

When a Blast Monitoring Consultant is required in the “Project Requirements” section of this provision, use an independent consultant prequalified by the NCDOT Construction Unit for vibration & noise monitoring work (work code 3120). Employees of the Contractor, any affiliated companies or product suppliers are not allowed to be independent consultants.

**(2) Peak Particle Velocity and Scaled Distance**

Use the following formulas to determine peak particle velocity (PPV) and scaled distance (Ds).

$$PPV = K(Ds)^m \qquad \text{and} \qquad Ds = D / (W_{max})^{0.5}$$

- where:
- PPV = Peak Particle Velocity (in/sec or mm/sec)
  - K and m = Site specific constants defining initial energy and decay
  - Ds = Scaled Distance (ft/lb<sup>0.5</sup> or m/kg<sup>0.5</sup>)
  - D = Distance to subject structure (ft or m)
  - W<sub>max</sub> = Maximum charge per delay (lbs or kg)

Typically, a K of 240 (1725 for metric units) and an m of -1.6 may be used for the equations above. However, K and m are site specific and may be determined by performing a regression analysis of multiple PPV and Ds data pairs. Select K and m based on actual site conditions, rock type and structure, subsurface information and blast monitoring measurements.

**(3) Pre-blast Survey**

Conduct pre-blast surveys in accordance with the “Project Requirements” section of this provision and the accepted general blast plan. At a minimum, include the following in the survey:

- Summary naming the person who performed the survey and comments about each structure and existing condition
- Sketches of interior and exterior walls and foundations with existing cracks and a written description of the cracks including the length, width, type and angle
- 4 x 6 inch (100 x 150 mm) color 35-mm or 5-megapixel digital photographs or miniDV or DVD digital video documenting the existing cracks and condition of each structure

Submit pre-blast surveys with site specific blast plans.

**(4) Post-blast Report**

Within 3 days after each blast or before the next blast, whichever is sooner, submit a post-blast report signed by the Blaster-in-Charge that includes the following:

- Results and effectiveness of the blast and any proposed changes to subsequent site specific blast plans
- Blast monitoring report
- Blast damage report when necessary
- Drilling records including blast pattern and blast hole drill logs

**(a) Blast Monitoring**

At a minimum, monitor vibration and air-overpressure (noise) at the nearest building, residence or utility and the nearest building, residence or utility in the direction of the blast in accordance with the accepted general blast plan. Furnish seismographs capable of measuring particle velocities in the longitudinal, vertical and horizontal directions. Use monitoring equipment calibrated within one year of the date the data is collected. Interpret the recorded data and submit a blast monitoring report signed by the Blaster-in-Charge (or Blast Monitoring Consultant, if applicable) with the post-blast report that includes the following for each monitoring location:

- Type, identification and specific location of monitoring equipment
- Distance and direction to blast
- PPV in each direction and peak vector sum
- Maximum air-overpressure

If damage occurs from blasting, notify the Engineer immediately. Submit a blast damage report signed by the Blaster-in-Charge (and Blast Monitoring Consultant, if applicable) with the post-blast report that includes the following:

- Property owner's (and injured person's, if any) names, addresses and telephone numbers
- Details and description of property damage (and injury, if any) with photos or video
- Any associated tort claims, complaint letters and other applicable information

**(b) Drilling Records**

Identify each blast hole with a number on a blast pattern. Log the hole number, total depth, date drilled and the depth and description of significant conditions encountered such as water, voids and weak or jointed seams. Submit the blast pattern and blast hole drill logs signed by the Driller with the post-blast report.

**Blast Design Requirements**

**(A) Vibration and Air-overpressure**

Design blasts for the vibration and air-overpressure (noise) warning levels and not-to-exceed limits in the "Project Requirements" section of this provision. If warning levels are exceeded, the Engineer may require additional monitoring and the Contractor should be aware that future blasts could exceed the not-to-exceed limits. If not-to-exceed limits are exceeded, the Engineer may suspend blasting operations in accordance with Article 108-7 of the *Standard Specifications* and require test blasts and a revised general blast plan.

**(B) Production Blasts**

Design production blasts in accordance with the following unless otherwise approved:

- Maintain a minimum 6 ft (1.8 m) clearance between the production blast holes and final cut slope face
- Diameter of production blast holes may not exceed 6" (150 mm)
- Do not drill production blast holes below the bottom of adjacent controlled blast holes
- Use delay blasting to detonate production blast holes towards a free face

**(C) Controlled Blasts**

Controlled blasts are required for final cut slopes steeper than 2:1 (H:V) when the height of the rock face exceeds 15 ft (4.6 m).

**(1) Cushion Blasts**

Cushion blasts refer to either trim or cushion blasting. Design cushion blasts in accordance with the following unless otherwise approved:

- Diameter of cushion blast holes may not exceed 6" (150 mm)
- Minimize subdrilling to only that required for excavation of the final cut slopes
- Do not subdrill below final grade
- Bench height or lift thickness may not exceed 25 ft (7.6 m)
- Use a maximum of half the charge density and burden of the production blast holes for the cushion blast holes
- Do not use bulk ANFO or any other bulk loaded products
- Fire cushion blast holes after production blast holes with a minimum 25 ms delay

**(D) Trench Blasts**

Design trench blasts in accordance with the following unless otherwise approved:

- Diameter of trench blast holes may not exceed 3" (75 mm)
- Do not use bulk ANFO or any other bulk loaded products
- Use cartridge explosives or other types of explosives specifically designed for trench blasting
- Use a charge diameter  $\frac{1}{2}$  to  $\frac{3}{4}$  inch (13 to 19 mm) less than the diameter of the trench blast holes

**Test Blasts**

A test blast is defined as drilling, blasting and excavation of a test section before beginning or restarting full scale blasting. When a test blast is required in the "Project Requirements" section of this provision or as directed by the Engineer, perform one or more test blasts for both production and controlled blasting (cushion or trim blasting) or trench blasting before beginning full scale blasting. Submit proposed test blast locations with the general blast plan. Also, if the Engineer suspends blasting operations after full scale blasting has begun, one or more test blasts may be required before resuming blasting. When this occurs, inform the Engineer of the test blast locations before submitting any site specific blast plans.

Perform test blasts in accordance with the submittal, blast design and construction requirements except submit site specific blast plans for test blasts 72 hours before beginning drilling. Full scale blasting may not begin or resume until the test blasts are acceptable to the Engineer. The Engineer will not consider whether a test blast is acceptable until the rock face is exposed and the post-blast report is submitted. Examples of results that may be unacceptable include excessive vibration, air-overpressure or flyrock, overbreakage, damage to the final cut slope face and overhangs.

## Construction Methods

Before beginning drilling, conduct a pre-blast meeting to discuss the blasting and monitoring. Schedule this meeting after all blast plans have been accepted. The Resident Engineer, Roadway Construction Engineer, Geotechnical Operations Engineer, Contractor and Blaster-in-Charge (and Blasting Consultant and Blast Monitoring Consultant, if applicable) will attend this pre-blast meeting.

Drill and blast in accordance with site specific blast plans, the general blast plan, and this provision as directed by the Engineer. Use explosives in accordance with all applicable government regulations, professional society standards and manufacturer guidelines and recommendations.

Remove all overburden material along the top of the excavation for a minimum of 30 ft (9.1 m) beyond the blast holes or the end of the cut unless otherwise approved. Inspect the free face to ensure there is adequate burden.

Drill blast holes within 3" (75 mm) of plan location and control drilling to maintain the final cut slope angle. Accurately determine the angle at which the drill steel enters the rock. Cover all blast holes after drilling to prevent unwanted backfill and identify and mark each hole with hole number and depth. Blast holes are required to be free of obstructions the entire depth. Load holes without dislodging material or caving in the blast hole wall. Use standard size nos. 67 and 78M in accordance with Section 1005 of the *Standard Specifications* for stemming. Stem blast holes with diameters of 5" (250 mm) or greater with no. 67 coarse aggregate and blast holes with diameters less than 5" (250 mm) with no. 78M coarse aggregate. Do not stem blast holes with drill cuttings. Matting is required when blasting in close proximity to buildings, residences, utilities, traffic and populated areas. Soil cover may be used in lieu of matting if allowed by the Engineer.

Notify all occupants of residences, businesses and structures in the surrounding area and the Engineer at least 24 hours before blasting. Check for misfires immediately after each blast before signaling all clear. Remove any loose, hanging or potentially dangerous conditions by hand or machine scaling methods. Resume drilling only after scaling is complete.

When the height of a cut requires multiple lifts or benches, offset the controlled blast holes for each subsequent lift the minimum distance necessary to allow for drill equipment clearances. Adjust the alignment of controlled blast holes to account for this offset as well as any drift that occurred in the preceding lift.

The Engineer may suspend blasting operations in accordance with Article 108-7 of the *Standard Specifications* when vibration, air-overpressure or flyrock limits are exceeded, unsatisfactory rock cut slopes are produced or other reasons.

Remove all loose material from final rock faces by scaling. The Contractor is responsible for the final rock face. If blasting damages the final rock face, stabilize the slope at no additional cost to the Department with a method proposed by the Contractor and accepted by the Department.

### **Secondary Blasting**

Secondary blasting is used to reduce the size of naturally occurring boulders or those resulting from initial blasting. Secondary blasting methods include block holing or boulder busting. Block holing or boulder busting is the breaking of boulders by loading and firing small explosive charges in small diameter blast holes. Submit a combined general and site specific blast plan for secondary blasting. The Engineer may waive the pre-blast surveys, blast monitoring and post-blast reports at their discretion.

Mud capping, which is defined as placing an unconfined explosive charge in contact with a rock surface without the use of a blast hole and covering it with mud, is not allowed.

### **Blasting Adjacent to Highway Structures**

Do not blast adjacent to highway structures until the concrete strength reaches 2400 psi (16.5 MPa). When blasting adjacent to highway structures, limit PPV to 4 in/sec (100 mm/sec) measured at a location on the structure nearest the blast. Perform blasting adjacent to highway structures in accordance with the submittal, blast design and construction requirements in this provision.

When blasting for foundation excavation, submit a combined general and site specific blast plan and the Engineer may waive the pre-blast surveys, blast monitoring and post-blast reports at their discretion.

### **Measurement and Payment**

No measurement for rock blasting or scaling will be made. Payment at the contract unit price bid for *Unclassified Excavation* or at the lump sum price bid for *Grading* in accordance with Section 225 or 226 of the *Standard Specifications* will be considered full compensation for all rock blasting or scaling necessary to complete the work in accordance with the contract.

No direct payment for rock blasting will be made for any pipe, utility or foundation excavation. Rock blasting for these items will be considered incidental to the compensation for the required excavation at the various locations. Where no direct payment for excavation is made, the cost for all rock blasting will be considered incidental to the required work and no separate payment for blasting will be made.

No additional payment will be made or extension of contract time allowed when the Engineer suspends blasting operations and requires test blasts, additional monitoring or submittals in accordance with this provision.



**BUILDING AND UNDERGROUND STORAGE TANK REMOVAL:**

(1-1-02) (Rev.6-21-05)

M2 R15

**Building Removal**

Remove the buildings and appurtenances listed below in accordance with Section 215 of the *2006 Metric Standard Specifications* and the following:

Prior to removal of any building, comply with the notification requirements of *Title 40 Code of Federal Regulations*, Part 61, Subpart M, which are applicable to asbestos. Give notification to the North Carolina Department of Health and Human Services, Division of Public Health Epidemiology Branch and/or the appropriate county agency when the county performs enforcement of the Federal Regulation. Submit a copy of the notification to the Engineer prior to the building removal.

Perform removal and disposal of asbestos in accordance with the requirements of *Title 40 Code of Federal Regulations*; comply with all Federal, State and local regulations when performing building removal and/or asbestos removal and disposal. Any fines resulting from violations of any regulation are the sole responsibility of the Contractor and the Contractor agrees to indemnify and hold harmless the Department against any assessment of such fines.

The Department has performed asbestos assessments for building items identified below. Copies of this report may be obtained through the Division Right-of-Way Agent. When asbestos is discovered after the opening of bids for the project, the Engineer may have the work performed by others or the cost of asbestos removal and disposal will be paid for in accordance with Article 104-7 of the *2006 Metric Standard Specifications*. When a building has had or will have asbestos removed and the Contractor elects to remove the building such that it becomes a public area, the Contractor is responsible for any additional costs incurred including final air monitoring.

**Underground Storage Tank Removal**

Prior to removal of any Underground Storage Tank (UST), comply with the notification requirements of the *Title 40 Code of Federal Regulations*, Part 280.71(a). Give notification to the appropriate regional office of the North Carolina Department of Environment and Natural Resources, Division of Waste Management, UST Section. Submit a copy of the notification to the Engineer prior to the removal of the underground storage tank.

Permanently close UST systems by removal and disposal in compliance with the regulations set forth in *Title 40, Code of Federal Regulations*, Part 280.71 and *North Carolina Administrative Code (NCAC)* Title 15A, Chapter 2, Subchapter 2N and any applicable local regulations. Assess Underground Storage Tank sites at closure for the presence of contamination as required in *NCAC* Title 15A, Chapter 2, Subchapter 2N, Section .0803 and as directed by the appropriate Regional Office of the Division of Waste Management. Remove and dispose of UST systems and contents in a safe manner in conformance with requirements of *American Petroleum Institute Bulletin 1604*, Removal and Disposal of Used Underground Petroleum Storage Tanks,

Chapters 3 through 6. (Note: As an exception to these requirements, the filling of the tank with water as a means of expelling vapors from the tank as described in Section 4.2.6.1 of *American Petroleum Institute Bulletin 1604*, will not be allowed. Comply with all Federal, State and local regulations when performing UST removal and contaminated material disposal. Any fines resulting from violations of any regulation are the sole responsibility of the Contractor and the Contractor agrees to indemnify and hold harmless the Department against any assessment of such fines.

Where underground storage tanks are indicated below, there will be no direct payment for the assessment or closure. When the contract does not indicate the presence of storage tanks and storage tanks are discovered after the opening of bids for the project, the Engineer may have the work performed by others or the cost of assessment, closure, and/or removal will be paid for in accordance with Article 104-7 of the *2006 Metric Standard Specifications*.

Disposition of any contaminated material associated with underground storage tanks will be made as provided in Article 107-26 of the *2006 Metric Standard Specifications*.

Building Removal 1
Barn
Parcel # R-2518A 001
Rt. of Survey Station 10+45, SLL

Building Removal 2
One Story Frame Business
Parcel # R-2518A 004
Rt. of Survey Station 11+40, SLL

Building Removal 3
One Story Metal Business
Parcel # R-2518A 007
Lt. of Survey Station 14+50, SLL

Building Removal 4
One Story Block Business
Parcel # R-2518A 007
Lt. of Survey Station 15+00, SLL

Building Removal 5
Shed
Parcel # R-2518A 007
Rt. of Survey Station, 14+45 SLL

Building Removal 6
Two Story Framed Dwelling
Parcel # R-2518A 009
Lt. of Survey Station 15+75, SLL

Building Removal 7
8 Mobile Homes
Parcel # R-2518A 009
Lt. of between Survey Station 16+40 and 17+40, SLL

Building Removal 8
Barn
Parcel # R-2518A 010
Rt. of Survey Station 17+60, SLL

Building Removal 9
One and one half Story Frame Dwelling
Parcel # R-2518A 010
Lt. of Survey Station 18+00, SLL

Building Removal 10
Shed
Parcel # R-2518A 010
Lt. of Survey Station 17+95, SLL

Building Removal 11
Garage
Parcel # R-2518A 010
Lt. of Survey Station 18+05

Building Removal 12
Shed
Parcel # R-2518A 010
Lt. of Survey Station 18+00, SLL

Building Removal 13
Mobile Home
Parcel # R-2518A 010
Lt. of Survey Station 20+50, SLL

Building Removal 14
Two Sheds
Parcel # R-2518A 010
Lt. of Survey Station 20+70, SLL

Building Removal 15
One Story Frame Building
Parcel # R-2518A 014
Lt. of Survey Station 20+90, SLL

Building Removal 16
One Story Frame Business
Parcel # R-2518A 014
Lt. of Survey Station 21+60, SLL

Building Removal 17
One Story Frame Business
Parcel # R-2518A 014
Lt. of Survey Station 21+60, SLL

Building Removal 18
One Story Block Business and Metal Canopy
Parcel # R-2518A 014
Lt. of Survey Station 22+80, SLL

Building Removal 19
One Story Metal Business
Parcel # R-2518A 014
Rt. of Survey Station 21+55, SLL

Building Removal 20
One Story Frame Dwelling
Parcel # R-2518A 018
Lt. of Survey Station 22+35, SLL

Building Removal 21
Garage
Parcel # R-2518A 018
Lt. of Survey Station 22+45, SLL

Building Removal 22
Carport
Parcel # R-2518A 023
Rt. of Survey Station 27+15, SLL

Building Removal 23
Garage
Parcel # R-2518A 023
Rt. of Survey Station 27+15, SLL

Building Removal 24
Shed
Parcel # R-2518A 023
Rt. of Survey Station 27+15, SLL

Building Removal 25
Barn
Parcel # R-2518A 025
Lt. of Survey Station 27+40, SLL

Building Removal 26
3 (Three) Sheds
Parcel # R-2518A 028
Lt. of Survey Station 27+55, SLL

Building Removal 27
Three Metal Storage Buildings
Parcel # R-2518A 028
Lt. of and between Survey Stations 28+10 and 28+60, SLL. These three buildings are to be cut off at the right of way line.

Building Removal 28
Shed
Parcel # R-2518A 032
Lt. of Survey Station 29+95, SLL

Building Removal 29
Shed
Parcel # R-2518A 032
Lt. of Survey Station 30+35, SLL

Building Removal 30
One House Trailer
Parcel # R-2518A 032
Lt. of Survey Station 30+50, SLL

Building Removal 31
Two Sheds
Parcel # R-2518A 033
Rt. of Survey Station 31+05, SLL

Building Removal 32
One Story Frame Dwelling
Parcel # R-2518A 033
Rt. of Survey Station 31+15, SLL

Building Removal 33
Shed
Parcel # R-2518A 035
Rt. of Survey Station 31+15, SLL

Building Removal 34
One Story Frame Dwelling
Parcel # R-2518A 042
Rt. of Survey Station 35+95, SLL

Building Removal 35
Shed
Parcel # R-2518A 042
Rt. of Survey Station 36+15, SLL

Building Removal 36
Shed
Parcel # R-2518A 043
Rt. of Survey Station 37+05, SLL

Building Removal 37
One Story Brick Dwelling
Parcel # R-2518A 043
Rt. of Survey Station 37+55, SLL

Building Removal 38
One Frame Shed
Parcel # R-2518A 046
Lt. of and between Survey Station 38+55, SLL

Building Removal 39
Mobile Home
Parcel # R-2518A 048
Lt. of Survey Station 39+70, SLL

Building Removal 40
Two Sheds
Parcel # R-2518A 048
Approximate Lt. of Survey Station 40+10, SLL

Building Removal 41
House Trailer
Parcel # R-2518A 049
Lt. of Survey Station 41+15, SLL

Building Removal 42
Two House Trailers and One Story Business
Parcel # R-2518A 050
Lt. of Survey Station 41+60, SLL

Building Removal 43
Shed
Parcel # R-2518A 050
Lt. of Survey Station 42+00, SLL

Building Removal 44
One Shed
Parcel #R-2518A050
Lt. of Survey Station 42+13, SLL

Building Removal 45
One Story Frame Dwelling
Parcel # R-2518A 053
Lt. of Survey Station 44+85, SLL

Building Removal 46
One Story Metal Garage
Parcel # R-2518A 057
Lt. of Survey Station 52+80, SLL

Building Removal 47
Shed
Parcel # R-2518A 059
Lt. of Survey Station 54+15, SLL

Building Removal 48
Barn
Parcel # R-2518A 060
Rt. of Survey Station 55+55, SLL

Building Removal 49
Shed
Parcel # R-2518A 061
Rt. of Survey Station 57+75, SLL

Building Removal 50
One Story Frame Business
Parcel # R-2518A 062
Lt. of Survey Station 56+80, SLL

Building Removal 51
One Story Frame Dwelling located on uneconomic remnant that was purchased.
Parcel # R-2518A 064
Rt. of Survey Station 58+85, SLL

Building Removal 52
Two Sheds
Parcel # R-2518A 064
Rt. of Survey Station 59+10, SLL – Located on uneconomic remnant that was purchased.

Building Removal 53
One House Trailer
Parcel # R-2518A 066
Rt. of Survey Station 60+65, SLL

Building Removal 54
One Story Block Business
Parcel # R-2518A 066
Rt. of Survey Station 61+00, SLL

Building Removal 55
Shed
Parcel # R-2518A 066
Rt. of Survey Station 61+35, SLL

Building Removal 56
One Story Brick Dwelling and Brick Wall
Parcel # R-2518A 066A
Rt. of Survey Station 61+75, SLL

Building Removal 57
One Story Block Business and Garage
Parcel # R-2518A 069
Rt. of Survey Station 64+25, SLL



Building Removal 58
One Story Brick Dwelling
Parcel # R-2518A 070
Rt. of Survey Station 65+40, SLL

Building Removal 59
Barn
Parcel # R-2518A 070
Rt. of Survey Station 65+75, SLL

Building Removal 60
One Story Frame Dwelling
Parcel # R-2518A 071
Rt. of Survey Station 66+80, SLL

Building Removal 61
Garage
Parcel # R-2518A 071
Rt. of Survey Station 66+90, SLL

Building Removal 62
One Story Frame Dwelling
Parcel # R-2518A 074
Rt. of Survey Station 72+85, SLL

Building Removal 63
One Shed
Parcel # R-2518A 074
Rt. of Survey Station 73+05, SLL

Building Removal 64
Two Sheds
Parcel # R-2518A 076
Rt. of Survey Station 75+50, SLL

Building Removal 65
One Story Frame Dwelling
Parcel # R-2518A 076
Rt. of Survey Station 75+70, SLL

Building Removal 66
One Shed
Parcel # R-2518A 078
Lt. of Survey Station 75+70, SLL

Building Removal 67
Two Story Block / Frame Business
Parcel # R-2518A 078
Lt. of Survey Station 75+90, SLL
Building Removal 68
One Shed
Parcel # R-2518A 078
Lt. of Survey Station 76+20, SLL
Building Removal 69
One Story Frame Dwelling
Parcel # R-2518A 078
Lt. of Survey Station 76+40, SLL
Building Removal 70
Barn
Parcel # R-2518A 079
Rt. of Survey Station 75+50, SLL
Building Removal 71
Single Story Frame Dwelling
Parcel # R-2518A 079
Rt. of Survey Station 75+90, SLL
Building Removal 72
Two Story Frame Dwelling
Parcel # R-2518A 080
Rt. of Survey Station 76+80, SLL
Building Removal 73
Shed
Parcel # R-2518A 080
Rt. of Survey Station 77+10, SLL
Building Removal 74
One Story Frame Dwelling and One Shed
Parcel # R-2518A 082
Rt. of Survey Station 77+20, SLL

Building Removal 75
One Story House Trailer
Parcel # R-2518A 087
Lt. of Survey Station 11+54, SLL
Building Removal 76
Barn
Parcel # R-2518A 087
Rt. of Survey Station 82+40, SLL
Building Removal 77
Shed
Parcel # R-2518A 091A
Rt. of Survey Station 10+20 Y-17
Building Removal 78
One Story House Trailer
Parcel # R-2518A 095
Lt. of Survey Station 83+10, SLL
Building Removal 79
One Story Frame Dwelling
Parcel # R-2518A 095
Lt. of Survey Station 83+35, SLL
Building Removal 80
Shed
Parcel # R-2518A 097
Lt. of Survey Station 85+95, SLL
Building Removal 81
Two Story Frame Dwelling
Parcel # R-2518A 097
Lt. of Survey Station 86+35, SLL
Building Removal 82
One Story Frame Dwelling
Parcel # R-2518A 099
Rt. of Survey Station 88+65, SLL
Building Removal 83
Barn
Parcel # R-2518A 101
Lt. of Survey Station 92+75, SLL

Building Removal 84
One Story House Trailer – Double Wide
Parcel # R-2518A 111
Rt. of Survey Station 108+90, SLL

Building Removal 85
Shed
Parcel # R-2518A 111
Rt. of Survey Station 108+70, SLL

Building Removal 86
Shed
Parcel # R-2518A 111A
Rt. of Survey Station 109+85, SLL

Building Removal 87
One Story Frame Dwelling
Parcel # R-2518A 119
Lt. of Survey Station 113+75, SLL

Building Removal 88
Barn
Parcel # R-2518A 119
Lt. of Survey Station 114+00, SLL

**EMBANKMENTS:**

(5-16-06)

M2 R18

Revise the *2006 Metric Standard Specifications* as follows:

**Page 2-18, Article 235-4(B) Embankment Formation**, add the following:

- (16) Do not place rock or broken pavement in embankment areas where piles or drilled shaft foundations are to be constructed. This shall include but not be limited to piles and foundations for structures, metal signal poles, overhead sign structures, and high mount lighting.

**TEMPORARY DETOURS:**

(7-1-95) (Rev 4-15-08)

M2 R30

Construct temporary detours required on this project in accordance with the typical sections in the plans or as directed.

Payment for the construction of the detours will be made at the contract unit prices for the various items involved. After the detours have served their purpose, remove the portions deemed unsuitable for use as a permanent part of the project as directed by the Engineer. Salvage and stockpile the aggregate base course removed from the detours at locations within the right of way, as directed by the Engineer, for removal by State Forces. Pipe culverts removed from the detours remain the property of the Contractor. Remove pipe culverts from the project when they are no longer needed. Place pavement and earth material removed from the detour in embankments or dispose of in waste areas furnished by the Contractor. Aggregate base course and earth material that is removed will be measured and will be paid for at the contract unit price per cubic meter for *Unclassified Excavation*. Pavement that is removed will be measured and will be paid for at the contract unit price per square meter for *Removal of Existing Pavement*. Pipe culverts that are removed will be measured and will be paid for at the contract unit price per linear meter for *Pipe Removal*. Such prices and payments will be full compensation for the work of removing, salvaging, and stockpiling aggregate base course; removing pipe culverts; and for placing earth material and pavement in embankments or disposing of earth material and pavement in waste areas.

**SHALLOW UNDERCUT:**

(9-18-07)

M2 R35 A

**Description**

Undercut to a depth of 150 to 600 mm and place fabric for soil stabilization and Class IV Subgrade Stabilization at locations shown on the plans or as directed by the Engineer.

**Materials**

Refer to Division 10 of the *2006 Metric Standard Specifications*.

<b>Item</b>	<b>Section</b>
Select Material, Class IV	1016
Fabric for Soil Stabilization, Type 4	1056

Use Class IV Select Material for Class IV Subgrade Stabilization. If Class IV Subgrade Stabilization does not meet the requirements of Article 1010-2 of the *2006 Metric Standard Specifications*, the Engineer, at his discretion, may consider the material reasonably acceptable in accordance with Article 105-3 of the *2006 Metric Standard Specifications*.

**Construction Methods**

Perform undercut excavation in accordance with Section 225 of the *2006 Metric Standard Specifications*. Place fabric for soil stabilization in accordance with Article 270-3 of the *2006 Metric Standard Specifications* before backfilling. Backfill with Class IV Subgrade Stabilization by end dumping subgrade stabilization material on the fabric. Do not operate heavy equipment on the fabric until it is covered with Class IV Subgrade Stabilization. Compact subgrade stabilization material to 92% of AASHTO T180 as modified by the Department or to the highest density that can be reasonably obtained.

Maintain Class IV Subgrade Stabilization in an acceptable condition and minimize the use of heavy equipment on subgrade stabilization material in order to avoid damaging the backfill. Provide and maintain drainage ditches and drains as required to prevent entrapment of water in backfill.

**Measurement and Payment**

*Class IV Subgrade Stabilization* will be measured and paid for at the contract unit price per metric ton. The quantity to be paid for will be the actual number of metric tons of subgrade stabilization material that has been incorporated into the completed and accepted work. The material will be measured by being weighed in trucks on certified platform scales or other certified weighing devices. This work includes but is not limited to furnishing, hauling, handling, placing, compacting and maintaining the subgrade stabilization material.

*Undercut Excavation* will be measured and paid for in accordance with Section 225 of the *2006 Metric Standard Specifications*.

*Fabric for Soil Stabilization* will be measured and paid for in accordance with Section 270 of the *2006 Metric Standard Specifications*.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Class IV Subgrade Stabilization	Metric Ton

**FALSE SUMPS:**

(7-1-95)

M2 R40

Construct false sumps in accordance with the details in the plans and at locations shown in the plans or at other locations as directed by the Engineer.

Payment for the work of construction of the false sumps will be made at the contract unit price per cubic meter for *Unclassified Excavation* or *Borrow Excavation* depending on the source of material, or included in *Grading-Lump Sum*.

**SHOULDER AND FILL SLOPE MATERIAL:**

(5-21-02)

M2 R45 C

**Description**

Perform the required shoulder and slope construction for this project in accordance with the applicable requirements of Section 560 and Section 235 of the *2006 Metric Standard Specifications* except as follows:

Construct the top 150 mm of shoulder and fill slopes with soils capable of supporting vegetation.

Provide soil with a P.I. greater than 6 and less than 25 and with a pH ranging from 5.5 to 6.8. Remove stones and other foreign material 2 inches or larger in diameter. All soil is subject to test and acceptance or rejection by the Engineer.

Obtain material from within the project limits or approved borrow source.

**Compensation**

When the Contractor elects to obtain material from an area located beneath a proposed fill sections which does not require excavation for any reason other than to generate acceptable shoulder and fill slope material, the work of performing the excavation will be considered incidental to the item of *Borrow Excavation* or *Shoulder Borrow*. If there is no pay item for *Borrow* or *Shoulder Excavation* in the contract, this work will be considered incidental to *Unclassified Excavation*. Stockpile the excavated material in a manner to facilitate measurement by the Engineer. Fill the void created by the excavation of the shoulder and fill slope material with suitable material. Payment for material used from the stockpile will be made at the contract unit price for *Borrow Excavation* or *Shoulder Borrow*. If there is no pay item for *Borrow Excavation* or *Shoulder Borrow*, then the material will be paid for at the contract unit price for *Unclassified Excavation*. The material used to fill the void created by the excavation of the shoulder and fill slope material will be made at the contract unit price for *Unclassified Excavation*, *Borrow Excavation*, or *Shoulder Borrow*, depending on the source of the material.

Material generated from undercut excavation, unclassified excavation or clearing and grubbing operations that is placed directly on shoulders or slope areas, will not be measured separately for payment, as payment for the work requiring the excavation will be considered adequate compensation for depositing and grading the material on the shoulders or slopes.

When undercut excavation is performed at the direction of the Engineer and the material excavated is found to be suitable for use as shoulder and fill slope material, and there is no area on the project currently prepared to receive the material generated by the undercut operation, the Contractor may construct a stockpile for use as borrow at a later date. Payment for the material used from the stockpile will be made at the contract unit price for *Borrow Excavation* or *Shoulder Borrow*.

When shoulder material is obtained from borrow sources or from stockpiled material, payment for the work of shoulder construction will be made at the contract unit price per cubic yard for *Borrow Excavation* or *Shoulder Borrow* in accordance with the applicable provisions of Section 230 or Section 560 of the *2006 Metric Standard Specifications*.

**NATURAL ROCK ENERGY DISSIPATOR:**

(9-26-07)

SPI

**Description**

This work consists of the construction and maintenance of natural rock energy dissipators.

**Materials**

Refer to Divisions 2 & 10 of the *2006 Standard Specifications*

<b>Item</b>	<b>Section</b>
Natural Rock (meeting gradation requirements of Rip Rap Class II)	1042
Filter Fabric for Drainage, Type 2	1056
Drainage Ditch Excavation	240

**Construction Methods**

Natural rock energy dissipators shall be constructed in accordance with the detail shown in the plans or as directed by the Engineer. From the outlet invert of a culvert (or bottom of a ditch) excavation will drop to a specified depth. Excavation will continue to widen through the dissipater. Natural Rock will be placed along the banks and bottom of the dissipator and along the apron.

**Measurement and Payment**

The quantity of energy dissipator material(s) may be affected by site conditions during construction of the project. The quantity of materials may be increased, decreased, or eliminated entirely at the direction of the Engineer. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

*Natural Rock* will be shot rock generated from the Unclassified Excavation. No additional payment will be made for natural rock as it will be considered a part of the work being paid for as "Unclassified Excavation".

*Filter Fabric for Drainage* will be measured and paid for in accordance with Section 876 of the *2006 Standard Specifications*.

*Drainage ditch excavation* will be measured and paid for in accordance with Section 240 of the *2006 Standard Specifications*.



Such price and payment will be full compensation for all work covered by this section, including, but not limited to, furnishing all materials (including berm material), labor, and equipment. No direct payment will be made for the rock cross vanes as such work will be included in the cost of the other items necessary to construct the natural rock energy dissipaters.

**FLOWABLE FILL:**

(9-17-02) (Rev 8-21-07)

M3 R30

**Description**

This work consists of all work necessary to place flowable fill in accordance with these provisions, the plans, and as directed.

**Materials**

Provide flowable fill material in accordance with Article 340-2 of the *2006 Metric Standard Specifications*.

**Construction Methods**

Discharge flowable fill material directly from the truck into the space to be filled, or by other approved methods. The mix may be placed full depth or in lifts as site conditions dictate. The Contractor shall provide a method to plug the ends of the existing pipe in order to contain the flowable fill.

**Measurement and Payment**

At locations where flowable fill is called for on the plans and a pay item for flowable fill is included in the contract, *flowable fill* will be measured in cubic meters and paid for as the actual number of cubic meters that have been satisfactorily placed and accepted. Such price and payment will be full compensation for all work covered by this provision including but not limited to the mix design, furnishing, hauling, placing and containing the flowable fill.

Payment will be made under:

**Pay Item**

Flowable Fill

**Pay Unit**

Cubic Meter

**PIPE TESTING:**

4-17-07

M3 R33

Revise the *2006 Metric Standard Specifications* as follows:

**Page 3-2, Article 300-6**, add the following as a new paragraph before (A):

The Department reserves the right to perform forensic testing on any installed pipe.

**PIPE ALTERNATES:**

(7-18-06) (Rev 4-17-07)

M3 R36

**Description**

The Contractor may substitute Aluminized Corrugated Steel Pipe, Type IR or HDPE Pipe, Type S or Type D up to 1219 mm in diameter in lieu of concrete pipe in accordance with the following requirements.

**Material**

<b>Item</b>	<b>Section</b>
HDPE Pipe, Type S or D	1032-10
Aluminized Corrugated Steel Pipe, Type IR	1032-3(A)(7)

Aluminized Corrugated Steel Pipe will not be permitted in counties listed in Article 310-2 of the *2006 Metric Standard Specifications*.

**Construction Methods**

Aluminized Corrugated Steel Pipe Culverts and HDPE Pipe Culverts shall be installed in accordance with the requirements of Section 300 of the *2006 Metric Standard Specifications* for Method A, except that the minimum cover shall be at least 300 mm. Aluminized Corrugated Steel Pipe Culvert and HDPE Pipe Culvert will not be permitted for use under travelways, including curb and gutter.

**Measurement and Payment**

\_\_\_\_\_ mm *Aluminized Corrugated Steel Pipe Culvert* to be paid for will be the actual number of linear meters installed and accepted. Measurement will be in accordance with Section 310-6 of the *2006 Metric Standard Specifications*.

\_\_\_\_\_ mm *HDPE Pipe Culvert* to be paid for will be the actual number of linear meters installed and accepted. Measurement will be in accordance with Section 310-6 of the *2006 Metric Standard Specifications*.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
_____ mm Aluminized Corrugated Steel Pipe Culverts, _____ mm Thick	Linear Meter
_____ mm HDPE Pipe Culverts	Linear Meter

**REINFORCED BRIDGE APPROACH FILL:**

(3-18-03) (Rev.7-18-06)

M4 R01

**Description**

This work consists of all work necessary to construct reinforced bridge approach fills in accordance with these provisions and the plans, and as directed by the Engineer.

**Materials****Geomembrane**

Provide geomembrane that is impermeable, composed of polyethylene polymers or polyvinyl chloride, and meets the following physical requirements:

<u>Property</u>	<u>Requirements</u>	<u>Test Method</u>
Thickness	0.6 mm Minimum	ASTM D1593
Tensile Strength at Break	18 kN/M Minimum	ASTM D638
Puncture Strength	0.2 kN Minimum	ASTM D 4833
Moisture Vapor Transmission Rate	0.667/gm/m <sup>2</sup> per Day Maximum	ASTM E96

**Fabric**

Refer to Section 1056 for Type 2 Engineering Fabric and the following:

Use a woven fabric consisting of strong rot-proof synthetic fibers such as polypropylene, polyethylene, or polyester formed into a stable network such that the filaments or yarns retain their relative positions to each other.

<u>Fabric Property</u>	<u>Requirements</u>	<u>Test Method</u>
Minimum Flow Rate	1358 cm <sup>3</sup> /sec/m <sup>2</sup>	ASTM D 4491

Lamination of fabric sheets to produce the physical requirements of a fabric layer will not be accepted. Furnish letters of certification from the manufacturer with each shipment of the fabric and geomembrane attesting that the material meets the requirements of this provision; however, the material is subject to inspection, test, or rejection by the Engineer at any time.

During all periods of shipment and storage, wrap the geomembrane and fabric in a heavy-duty protective covering to protect the material from ultraviolet rays. After the protective wrapping has been removed, do not leave the material uncovered under any circumstances for longer than 4 days.

### Select Material

Provide select material meeting the requirements of Class III, Type 1 or Type 2, or Class V select material of Section 1016 of the *2006 Metric Standard Specifications*. When select material is required under water, use select material class V only, up to one foot above the existing water elevation.

### 100 mm Diameter Corrugated Drainage Pipe and Fittings

Provide pipe and fittings that meet all the applicable requirements of Section 815 or 816 of the *2006 Metric Standard Specifications*.

### Construction Methods

Place the geomembrane and fabric as shown on the plans or as directed by the Engineer. Perform the excavation for the fabric reinforced fill to the limits shown on the plans. Provide an excavated surface free of obstructions, debris, pockets, stumps, and cleared of all vegetation. The geomembrane or fabric will be rejected if it has defects, rips, holes, flaws, deterioration or damage incurred during manufacture, transportation, handling or storage. Lay all layers smooth, and free from tension, stress, folds, wrinkles or creases. Place all the fabric layers with the machine direction (roll direction) parallel to the centerline of the roadway. A minimum roll width of 3 m for the fabric is required. Overlap geomembrane or fabric splices parallel to the centerline of the roadway a minimum of 450 mm. Geomembrane or fabric splices parallel to the backwall face will not be allowed.

Deposit and spread select material in successive, uniform, approximately horizontal layers of not more than 254 mm in depth, loose measurement, for the full width of the cross section, and keep each layer approximately level. Place and compact each layer of select material fill no more than 254 mm thick with low ground pressure equipment. Use hand operated equipment to compact the fill material within 1 m of the backwall and wingwalls as directed by the Engineer. Compact select material to a density equal to at least 95% of that obtained by compacting a sample of the material in accordance with AASHTO T99 as modified by the Department. Compact the top 200 mm of select material to a density to at least 100% of that obtained by compacting a sample of the material in accordance with AASHTO T99 as modified by the Department. Density requirements are not applicable to select material, class V; however compact the fill with at least four passes of low ground pressure equipment on the entire surface as directed by the Engineer. The compaction of each layer of select material shall be inspected and approved by the Department prior to the placement of the next fill layer. No equipment will be allowed to operate on the drainage pipe or any geomembrane/fabric layer until it is covered with at least 150 mm of fill material. Compaction shall not damage the drainage pipe, geomembrane, or fabric under the fill. Cover the geomembrane/fabric with a layer of fill material within four days after placement of the geomembrane/fabric. Geomembrane and fabric that are damaged as a result of installation will be replaced as directed by the Department at no additional cost.

Place the geomembrane on the ground, and attach and secure it tightly to the vertical face of the backwall and wingwalls with adhesives, duct-tape, nails or any other method approved by the Engineer. Place the first fabric layer on the surface of the geomembrane with the same dimensions of the geomembrane. No material or void is allowed between the geomembrane and the first fabric layer. Place and fold the remaining fabric layers on the edges as shown on the plans or as directed by the Engineer. Provide vertical separation between fabric layers as specified on the plans. The number of fabric layers will be shown in the plans.

Place 100 mm diameter perforated drainage pipe along the base of the backwall and sloped to drain as shown on the plans. Completely wrap perforated drainage pipe and #78M stone with Type 2 Engineering Fabric as shown on the plan detail. Install a pipe sleeve through the bottom of or under the wing wall prior to placing concrete for the wing wall. The pipe sleeve shall be of adequate strength to withstand the wingwall load. Place the pipe sleeve in position to allow the drainage pipe to go through the wing wall with a proper slope. Connect 100 mm diameter nonperforated (plain) drainage pipe with a coupling to the perforated pipe near the inside face of the wingwall. Place the nonperforated drainage pipe through the pipe sleeve, extend down to the toe of the slope and connect, to a ditch or other drainage systems as directed by the Engineer. For bridge approaches in cut sections where no side slope is available, direct the drainage pipe outlet to the end slope down to the toe using elbows as directed by the Engineer.

### Measurement and Payment

*Reinforced Bridge Approach Fill, Station \_\_\_\_\_* will be paid for at the contract lump sum price. Such price and payment will be full compensation for both approach fills at each bridge installation, including but not limited to furnishing, placing and compacting select material, furnishing and placing geomembrane and woven fabric, furnishing and placing pipe sleeve, drainage pipe, and stone, furnishing and installing concrete pads at the end of outlet pipes, excavation and any other items necessary to complete the work.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Reinforced Bridge Approach Fill, Station _____	Lump Sum

### AGGREGATE BASE COURSE:

12-19-06

M5 R03

Revise the *2006 Metric Standard Specifications* as follows:

**Page 5-9, Article 520-5 Hauling and Placing Aggregate Base Material**, 6th paragraph, replace the first sentence with the following:

Base course that is in place on November 15 shall have been covered with a subsequent layer of pavement structure or with a sand seal. Base course that has been placed between November 16 and March 15 inclusive shall be covered within 7 calendar days with a subsequent layer of pavement structure or with a sand seal.

**PREPARATION OF SUBGRADE AND BASE:**

(1-16-96)

M5 R05

On mainline portions and ramps of this project, prepare the subgrade and base beneath the pavement structure in accordance with the applicable sections of the *2006 Metric Standard Specifications* except use an automatically controlled fine grading machine utilizing string lines, laser controls, or other approved methods to produce final subgrade and base surfaces meeting the lines, grades, and cross sections required by the plans or established by the Engineer.

No direct payment will be made for the work required by this provision as it will be considered incidental to other work being paid for by the various items in the contract.

**AGGREGATE FOR SOIL-CEMENT BASE:**

(7-18-06)

M5 R15

Revise the *2006 Metric Standard Specifications* as follows:

**Page 5-23, Article 542-1.** Delete the first sentence and substitute the following:

The work covered by this section consists of constructing and curing a soil-cement base by treating the subgrade, existing subbase, or existing base, or any combination of these materials, by pulverizing, adding portland cement, adding aggregate when required, mixing, wetting, and compacting the mixture to the required density.

**Page 5-23, Article 542-2.** Add the following:

<b>Item</b>	<b>Section</b>
Aggregate, Std. Size ABC	1005

**Page 5-24, Article 542-7.** Add the following after the first paragraph:

Prior to spreading cement, aggregate shall be spread at the rate shown in the plans.

**Page 5-26, Article 542-16.** Add the following paragraph after the first paragraph:

*Aggregate for Soil-Cement Base* will be measured and paid for in metric tons at the contract unit price per metric ton. The aggregate will be measured by weighing in trucks or certified platform scales or other certified weighing devices. No deductions will be made for any moisture contained in the aggregate at the time of weighing.

Add the following to the pay item:

<b>Pay Item</b>	<b>Pay Unit</b>
Aggregate for Soil-Cement Base	Metric Ton

**ASPHALT PAVEMENTS - SUPERPAVE:**

(7-18-06) (Rev 5-20-08)

M6 R01

Revise the *2008 Metric Standard Specifications* as follows:

**Page 6-2, Article 600-9 Measurement and Payment, delete the second paragraph.**

**Page 6-10, Subarticle 609-5(C)2, Required Sampling and Testing Frequencies, first partial paragraph at the top of the page, delete last sentence and add the following:**

If the Engineer allows the mix to remain in place, payment will be made in accordance with Article 105-3.

**Page 6-10, Subarticle 609-5(C)2, QUALITY CONTROL MINIMUM SAMPLING AND TESTING SCHEDULE**

**First paragraph, delete and replace with the following.**

Sample and test the completed mixture from each mix design per plant per year at the following minimum frequency during mix production:

**Second paragraph, delete the fourth sentence, and replace with the following**

When daily production of each mix design exceeds 100 metric tons and a regularly scheduled full test series random sample location for that mix design does not occur during that day's production, perform at least one partial test series consisting of Items A and B in the schedule below.

**Page 6-10, Subarticle 609-5(C)2(c) Maximum Specific Gravity, add after (AASHTO T 209):**

*or ASTM D 2041*

**Page 6-11, Subarticle 609-5(C)2(e) Retained Tensile Strength, add a heading before the first paragraph as follows:**

- (i) Option 1

**Insert the following immediately after the first paragraph:**

- (ii) Option 2

Mix sampled from truck at plant with one set of specimens prepared by the Contractor and then tested jointly by QA and QC at a mutually agreed upon lab site within the first 7 calendar days after beginning production of each new mix design.

**Second paragraph, delete the and replace with the following:**

Test all TSR specimens required by either option noted above on either a recording test press or a test press that maintains the peak load reading after the specimen has broken.

**Page 6-11, Subarticle 609-5(C)(3) Control Charts, delete the second sentence of the first paragraph and replace with the following:**

For mix incorporated into the project, record full test series data from all regularly scheduled random samples or directed samples that replace regularly scheduled random samples, on control charts the same day the test results are obtained.

**Page 6-12, Subarticle 609-5(C)(3) Control Charts, fourth paragraph on this page, delete the last sentence and substitute the following:**

Denote the moving average control limits with a dash green line and the individual test limits with a dash red line.

**Subarticle 609-5(C)(3)(a), (b) and (c), replace (a) (b) and (c) with the following:**

- (a) A change in the binder percentage, aggregate blend, or  $G_{mm}$  is made on the JMF, or,
- (b) When the Contractor elects to stop or is required to stop production after one or two moving average values, respectively, fall outside the moving average limits as outlined in Subarticle 609-5(C)6 or,
- (c) If failure to stop production after two consecutive moving averages exceed the moving average limits occurs, but production does stop at a subsequent time, re-establish a new moving average beginning at the actual production stop point.

**Subarticle 609-5(C)(4) Control Limits, replace the first paragraph and the CONTROL LIMITS Table on page 6-13 with the following.**

The following are established as control limits for mix production. Apply the individual limits to the individual test results. Control limits for the moving average limits are based on a moving average of the last 4 data points. Apply all control limits to the applicable target source.



**CONTROL LIMITS**

Mix Control Criteria	Target Source	Moving Average Limit	Individual Limit
2.36 mm Sieve	JMF	±4.0 %	±8.0 %
0.075mm Sieve	JMF	±1.5 %	±2.5 %
Binder Content	JMF	±0.3 %	±0.7 %
VTM @ N <sub>des</sub>	JMF	±1.0 %	±2.0 %
VMA @ N <sub>des</sub>	Min. Spec. Limit	-0.5%	-1.0%
P <sub>0.075</sub> / P <sub>be</sub> Ratio	1.0	±0.4	±0.8
%G <sub>mm</sub> @ N <sub>ini</sub>	Max. Spec. Limit	N/A	+2.0%
TSR	Min. Spec. Limit	N/A	- 15%

**Page 6-13, Subarticle 609-5(C)(5) Warning Bands, delete this Subarticle in its entirety.**

**Pages 6-13 through 6-15, Subarticle 609-5(C)(6), delete the word "warning" and substitute the words "moving average".**

**Page 6-13, Subarticle 609-5(C)(6) Corrective Actions, first paragraph, first sentence, delete and replace with the following:**

Immediately notify the Engineer when moving averages exceed the moving average limits.

**Page 6-14, Subarticle 609-5(C)(6) Corrective Actions, second paragraph, delete and replace with the following:**

Failure to stop production when required due to an individual mix test not meeting the specified requirements will subject all mix from the stop point tonnage to the point when the next individual test is back on or within the moving average limits, or to the tonnage point when production is actually stopped, whichever occurs first, to being considered unacceptable.

**Fifth full paragraph, delete the first, second, and third sentence and replace with the following:**

Immediately notify the Engineer when any moving average value exceeds the moving average limit. If two consecutive moving average values for any one of the mix control criteria fall outside the moving average limits, cease production of that mix, immediately notify the Engineer of the stoppage, and make adjustments. The Contractor may elect to stop production after only one moving average value falls outside the moving average limits.

**Page 6-14, Subarticle 609-5(C)(6) Corrective Actions eighth paragraph, delete and replace with the following:**

If the process adjustment improves the property in question such that the moving average after four additional tests is on or within the moving average limits, the Contractor may continue production with no reduction in payment

**Page 6-14, delete the last paragraph and the first paragraph on Page 6-15, including the Table for Payment for Mix Produced in the Warning Bands and substitute the following:**

If the adjustment does not improve the property in question such that the moving average after four additional individual tests is outside the moving average limits, the mix will be evaluated for acceptance in accordance with Article 105-3. Reduced payment for or removal of the mix in question will be applied starting from the plant sample tonnage at the stop point to the sample tonnage when the moving average is on or within the moving average limits. In addition, any mix that is obviously unacceptable will be rejected for use in the work.

**Page 6-15, Subarticle 609-5(C)(6) Corrective Actions, delete the last paragraph in this Subarticle and replace with the following:**

Failure to stop production and make adjustments when required due to two consecutive moving average values falling outside the moving average limits will subject all mix produced from the stop point tonnage to the tonnage point when the moving average is back on or within the moving average limits or to the tonnage point when production is actually stopped, whichever occurs first, to being considered unacceptable. Remove this material and replaced with materials which comply with the Specifications at no additional costs to the Department, unless otherwise approved. Payment will be made for the actual quantities of materials required to replace the removed quantities, not to exceed the original amounts.

**Page 6-16, Subarticle 609-5(D)(1) General, delete the last paragraph on this page, and replace with the following:**

Perform the sampling and testing at the minimum test frequencies as specified above. Should the density testing frequency fail to meet the minimum frequency as specified above, all mix without the required density test representation will be considered unsatisfactory. If the Engineer allows the mix to remain in place, payment will be made in accordance with Article 105-3.

**Page 6-18, Subarticle 609-5(D)(5) Limited Production Procedure, delete the first paragraph including (a), (b), (c) and substitute the following:**

Proceed on limited production when, for the same mix type and on the same contract, one of the following conditions occur (except as noted in the first paragraph below).

- (a) Two consecutive failing lots, except on resurfacing\*
- (b) Three consecutive failing lots on resurfacing\*
- (c) Two consecutive failing nuclear control strips.

\* Resurfacing is defined as the first new uniform layer placed on an existing pavement.

**Page 6-23, Subarticle 610-3(A) Mix Design-General, add the following as the fourth paragraph:**

Reclaimed Asphalt Pavement (RAP) or Reclaimed Asphalt Shingles (RAS) may be incorporated into asphalt plant mixes in accordance with Article 1012-1 and the following applicable requirements.

**Page 6-23, Subarticle 610-3(A) Mix Design-General, fourth paragraph, third sentence:**

Substitute 20% for 15%

**Page 6-24, Subarticle 610-3(A) Mix Design-General, first full paragraph, first, second and third sentences:**

Substitute 20% for 15%

**Page 6-29, Table 610-3 delete and replace with the following:**

**TABLE 610-3  
ASPHALT PLACEMENT- MINIMUM TEMPERATURE REQUIREMENTS**

Asphalt Concrete Mix Type	Minimum Air Temperature	Minimum Surface Temperature
ACBC, Type B 25.0B, C, B 37.5C	2°C	2°C
ACIC, Type I 19.0B, C, D	2°C	2°C
ACSC, Type S 4.75A, SF 9.5A, S 9.5B	4°C	* 10°C
ACSC, Type S 9.5C, S 12.5C	7°C	10°C
ACSC, Type S 9.5D, S 12.5D	10°C	10°C

\* 2°C if surface is soil or aggregate base for secondary road construction.

**Page 6-36, Article 610-8 Spreading and Finishing, sixth paragraph on this page, replace the first sentence with the following:**

Use the 9 m minimum length mobile grade reference system or the non-contacting laser or sonar type ski *with at least four referencing stations mounted on the paver at a minimum length 7.3 m* to control the longitudinal profile when placing the initial lanes and all adjacent lanes of all layers, including resurfacing and asphalt in-lays, unless otherwise specified or approved.

**Page 6-41, Article 610-13 Density Acceptance, delete the second paragraph and replace with the following:**

As an exception, when the first layer of mix is a surface course and is being placed directly on an unprimed aggregate or soil base, the layer will be included in the "Other" construction category.

**Page 6-44, Article 620-4 Measurement and Payment, fourth full paragraph, delete the last sentence.**

**Page 6-44, Article 620-4 Measurement and Payment, add the following pay item:**

<b>Pay Item</b>	<b>Pay Unit</b>
Asphalt Binder for Plant Mix, Grade PG 70-28	Metric Ton

**Page 6-57, Table 660-1 Material Application Rates and Temperatures, add the following:**

<b>Type of Coat</b>	<b>Grade of Asphalt</b>	<b>Asphalt Rate L/Sq M</b>	<b>Application Temperature °C</b>	<b>Aggregate Size</b>	<b>Aggregate Rate Kg/Sq M Total</b>
Sand Seal	CRS-2 or CRS-2P	1.00-1.36	66-79	Blotting Sand	6-8

**Page 6-62, Subarticle 660-9(B), add the following as sub-item (5)**

(5) Sand Seal

Place the fully required amount of asphalt material in one application and immediately cover with the seal coat aggregate. Uniformly spread the fully required amount of aggregate in one application and correct all non-uniform areas prior to rolling.

Immediately after the aggregate has been uniformly spread, perform rolling.

When directed, broom excess aggregate material from the surface of the seal coat.

When the sand seal is to be constructed for temporary sealing purposes only and will not be used by traffic, other grades of asphalt material meeting the requirements of Articles 1020-6 and 1020-7 may be used in lieu of the grade of asphalt required by Table 660-1 when approved.

**Page 6-63, Article 661-1 Description, add the following as the 2nd paragraph:**

Provide and conduct the quality control and required testing for acceptance of the UBWC in accordance with "Quality Management System for Asphalt Pavements (OGAFC, PADL, and Ultra-Thin HMA Version)", included in the contract.

**Page 6-66, Subarticle 661-3(A) Equipment, add the following as the first paragraph:**

Use asphalt mixing plants in accordance with Article 610-5.

**Page 10-34, Table 1012-1, delete the last row of entries for OGAF C and add the following:**

Mix Type	Course Aggregate Angularity <sup>(b)</sup> ASTM D5821	Fine Aggregate Angularity % Minimum AASHTO T304 Method A	Sand Equivalent % Minimum AASHTO T176	Flat & Elongated 5:1 Ratio % Maximum ASTM D4791 Section 8.4
S 9.5 D	100/100	45	50	10
OGAF C	100/100	N/A	N/A	10
UBW C	100/85	40	45	10

**Delete Note (c) under the Table 1012-1 and replace with the following:**

- (c) Does not apply to Mix Types SF 9.5A and S 9.5B.

**Page 10-35 through 10-37, Subarticle 1012-1(G), delete this in its entirety and replace with the following:****(G) Reclaimed Asphalt Pavement (RAP)****(1) Mix Design RAP**

Incorporate RAP from stockpiles or other sources that have been tested for uniformity of gradation and binder content prior to use in an asphalt mix design. Use reclaimed asphalt pavement that meets all requirements specified for *one of* the following *two* classifications.

**(a) Millings**

Existing reclaimed asphalt pavement (RAP) that is removed from its original location by a milling process as specified in Section 607. Millings should be such that it has a uniform gradation and binder content and all materials will pass a 50 mm sieve prior to introduction into the plant mixer unit.

**(b) Processed RAP**

RAP that is processed in some manner (possibly by crushing and/or use of a blending method) to produce a uniform gradation and binder

content in the RAP prior to use in a recycled mix. Process RAP so that all materials have a uniform gradation and binder content and will pass a 50 mm sieve prior to introduction into the plant mixer unit.

**(2) Mix Production RAP**

During mix production use RAP that meets the criteria for one of the following categories:

**(a) Mix Design RAP**

RAP contained in the mix design stockpiles as described above may be used in all applicable JMFs. These stockpiles have been pretested; however, they are subject to required QC/QA testing in accordance with Subarticle 609-5(C)(2).

**(b) New Source RAP**

New Source RAP is defined as any acceptable material which was not included in the stockpile or other source when samples were taken for mix design purposes. Process new source RAP so that all materials have a uniform gradation and binder content and will pass a 50 mm sieve prior to introduction into the plant mixer unit.

After a stockpile of processed RAP or millings has been sampled and mix designs made from these samples, do not add new source RAP to the original stockpile without prior field testing to insure gradation and binder uniformity. Sample and test new source RAP before blending with the existing stockpile.

Store new source RAP in a separate stockpile until the material can be sampled and tested for comparison with the original recycled mix design data. New source RAP may also be placed against the existing stockpile in a linear manner provided it is sampled for mix design conformity prior to its use in the recycled mix.

Unprocessed RAP is asphalt material that was not milled and/or has not been processed to obtain a uniform gradation and binder content and is not representative of the RAP used during the applicable mix design. Unprocessed RAP shall not be incorporated into any JMFs prior to processing. Different sources of unprocessed RAP may be stockpiled together provided it is generally free of contamination and will be processed prior to use in a recycled mix. RAP contamination in the form of excessive dirt, debris, clean stone, concrete, etc. will not be allowed. Incidental amounts of dirt, concrete, and clean stone may

be acceptable. Unprocessed RAP may be processed and then classified as a new source RAP as described above.

Field approval of new source RAP will be based on Table 1012-2 below and volumetric mix properties on the mix with the new source RAP included. Provided the Table 1012-2 tolerances are met, volumetric properties of the new mix will then be performed. If all volumetric mix properties meet the mix design criteria for that mix type, the new source RAP may continue to be used.

If the gradation, binder content, or any of the volumetric mix properties are not within the allowable tolerances of Table 1012-2, do not use the new source RAP unless approved by the Engineer. The Contractor may elect to either not use the stockpile, to request an adjustment to the JMF, or to redesign the mix.

**TABLE 1012-2  
NEW SOURCE RAP GRADATION and BINDER TOLERANCES  
(Apply Tolerances to Mix Design Data)**

Mix Type	0-20% RAP			20 <sup>+</sup> -25 % RAP			25 <sup>+</sup> % RAP			
	Sieve (mm)	Base	Inter.	Surf.	Base	Inter.	Surf.	Base	Inter.	Surf.
P <sub>b</sub> %		± 0.7%			± 0.4%			± 0.3%		
25.0	±10	-	-	-	±7	-	-	±5	-	-
19.0	±10	±10	-	-	±7	±7	-	±5	±5	-
12.5	-	±10	±6	-	-	±7	±3	-	±5	±2
9.5	-	-	±8	-	-	-	±5	-	-	±4
4.75	±10	-	±10	-	±7	-	±7	±5	-	±5
2.36	±8	±8	±8	-	±5	±5	±5	±4	±4	±4
1.18	±8	±8	±8	-	±5	±5	±5	±4	±4	±4
0.300	±8	±8	±8	-	±5	±5	±5	±4	±4	±4
0.150	-	-	±8	-	-	-	±5	-	-	±4
0.075	±4	±4	±4	-	±2	±2	±2	±1.5	±1.5	±1.5

**ASPHALT BINDER CONTENT OF ASPHALT PLANT MIXES:**

(11-21-00)

M6 R15

The approximate asphalt binder content of the asphalt concrete plant mixtures used on this project will be as follows:

Asphalt Concrete Base Course	Type B 25.0	4.3%
Asphalt Concrete Intermediate Course	Type I 19.0	4.7%
Asphalt Concrete Surface Course	Type S 4.75A	7.0%
Asphalt Concrete Surface Course	Type SF 9.5A	6.5%

Asphalt Concrete Surface Course	Type S 9.5__	6.0%
Asphalt Concrete Surface Course	Type S 12.5__	5.5%

The actual asphalt binder content will be established during construction by the Engineer within the limits established in the *2006 Metric Standard Specifications*.

**ASPHALT PLANT MIXTURES:**

(7-1-95)

M6 R20

Place asphalt concrete base course material in trench sections with asphalt pavement spreaders made for the purpose or with other equipment approved by the Engineer.

**PRICE ADJUSTMENT - ASPHALT BINDER FOR PLANT MIX:**

(11-21-00)

M6 R25

Price adjustments for asphalt binder for plant mix will be made in accordance with Section 620 of the *2006 Metric Standard Specifications*.

The base price index for asphalt binder for plant mix is \$ **477.80** per metric ton.

This base price index represents an average of F.O.B. selling prices of asphalt binder at supplier's terminals on **May 1, 2008**.

**FINAL SURFACE TESTING - ASPHALT PAVEMENTS (Rideability):**

(5-18-04) (Rev.7-18-06)

M6 R45

On portions of this project where the typical section requires two or more layers of new pavement, perform acceptance testing of the longitudinal profile of the finished pavement surface in accordance with these provisions using a North Carolina Hearne Straightedge (Model No. 1). Furnish and operate the straightedge to determine and record the longitudinal profile of the pavement on a continuous graph. Final surface testing is an integral part of the paving operation and is subject to observation and inspection by the Engineer as deemed necessary.

Push the straightedge manually over the pavement at a speed not exceeding 3 kilometers per hour. For all lanes, take profiles in the right wheel path approximately 1 meter from the right edge of pavement in the same direction as the paving operation, unless otherwise approved due to traffic control or safety considerations. Make one pass of the straightedge in each full width travel lane. The full lane width should be comparable in ride quality to the area evaluated with the Hearne Straightedge. If deviations exist at other locations across the lane width, utilize a 3 meter non-mobile straightedge or the Hearne Straightedge to evaluate which areas may require corrective action. Take profiles as soon as practical after the pavement has been rolled and compacted but in no event later than 24 hours following placement of the pavement, unless otherwise authorized by the Engineer. Take profiles over the entire length of final surface travel lane pavement exclusive of -Y- line travel lanes less than or equal to 90 meters in length, turn lanes less than or equal to 90 meters in length, structures, approach slabs, paved shoulders, loops, and tapers or other irregular shaped areas of pavement, unless otherwise approved by the Engineer. Test in accordance with this provision all mainline travel lanes, full width acceleration



or deceleration lanes, -Y- line travel lanes greater than 90 meters in length, ramps, full width turn lanes greater than 90 meters in length, and collector lanes.

At the beginning and end of each day's testing operations, and at such other times as determined necessary by the Engineer, operate the straightedge over a calibration strip so that the Engineer can verify correct operation of the straightedge. The calibration strip shall be a 30 meter section of pavement that is reasonably level and smooth. Submit each day's calibration graphs with that day's test section graphs to the Engineer. Calibrate the straightedge in accordance with the current NCDOT procedure titled *North Carolina Hearne Straightedge - Calibration and Determination of Cumulative Straightedge Index*. Copies of this procedure may be obtained from the Department's Pavement Construction Section.

Plot the straightedge graph at a horizontal scale of approximately 3 meters per centimeter with the vertical scale plotted at a true scale. Record station numbers and references (bridges, approach slabs, culverts, etc.) on the graphs, and distances between references/stations must not exceed 30 meters. Have the operator record the Date, Project No., Lane Location, Wheel Path Location, Type Mix, and Operator's Name on the graph.

Upon completion of each day's testing, evaluate the graph, calculate the Cumulative Straightedge Index (CSI), and determine which lots, if any, require corrective action. Document the evaluation of each lot on a QA/QC-7 form. Submit the graphs along with the completed QA/QC-7 forms to the Engineer, within 24 hours after profiles are completed, for verification of the results. The Engineer will furnish results of their acceptance evaluation to the Contractor within 48 hours of receiving the graphs. In the event of discrepancies, the Engineer's evaluation of the graphs will prevail for acceptance purposes. The Engineer will retain all graphs and forms.

Use blanking bands of 5 mm, 7.5 mm, and 10 mm to evaluate the graph for acceptance. The 5 mm and 7.5 mm blanking bands are used to determine the Straightedge Index (SEI), which is a number that indicates the deviations that exceed each of the 5 mm and 7.5 mm bands within a 30.5 meter test section. The Cumulative Straightedge Index (CSI) is a number representing the total of the SEIs for one lot, which consist of not more than 25 consecutive test sections. In addition, the 10 mm blanking band is used to further evaluate deviations on an individual basis. The Cumulative Straightedge Index (CSI) will be determined by the Engineer in accordance with the current procedure titled "North Carolina Hearne Straightedge - Calibration and Determination of Cumulative Straightedge Index".

The pavement will be accepted for surface smoothness on a lot by lot basis. A test section represents pavement one travel lane wide not more than 30.5 meters in length. A lot will consist of 25 consecutive test sections, except that separate lots will be established for each travel lane, unless otherwise approved by the Engineer. In addition, full width acceleration or deceleration lanes, ramps, turn lanes, and collector lanes, will be evaluated as separate lots. For any lot that is less than 750 meters in length, the applicable pay adjustment incentive will be prorated on the basis of the actual lot length. For any lot which is less than 750 meters in length, the applicable pay adjustment disincentive will be the full amount for a lot, regardless of the lot length.

If during the evaluation of the graphs, 5 lots (mainline travel lanes and full width -Y- line travel lanes greater than 90 meters in length only require corrective action, then proceed on limited production for unsatisfactory laydown in accordance with Article 610-12 of the *2006 Metric Standard Specifications*. Proceeding on limited production is based upon the Contractor's initial evaluation of the straightedge test results and must begin immediately upon obtaining those results. Additionally, the Engineer may direct the Contractor to proceed on limited production in accordance with Article 610-12 due to unsatisfactory laydown or workmanship.

Limited production for unsatisfactory laydown is defined as being restricted to the production, placement, compaction, and final surface testing of a sufficient quantity of mix necessary to construct only 750 meters of pavement at the laydown width. Once this lot is complete, the final surface testing graphs will be evaluated jointly by the Contractor and the Engineer. Remain on limited production until such time as acceptable laydown results are obtained or until three consecutive 750 meter sections have been attempted without achieving acceptable laydown results. The Engineer will determine if normal production may resume based upon the CSI for the limited production lot and any adjustments to the equipment, placement methods, and/or personnel performing the work. Once on limited production, the Engineer may require the Contractor to evaluate the smoothness of the previous asphalt layer and take appropriate action to reduce and/or eliminate corrective measures on the final surface course. Additionally, the Contractor may be required to demonstrate acceptable laydown techniques off the project limits prior to proceeding on the project.

If the Contractor fails to achieve satisfactory laydown results after three consecutive 750 meter sections have been attempted, cease production of that mix type until such time as the cause of the unsatisfactory laydown results can be determined.

As an exception, the Engineer may grant approval to produce a different mix design of the same mix type if the cause is related to mix problem(s) rather than laydown procedures. If production of a new mix design is allowed, proceed under the limited production procedures detailed above.

After initially proceeding under limited production, the Contractor shall immediately notify the Engineer if any additional lot on the project requires corrective action. The Engineer will determine if limited production procedures are warranted for continued production.

If the Contractor does not operate by the limited production procedures as specified above, the 5 lots, which require corrective action, will be considered unacceptable and may be subject to removal and replacement. Mix placed under the limited production procedures for unsatisfactory laydown will be evaluated for acceptance in accordance with Article 105-3.

The pay adjustment schedule for the Cumulative Straightedge Index (CSI) test results per lot is as follows:

<b>Pay Adjustment Schedule for Cumulative Straightedge Index (CSI) (Obtained by adding SE Index of up to 25 consecutive 30.5 meter sections)</b>				
*CSI	ACCEPTANCE CATEGORY	CORRECTIVE ACTION	PAY ADJUSTMENT	
			Before Corrective Action	After Corrective Action
0-0	Acceptable	None	\$300 incentive	None
1-0 or 2-0	Acceptable	None	\$100 incentive	None
3-0 or 4-0	Acceptable	None	No Adjustment	No Adjustment
1-1, 2-1, 5-0 or 6-0	Acceptable	Allowed	\$300 disincentive	\$300 disincentive
3-1, 4-1, 5-1 or 6-1	Acceptable	Allowed	\$600 disincentive	\$600 disincentive
Any other Number	Unacceptable	Required	Per CSI after Correction(s) (not to exceed 100% Pay)	

**\*Either Before or After Corrective Actions**

Correct any deviation that exceeds a 10 mm blanking band such that the deviation is reduced to 7.5 mm or less.

Corrective actions shall be performed at the Contractor's expense and shall be presented for evaluation and approval by the Engineer prior to proceeding. Any corrective action performed shall not reduce the integrity or durability of the pavement that is to remain in place. Corrective action for deviation repair may consist of overlaying, removing and replacing, indirect heating and rerolling. Scraping of the pavement with any blade type device will not be allowed as a corrective action. Provide overlays of the same type mix, full roadway width, and to the length and depth established by the Engineer. Tapering of the longitudinal edges of the overlay will not be allowed.

Corrective actions will not be allowed for lots having a CSI of 40 or better. If the CSI indicates *Allowed* corrective action, the Contractor may elect to take necessary measures to reduce the CSI in lieu of accepting the disincentive. Take corrective actions as specified if the CSI indicates *Required* corrective action. The CSI after corrective action should meet or exceed *Acceptable* requirements.

Where corrective action is allowed or required, the test section(s) requiring corrective action will be retested, unless the Engineer directs the retesting of the of the entire lot. No disincentive will apply after corrective action if the CSI is 40 or better. If the retested lot after corrective action has a CSI indicating a disincentive, the appropriate disincentive will be applied.

Test sections and/or lots that are initially tested by the Contractor that indicate excessive deviations such that either a disincentive or corrective action is necessary, may be re-rolled with asphalt rollers while the mix is still warm and in a workable condition, to possibly correct the problem. In this instance, reevaluation of the test section(s) shall be completed within 24 hours of pavement placement and these test results will serve as the initial test results.

Incentive pay adjustments will be based only on the initially measured CSI, as determined by the Engineer, prior to any corrective work. Where corrective actions have been taken, payment will be based on the CSI determined after correction, not to exceed 100 percent payment.

Areas excluded from testing by the N.C. Hearne Straightedge will be tested by using a non-mobile 3 meter straightedge. Assure that the variation of the surface from the testing edge of the straightedge between any two contact points with the surface is not more than 3 mm. Correct deviations exceeding the allowable tolerance in accordance with the corrective actions specified above, unless the Engineer permits other corrective actions.

Furnish the North Carolina Hearne Straightedge(s) necessary to perform this work. Maintain responsibility for all costs relating to the procurement, handling, and maintenance of these devices. The Department has entered into a license agreement with a manufacturer to fabricate, sell, and distribute the N.C. Hearne Straightedge. The Department's Pavement Construction Section may be contacted for the name of the current manufacturer and the approximate price of the straightedge.

No direct payment will be made for the work covered by this section. Payment at the contract unit prices for the various items covered by those sections of the specifications directly applicable to the work constructed will be full compensation for all work covered by this section including, but not limited to, performing testing in accordance with this specification, any corrective work required as a result of this testing and any additional traffic control as may be necessary.

#### **MASONRY DRAINAGE STRUCTURES:**

(10-16-07)

M8 R01

Revise the *2006 Standard Specifications* as follows:

**Page 8-25, Article 840-4 Measurement and Payment**, add the following at the end of the second paragraph:

For that portion of *Masonry Drainage Structure* measured above a height of 3 meters, payment will be made at 1.3 times the contract unit price per linear meter for *Masonry Drainage Structure*.

#### **BORROW EXCAVATION AND SHPO DOCUMENTATION FOR BORROW/WASTE**

##### **SITES:**

(12-18-07)(4-15-08)

M8 R02

Revise the *2006 Metric Standard Specifications* as follows:

#### **Division 2 Earthwork**

**Page 2-12, Subarticle 230-1(D)**, add the words: *The Contractor specifically waives* as the first words of the sentence.

**Page 2-13, Article 230-4(B) Contractor Furnished Sources, first paragraph, first sentence replace with the following:**

Prior to the approval of any borrow sources developed for use on any project, obtain certification from the State Historic Preservation Officer of the State Department of Cultural Resources certifying that the removal of the borrow material from the borrow sources(s) will have no effect on any known district, site building, structure, or object, architectural and/or archaeological that is included or eligible for inclusion in the National Register of Historic Places.

**Division 8 Incidentals**

**Page 8-8, Article 802-2 General Requirements, add the following as the 1st paragraph:**

Prior to the removal of any waste from any project, obtain certification from the State Historic Preservation Officer of the State Department of Cultural Resources certifying that the deposition of the waste material to the proposed waste area will have no effect on any known district, site building, structure, or object, architectural and/or archaeological that is included or eligible for inclusion in the National Register of Historic Places. Furnish a copy of this certification to the Engineer prior to performing any work in the proposed waste site.

**Page 8-8, Article 802-2, General Requirements, 7th paragraph, add the following as the 2nd sentence:**

The Department’s borrow and waste site reclamation procedures for contracted projects is available on the NCDOT website and shall be used for all borrow and waste sites on this project.

**MODIFIED CONCRETE FLUME WITH CONCRETE OUTLET:**

(3-19-96) (Rev. 6-17-08)

M8 R10

At locations shown in the plans, construct concrete flumes, concrete curb, and apron in accordance with the details in the plans. Use materials meeting the requirements of Section 825 of the *2006 Metric Standard Specifications* except that the concrete must be Class "B" or of higher compressive strength.

Each concrete flume, concrete curb, and apron completed and accepted will be paid for at the contract unit price per each for *Modified Concrete Flume*. Such price and payment will be full compensation for all materials, labor, equipment, tools, removing and disposing of the temporary slope drains, and any other incidentals necessary to complete the work satisfactorily.

The concrete curb and ditch outside the pay limits of the apron will be measured and paid for in accordance with Section 846 and 850 of the *2006 Metric Standard Specifications*.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Modified Concrete Flume	Each

**ENERGY DISSIPATOR:**

(2-17-98)

SPI

**Description**

Construct a concrete energy dissipator according to the details and in the locations shown on the plans. Provide all excavation, backfill, labor and material to complete this item of work. Structure may be cast-in-place or precast.

**Material**

Provide all material in accordance with Section 840-2 or Section 1077-3 as applicable. Use Class B concrete for cast-in-place or 28 MPa (4000 psi) for precast.

**Construction Methods**

Perform all work in accordance with Section 840 or Section 1077 of the *Standard Specifications* as applicable.

**Measurement and Payment**

Each structure will be measured on a "per each" basis. The quantity paid for will be the actual number completed and accepted.

Payment will be made under:

**Pay Item**

Energy Dissipator

**Pay Unit**

Each

**GUARDRAIL ANCHOR UNITS, TYPE M-350:**

(4-20-04)

M8 R60

**Description**

Furnish and install guardrail anchor units in accordance with the details in the plans, the applicable requirements of Section 862 of the *2006 Metric Standard Specifications*, and at locations shown in the plans.

**Materials**

The Contractor may, at his option, furnish any one of the following guardrail anchor units.

The guardrail anchor unit (SRT-350) as manufactured by:

Trinity Industries, Inc.  
2525 N. Stemmons Freeway  
Dallas, Texas 75207  
Telephone: 800-644-7976

The guardrail anchor unit (FLEAT) as manufactured by:

Road Systems, Inc.  
3616 Old Howard County Airport  
Big Springs, Texas 79720  
Telephone: 915-263-2435

The guardrail anchor unit (REGENT) as manufactured by:

Energy Absorption Systems, Inc.  
One East Wacker Drive  
Chicago, Illinois 60601-2076  
Telephone: 888-32-ENERGY

Prior to installation the Contractor shall submit to the Engineer:

- (A) FHWA acceptance letter for each guardrail anchor unit certifying it meets the requirements of NCHRP Report 350, Test Level 3, in accordance with Section 106-2 of the *2006 Metric Standard Specifications*.
- (B) Certified working drawings and assembling instructions from the manufacturer for each guardrail anchor unit in accordance with Section 105-2 of the *2006 Metric Standard Specifications*.

No modifications shall be made to the guardrail anchor unit without the express written permission from the manufacturer. Perform installation in accordance with the details in the plans, and details and assembling instructions furnished by the manufacturer.

### **Construction Methods**

Guardrail end delineation shall be required on all approach and trailing end sections for both temporary and permanent installations. Guardrail end delineation consists of yellow reflective sheeting applied to the entire end section of the guardrail in accordance with Section 1088-3 of the *2006 Metric Standard Specifications* and is incidental to the cost of the guardrail anchor unit.

**Measurement and Payment**

Measurement and payment will be made in accordance with Article 862-6 of the *2006 Metric Standard Specifications*.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Guardrail Anchor Units, Type M-350	Each

**GUARDRAIL ANCHOR UNITS, TYPE 350:**

(4-20-04)

M8 R65

**Description**

Furnish and install guardrail anchor units in accordance with the details in the plans, the applicable requirements of Section 862 of the *2006 Metric Standard Specifications*, and at locations shown in the plans.

**Materials**

The Contractor may at his option, furnish any one of the guardrail anchor units.

Guardrail anchor unit (ET-2000) as manufactured by:

Trinity Industries, Inc.  
2525 N. Stemmons Freeway  
Dallas, Texas 75207  
Telephone: 800-644-7976

The guardrail anchor unit (SKT 350) as manufactured by:

Road Systems, Inc.  
3616 Old Howard County Airport  
Big Spring, Texas 79720  
Telephone: 915-263-2435

Prior to installation the Contractor shall submit to the Engineer:

(A) FHWA acceptance letter for each guardrail anchor unit certifying it meets the requirements of NCHRP Report 350, Test Level 3, in accordance with Section 106-2 of the *2006 Standard Specifications*.

(B) Certified working drawings and assembling instructions from the manufacturer for each guardrail anchor unit in accordance with Section 105-2 of the *2006 Metric Standard Specifications*.



No modifications shall be made to the guardrail anchor unit without the express written permission from the manufacturer. Perform installation in accordance with the details in the plans, and details and assembling instructions furnished by the manufacturer.

**Construction Methods**

Guardrail end delineation is required on all approach and trailing end sections for both temporary and permanent installations. Guardrail end delineation consists of yellow reflective sheeting applied to the entire end section of the guardrail in accordance with Section 1088-3 of the *2006 Metric Standard Specifications* and is incidental to the cost of the guardrail anchor unit.

**Measurement and Payment**

Measurement and payment will be made in accordance with Articles 862-6 of the *2006 Metric Standard Specifications*.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Guardrail Anchor Units, Type 350	Each

**IMPACT ATTENUATOR UNITS, TYPE 350:**

(4-20-04) (Rev 7-18-06)

M8 R75

**Description**

Furnish and install impact attenuator units and any components necessary to connect the impact attenuator units in accordance with the manufacturer’s requirement, the details in the plans and at locations shown in the plans.

**Materials**

**NON-GATING IMPACT ATTENUATOR UNITS:**

The impact attenuator unit (QUADGUARD) as manufactured by:

Energy Absorption Systems, Inc.  
One East Wacker Drive  
Chicago, Illinois 60601-2076  
Telephone: 312-467-6750

The impact attenuator unit (TRACC) as manufactured by:

Trinity Industries, Inc.  
2525 N. Stemmons Freeway  
Dallas, Texas 75207  
Telephone: 800-644-7976

**GATING IMPACT ATTENUATOR UNITS:**

The impact attenuator unit (BRAKEMASTER) as manufactured by:

Energy Absorption Systems, Inc.  
One East Wacker Drive  
Chicago, Illinois 60601-2076  
Telephone: 312-467-6750

The impact attenuator unit (CAT) as manufactured by:

Trinity Industries, Inc.  
2525 N. Stemmons Freeway  
Dallas, Texas 75207  
Telephone: 800-644-7976

Prior to installation the Contractor shall submit to the Engineer:

(A) FHWA acceptance letter for each impact attenuator unit certifying it meets the requirements of NCHRP Report 350, Test Level 3, in accordance with Article 106-2 of the *2006 Metric Standard Specifications*.

(B) Certified working drawings and assembling instructions from the manufacturer for each impact attenuator unit in accordance with Article 105-2 of the *2006 Metric Standard Specifications*.

No modifications shall be made to the impact attenuator unit without the express written permission from the manufacturer. Perform installation in accordance with the details in the plans, and details and assembling instructions furnished by the manufacturer.

**Construction Methods**

If the median width is 12.2 meters or less, the Contractor shall supply one of the NON-GATING Impact Attenuator Units listed in the Materials Section herein.

If the median width is greater than 12.2 meters, the Contractor may use any of the GATING or NON-GATING Impact Attenuator Units listed in the Materials Section herein.

**Measurement and Payment**

*Impact Attenuator Unit, Type 350* will be measured and paid for at the contract unit price per each. Such prices and payment will be full compensation for all work covered by this provision including but not limited to furnishing, installing and all incidentals necessary to complete the work.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Impact Attenuator Unit, Type 350	Each

**FENCE:**

(3-6-06)

M8 R86

Revise the *2006 Metric Standard Specifications* as follows:

**Page 8-44, Subarticle 866-3(A)**, second sentence,

Add *existing fencing* after stumps

**PREFORMED SCOUR HOLE WITH LEVEL SPREADER APRON:**

(10-15-02) (Rev 6-17-08)

M8 R105

**Description**

Construct and maintain preformed scour holes with spreader aprons at the locations shown on the plans and in accordance with the details in the plans. Work includes excavation, shaping and maintaining the hole and apron, furnishing and placing filter fabric, rip rap (class as specified in the plans) and permanent soil reinforcement matting.

**Materials**

<b>Item</b>	<b>Section</b>
Plain Rip Rap	1042
Filter Fabric	1056

The permanent soil reinforcement matting shall be permanent erosion control reinforcement mat and shall be constructed of 100% coconut fiber stitch bonded between a heavy duty UV stabilized cusped (crimped) netting overlaid with a heavy duty UV stabilized top net. The three nettings shall be stitched together on 38 mm centers UV stabilized polyester thread to form a permanent three dimensional structure. The mat shall have the following physical properties:

<i>Property</i>	<i>Test Method</i>	<i>Value Unit</i>
Light Penetration	ASTM D6567	15 %
Thickness	ASTM D6525	13 mm
Mass Per Unit Area	ASTM D6566	0.339 kg/m <sup>2</sup>
Tensile Strength	ASTM D6818	572 kg/m
Elongation (Maximum)	ASTM D6818	49 %
Resiliency	ASTM D6524	> 70 %
UV Stability*	ASTM D4355	≥80 %
Porosity (Permanent Net)	Calculated	≥85 %
Minimum Filament	Measured	0.76 mm
Maximum Permissible Shear Stress (Vegetated)	Performance Test	≥ 39.1 kg/m <sup>2</sup>
Maximum Allowable Velocity	Performance Test	≥ 4.9 m/s

\*ASTM D1682 Tensile Strength and % strength retention of material after 1000 hours of exposure.

Submit a certification from the manufacturer showing:

- (A) the chemical and physical properties of the mat used, and
- (B) conformance of the mat with this specification

**Soil Preparation**

All areas to be protected with the mat shall be brought to final grade and seeded in accordance with Section 1660. The surface of the soil shall be smooth, firm, stable and free of rocks, clods, roots or other obstructions that would prevent the mat from lying in direct contact with the soil surface. Areas where the mat is to be placed will not need to be mulched.

**Measurement and Payment**

*Performed Scour Holes with Level Spreader Aprons* will be measured and paid as the actual number that has been incorporated into the completed and accepted work. Such price and payment will be full compensation for all work covered by this provision.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Performed Scour Hole with Level Spreader Aprons	Each

**STREET SIGNS AND MARKERS AND ROUTE MARKERS:**

(7-1-95)

M9 R01

Move any existing street signs, markers, and route markers out of the construction limits of the project and install the street signs and markers and route markers so that they will be visible to the traveling public if there is sufficient right of way for these signs and markers outside of the construction limits.

Near the completion of the project and when so directed by the Engineer, move the signs and markers and install them in their proper location in regard to the finished pavement of the project.

Stockpile any signs or markers that cannot be relocated due to lack of right of way, or any signs and markers that will no longer be applicable after the construction of the project, at locations directed by the Engineer for removal by others.

The Contractor shall be responsible to the owners for any damage to any street signs and markers or route markers during the above described operations.

No direct payment will be made for relocating, reinstalling, and/or stockpiling the street signs and markers and route markers as such work shall be considered incidental to other work being paid for by the various items in the contract.

**STEEL U-CHANNEL POSTS:**

(7-18-06)

M9 R02

Revise the *2006 Metric Standard Specifications* as follows:

**Page 9-12 Subarticle 903-3(D)** first paragraph, last sentence, delete the last sentence and add the following:

Use posts of sufficient length to permit the appropriate sign mounting height. Spliced posts are not permitted on new construction.

**AGGREGATE PRODUCTION:**

(11-20-01)

M10 R05

Provide aggregate from a producer who uses the current Aggregate Quality Control/Quality Assurance Program that is in effect at the time of shipment.

No price adjustment is allowed to contractors or producers who use the program. Participation in the program does not relieve the producer of the responsibility of complying with all requirements of the *2006 Metric Standard Specifications*. Copies of this procedure are available upon request from the Materials and Test Unit.

**CONCRETE BRICK AND BLOCK PRODUCTION:**

(11-20-01)

M10 R10

Provide concrete brick and block from a producer who uses the current Solid Concrete Masonry Brick/Unit Quality Control/Quality Assurance Program that is in effect on the date that material is received on the project.

No price adjustment is allowed to contractors or producers who use the program. Participation in the program does not relieve the producer of the responsibility of complying with all requirements of the *2006 Metric Standard Specifications*. Copies of this procedure are available upon request from the Materials and Test Unit.

**PORTLAND CEMENT CONCRETE (Alkali-Silica Reaction):**

(2-20-07)

M10 R16

Revise the *2006 Metric Standard Specifications* as follows:

**Article 1024-1(A)**, replace the 2nd paragraph with the following:

Certain combinations of cement and aggregate exhibit an adverse alkali-silica reaction. The alkalinity of any cement, expressed as sodium-oxide equivalent, shall not exceed 1.0 percent. For mix designs that contain non-reactive aggregates and cement with an alkali content less than

0.6%, straight cement or a combination of cement and fly ash, cement and ground granulated blast furnace slag or cement and microsilica may be used. The pozzolan quantity shall not exceed the amount shown in Table 1024-1. For mixes that contain cement with an alkali content between 0.6% and 1.0%, and for mixes that contain a reactive aggregate documented by the Department, regardless of the alkali content of the cement, use a pozzolan in the amount shown in Table 1024-1.

Obtain the list of reactive aggregates documented by the Department at:  
<http://www.ncdot.org/doh/operations/materials/pdf/quarryasrprob.pdf>

<b>Table 1024-1</b>	
<b>Pozzolans for Use in Portland Cement Concrete</b>	
<i>Pozzolan</i>	<i>Rate</i>
Class F Fly Ash	20% by weight of required cement content, with 1.2 kg Class F fly ash per kg of cement replaced
Ground Granulated Blast Furnace Slag	35%-50% by weight of required cement content with 1 kg slag per kg of cement replaced
Microsilica	4%-8% by weight of required cement content, with 1 kg microsilica per kg of cement replaced

**GLASS BEADS:**

(7-18-06)

M10 R35

Revise the 2006 *Metric Standard Specifications* as follows:

**Page 10-182, 1087-4(C) Gradation & Roundness**

Replace the second sentence of the first paragraph with the following:

*All Drop-On and Intermixed Glass Beads shall be tested in accordance with ASTM D1155.*

Delete the last paragraph.

**ENGINEERING FABRICS TABLE 1056-1:**

(7-18-06)

M10 R40

Revise the *2006 Metric Standard Specifications* as follows:

**Page 10-80, Table 1056-1**, replace the values for Trapezoidal Tear Strength with the following:

Physical Property	ASTM Test Method	Type 1	Type 2	Type 3		Type 4
				Class A	Class B	
Typical Applications		Shoulder Drain	Under Riprap	Temporary Silt Fence		Soil Stabilization
Trapezoidal Tear Strength	D4533	200 N	334 N	--	--	334 N

**PORTABLE CONCRETE BARRIER**

(2-20-07)

M10 R50

The *2006 Metric Standard Specifications* is revised as follows:

**Page 10-200, Article 1090-1(A) General**, add the following after the first sentence:

The requirement for approved galvanized connectors will be waived if the barrier remains the property of the Contractor.

**TEMPORARY SHORING:**

(2-20-07) (Rev 9-25-07)

M11 R02

**Description**

Design and construct temporary shoring in accordance with the contract. Temporary shoring includes standard shoring, temporary mechanically stabilized earth (MSE) walls and non-anchored temporary shoring. Trench boxes are not considered temporary shoring. "Standard shoring" refers to *standard temporary shoring* and *standard temporary MSE walls*. Notes on plans may restrict the use of one or both types of standard shoring. Notes on plans may also require or prohibit temporary MSE walls.

Unless noted otherwise on the plans, temporary shoring is required as shown on the plans and to maintain traffic. Temporary shoring to maintain traffic is defined as shoring necessary to provide lateral support to the side of an excavation or embankment parallel to an open travelway when a theoretical 2:1 (H:V) slope from the bottom of the excavation or embankment intersects the existing ground line closer than 1.5 m from the edge of pavement of the open travelway.

This provision is not applicable to anchored temporary shoring or the installation of pipes, drop inlets and utilities unless noted otherwise on the plans. Provide all shoring submittals before beginning work.

## **Materials**

### **(A) Certifications, Storage and Handling**

Provide Type 7 Contractor's Certifications in accordance with Article 106-3 of the *2006 Metric Standard Specifications* for all shoring materials used with the exception of reinforcing fabrics and geogrids. Furnish Type 2 Typical Certified Mill Test Reports in accordance with Article 106-3 of the *2006 Metric Standard Specifications* for all seam strengths and reinforcing fabric and geogrid properties. Provide minimum average roll values (MARV) in accordance with ASTM D4759 for test reports. For testing reinforcing fabric and geogrids, a lot is defined as a single day's production.

Load, transport, unload and store shoring materials such that they are kept clean and free of damage. Identify, store and handle all geogrids and geotextile fabrics in accordance with ASTM D4873. Geogrids and fabrics with defects, flaws, deterioration or damage will be rejected. Do not leave fabrics or geogrids uncovered for more than 7 days.

### **(B) Shoring Backfill**

Use shoring backfill for the construction of all temporary shoring including backfilling behind non-anchored temporary shoring and in the reinforced zone for temporary MSE walls. Unless backfilling around culverts, use shoring backfill that meets the requirements of Class II Type I, Class III, Class V or Class VI select material in accordance with Section 1016 of the *2006 Metric Standard Specifications* or AASHTO M145 for soil classification A-2-4 with a maximum plasticity index (PI) of 6. For backfilling around culverts, use shoring backfill as defined herein except for A-2-4 soil.

### **(C) Non-anchored Temporary Shoring**

Use steel shapes, plates and piles that meet the requirements of ASTM A36 and steel sheet piles that meet the requirements of Article 1084-2 of the *2006 Metric Standard Specifications*. Use timber lagging with a minimum allowable bending stress of 6.9 MPa that meets the requirements of Article 1082-1 of the *2006 Metric Standard Specifications*. For standard temporary shoring, use pile sections and lengths and lagging sizes as shown on the plans.

### **(D) Temporary MSE Walls**

Use welded wire reinforcement forms, facings, mesh and mats that meet the requirements of AASHTO M55 or M221. Use connector bars and wires for welded wire wall components and support struts that meet the requirements of AASHTO M32. For



standard temporary MSE walls, use wire gauges, strut sizes and welded wire components as shown on the plans.

**(1) Geotextile Fabrics**

Use geotextile fabrics that meet the requirements of Article 1056-1 of the *2006 Metric Standard Specifications*.

**(a) Reinforcing Fabric**

The reinforcement direction (RD) is defined as the direction perpendicular to the wall face and the cross-reinforcement direction (CRD) is defined as the direction parallel to the wall face.

Use woven polyester or polypropylene fabric that meets the following properties:

Property	Test Method	Requirement (MARV)
Wide Width Tensile Strength @ Ultimate (RD)	ASTM D4595	Varies – 35 kN/m min
Wide Width Tensile Strength @ Ultimate (CRD)	ASTM D4595	18 kN/m min
Trapezoidal Tear Strength	ASTM D4533	0.44 kN min
CBR Puncture Strength	ASTM D6241	2.67 kN min
UV Resistance after 500 hrs	ASTM D4355	70 %
Apparent Opening Size (AOS), US Sieve	ASTM D4751	0.212 mm min – 0.850 mm max
Permittivity	ASTM D4491	0.20 sec <sup>-1</sup>

For standard temporary MSE walls (temporary fabric wall) use reinforcing fabric wide width tensile strengths and lengths in the RD as shown on the plans.

**(b) Retention Fabric**

Retain shoring backfill at the face of temporary MSE walls with retention fabric. Use fabric that meets the requirements of Class 3 and the UV resistance, AOS and permittivity for separation geotextile in accordance with AASHTO M288.

**(2) SierraScape Temporary Wall**

Use uniaxial (UX) geogrids composed of high-density polyethylene (HDPE) manufactured by Tensar Earth Technologies. Test geogrids in accordance with ASTM D6637. Use connection rods manufactured by Tensar Earth Technologies to transfer the load between the facings and geogrids.

For standard temporary MSE walls (SierraScape temporary wall) use geogrid types and lengths as shown on the plans.

### **(3) Terratrel Temporary Wall**

Use ribbed reinforcing steel strips manufactured by The Reinforced Earth Company that meet the requirements of ASTM A572, Grade 450. Use connector rods that meet the requirements of AASHTO M31, Grade 415 and hair pin connectors that meet the requirements of ASTM A1011, Grade 345. Use bolts, nuts and washers that meet the requirements of AASHTO M164.

For standard temporary MSE walls (Terratrel temporary wall) use ribbed steel strip size and lengths, rod lengths and diameters, hairpin connectors, bolts, nuts and washers as shown on the plans.

### **Embedment**

“Embedment” is defined as the depth of shoring below the bottom of the excavation or the grade in front of the shoring. For cantilever shoring, embedment is the depth of the piling below the grade in front of the shoring. For temporary MSE walls, embedment is the difference between the grade elevation in front of the wall and the elevation of the bottom of the reinforced zone.

### **Portable Concrete Barriers**

Provide portable concrete barriers in accordance with the plans and if shoring is located within the clear zone as defined in the *AASHTO Roadside Design Guide*. Use NCDOT portable concrete barriers (PCBs) in accordance with Roadway Metric Standard Drawing No. 1170.01 and Section 1170 of the *2006 Metric Standard Specifications*. Use Oregon Tall F-Shape Concrete Barriers in accordance with detail drawing and special provision obtained from:

<http://www.ncdot.org/doh/preconstruct/wztc/DesRes/English/DesResEng.html>

The clear distance is defined as the horizontal distance from the back face of the barrier to the edge of pavement and the minimum required clear distance is shown on the traffic control plans. At the Contractor’s option or if the minimum required clear distance is not available, set an unanchored PCB against the traffic side of the shoring and design shoring for traffic impact or use the “surcharge case with traffic impact” for the standard temporary shoring. An anchored PCB or Oregon barrier is required for barriers above and behind temporary MSE walls.

### **Contractor Designed Shoring**

“Contractor designed shoring” is defined as non-anchored temporary shoring or temporary MSE walls designed by the Contractor. Unless prohibited or required, Contractor designed shoring is optional. Contractor designed shoring is required when notes on plans prohibit the use of standard shoring. Non-anchored Contractor designed shoring is prohibited when notes on plans

require the use of temporary MSE walls and Contractor designed temporary MSE walls are prohibited when notes on plans prohibit the use of temporary MSE walls.

Before beginning design, survey the shoring location to determine existing elevations and actual design heights. Submit design calculations and drawings including typical sections for review and acceptance showing details of the proposed design and construction sequence in accordance with Article 105-2 of the *2006 Metric Standard Specifications*. Have shoring designed, detailed and sealed by a Professional Engineer registered in the State of North Carolina. Submit 3 hard copies of design calculations and 10 hard copies of drawings and an electronic copy (pdf or jpeg format on CD or DVD) of both the calculations and drawings.

Design non-anchored temporary shoring in accordance with the *AASHTO Guide Design Specifications for Bridge Temporary Works* and temporary MSE walls in accordance with the *AASHTO Allowable Stress Design Standard Specifications for Highway Bridges*. Use the following soil parameters for shoring backfill in the reinforced zone.

Total Unit Weight =  $18.8 \text{ kN/m}^3$   
Friction Angle = 30 degrees  
Cohesion = 0 kPa

Design temporary shoring in accordance with the in-situ assumed soil parameters shown on the plans. Design shoring for a 3-year design service life and a traffic surcharge equal to 11.5 kPa. This surcharge is not applicable for construction traffic. If a construction surcharge will be present within a horizontal distance equal to the height of the shoring, design the shoring for the required construction surcharge. If the edge of pavement or a structure to be protected is within a horizontal distance equal to the height of the shoring, design shoring for a maximum deflection of 75 mm. Otherwise, design shoring for a maximum deflection of 150 mm.

For non-anchored temporary shoring, the top of shoring elevation is defined as the elevation where the grade intersects the back face of the shoring. For traffic impact, apply 29.2 kN/m to the shoring 450 mm above the top of shoring elevation. When designing for traffic impact, extend shoring at least 800 mm above the top of shoring elevation. Otherwise, extend shoring at least 150 mm above the top of shoring elevation.

### **Standard Shoring**

Unless notes on plans prohibit the use of one or both types of standard shoring, standard shoring is optional. Submit a "Standard Temporary MSE Wall Selection Form" for each standard temporary MSE wall location and a "Standard Temporary Shoring Selection Form" for up to three standard temporary shoring locations. Submit selection forms at least 14 days before beginning shoring construction. Obtain standard shoring selection forms from:

<http://www.ncdot.org/doh/preconstruct/highway/geotech/formdet/>

**(A) Standard Temporary Shoring**

Determine the shoring height, traffic impact, groundwater condition and slope or surcharge case for each standard temporary shoring location. Determine the minimum required extension, embedment and sheet pile section modulus or H pile section from the plans for each location.

**(B) Standard Temporary MSE Walls**

Choose a standard temporary MSE wall from the multiple temporary MSE wall options shown in the plans. Do not use more than one option per wall location.

Step bottom of reinforced zone in increments equal to vertical reinforcement spacing for the wall option chosen. Determine the wall height and slope or surcharge case for each section of standard temporary MSE wall. With the exception of either the first or last section of wall, use horizontal section lengths in increments equal to the following for the wall option chosen.

Standard Temporary MSE Wall Option	Increment
Temporary Fabric Wall	2.7 m min (varies)
Hilfiker Temporary Wall	3.0 m min (varies)
SierraScape Temporary Wall	5.7 m
Retained Earth Temporary Wall	7.3 m
Terratrel Temporary Wall	6.0 m

Determine the appropriate facings and/or forms and reinforcement length, spacing, strength, type, density and/or size from the plans for each wall section.

**Construction Methods**

When using an anchored PCB, anchor the barrier in accordance with Roadway Metric Standard Drawing 1170.01 and Section 1170 of the *2006 Metric Standard Specifications*. Control drainage during construction in the vicinity of temporary shoring. Collect and direct run off away from temporary MSE walls, shoring and shoring backfill.

**(A) Non-anchored Temporary Shoring**

Install and interlock sheet piling or install piles as shown on the plans or accepted submittals with a tolerance of 42 mm per meter from vertical. Contact the Engineer if the design embedment is not achieved. If piles are placed in drilled holes, perform pile excavation to the required elevations and backfill excavations with concrete and lean sand grout.

Remove grout as necessary to install timber lagging. Install timber lagging with a minimum bearing distance of 75 mm on each pile flange. Backfill voids behind lagging with shoring backfill.

Perform welding in accordance with the accepted submittals and Article 1072-20 of the *2006 Metric Standard Specifications*.

**(1) Pile Excavation**

Excavate a hole with a diameter that will result in at least 75 mm of clearance around the entire pile. Use equipment of adequate capacity and capable of drilling through soil and non-soil including rock, boulders, debris, man-made objects and any other materials encountered. Blasting is not permitted to advance excavations. Blasting for core removal is permitted only when approved by the Engineer. Dispose of drilling spoils in accordance with Section 802 of the *2006 Metric Standard Specifications*. Drilling spoils consist of all excavated material including water removed from excavations by either pumping or drilling tools.

If unstable, caving or sloughing soils are encountered, stabilize excavations with clean watertight steel casing. Steel casings may be either sectional type or one continuous corrugated or non-corrugated piece. Provide casings of ample strength to withstand handling and driving stresses and the pressures imposed by concrete, earth or backfill. Use steel casings with an outside diameter equal to the hole size and a minimum wall thickness of 6 mm.

Before placing concrete, check the water inflow rate in the excavation after any pumps have been removed. If the inflow rate is less than 150 mm per half hour, remove any water and free fall the concrete into the excavation. Ensure that concrete flows completely around the pile. If the water inflow rate is greater than 150 mm per half hour, propose and obtain approval of the concrete placement procedure before placing concrete.

Center the pile in the excavation and fill the excavation with Class A concrete in accordance with Section 1000 of the *2006 Metric Standard Specifications* except as modified herein. Provide concrete with a slump of 150 to 200 mm. Use an approved high-range water reducer to achieve this slump. Place concrete in a continuous manner to the bottom of shoring or the elevations shown on the accepted submittals. Fill the remainder of the excavation with a lean sand grout and remove all casings.

**(B) Temporary MSE Walls**

The Engineer may require a wall preconstruction meeting to discuss the construction and inspection of the temporary MSE walls. If required, conduct the meeting with the Site Superintendent, the Resident or Bridge Maintenance Engineer, the Bridge Construction Engineer and the Geotechnical Operations Engineer before beginning wall construction.

Perform all necessary clearing and grubbing in accordance with Section 200 of the *2006 Metric Standard Specifications*. Excavate as necessary as shown on the plans or accepted submittals. Notify the Engineer when foundation excavation is complete. Do not place shoring backfill or first reinforcement layer until obtaining approval of the excavation depth and foundation material.

If applicable, install foundations located within the reinforced zone in accordance with the plans or accepted submittals.

Erect and maintain facings and forms as shown on the plans or accepted submittals. Stagger vertical joints of facings and forms to create a running bond when possible unless shown otherwise on the plans or accepted submittals.

Place facings and forms as near to vertical as possible with no negative batter. Construct temporary MSE walls with a vertical and horizontal tolerance of 75 mm when measured with a 3 m straight edge and an overall vertical plumbness (batter) and horizontal alignment of less than 150 mm.

Place reinforcement at locations and elevations shown on the plans or accepted submittals and in slight tension free of kinks, folds, wrinkles or creases. Repair or replace any damaged reinforcement. Contact the Engineer when existing or future structures such as foundations, pavements, pipes, inlets or utilities will interfere with reinforcement. To avoid structures, deflect, skew and modify reinforcement.

Do not splice reinforcement in the reinforcement direction (RD), i.e., parallel to the wall face. Seams are allowed in the cross-reinforcement direction (CRD). Bond or sew adjacent reinforcing fabric together or overlap fabric a minimum of 450 mm with seams oriented perpendicular to the wall face.

Place shoring backfill in 200 to 250 mm thick lifts and compact in accordance with Subarticle 235-4(C) of the *2006 Metric Standard Specifications*. Use only hand operated compaction equipment within 1 m of the wall face. Do not damage reinforcement when placing and compacting shoring backfill. End dumping directly on the reinforcement is not permitted. Do not operate heavy equipment on reinforcement until it is covered with at least 250 mm of shoring backfill. Do not use sheepsfoot, grid rollers or other types of compaction equipment with feet.

Cover reinforcing and retention fabric with at least 75 mm of shoring backfill. Place top reinforcement layer between 100 to 600 mm below top of wall as shown on the plans or accepted submittals.

Bench temporary MSE walls into the sides of excavations where applicable. If the top of wall is within 1.5 m of finished grade, remove top form or facing and incorporate the top reinforcement layer into the fill when placing fill in front of the wall. Temporary MSE walls remain in place permanently unless required otherwise.

**Measurement and Payment**

*Temporary Shoring* will be measured and paid for at the contract unit price per square meter of exposed face area at locations shown on the plans or required by the Engineer. For temporary MSE walls, the wall height will be measured as the difference between the top and bottom of wall and does not include the embedded portions of the wall or any pavement thickness above the wall. For all other temporary shoring, the shoring height will be measured as the difference between the top and bottom of shoring elevation. The bottom of shoring elevation is defined as where the grade intersects the front face of the shoring. The top of shoring elevation is defined as where the grade intersects the back face of the shoring. No payment will be made for any extension of shoring above the top of shoring or any embedment below the bottom of shoring. Such price and payment will be full compensation for furnishing all labor, tools, equipment, materials and all incidentals necessary to design and install the temporary shoring and complete the work as described in this provision.

No payment will be made for temporary shoring not shown on the plans or required by the Engineer including shoring for OSHA reasons or the Contractor’s convenience. No value engineering proposals will be accepted based solely on revising or eliminating the shoring locations shown on the plans or the estimated quantities shown in the bid item sheets as a result of actual field measurements or site conditions.

No additional payment will be made for anchoring PCBs or providing Oregon barriers in lieu of unanchored PCBs. Additional costs for anchoring PCBs or providing Oregon barriers will be considered incidental to *Temporary Shoring*.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Temporary Shoring	Square Meter

**ANCHORED TEMPORARY SHORING: (SPECIAL)**

**Description**

Anchored temporary shoring consists of sheet piling or H piles with timber lagging anchored with ground or helical anchors. At the Contractor’s option, use anchored temporary shoring in lieu of temporary shoring. Design and construct anchored temporary shoring based on actual

elevations and dimensions in accordance with the contract and accepted submittals. For this provision, “anchored shoring” refers to anchored temporary shoring and “Anchored Shoring Contractor” refers to the contractor installing the anchors. Use an Anchored Shoring Contractor prequalified by the NCDOT Construction Unit for anchored retaining walls work (work code 3020).

### **Materials**

Provide Type 7 Contractor’s Certifications in accordance with Article 106-3 of the *Standard Specifications* for all anchored shoring materials. Store steel materials on blocking a minimum of 12” (300 mm) above the ground and protect it at all times from damage; and when placing in the work make sure it is free from dirt, dust, loose mill scale, loose rust, paint, oil or other foreign materials. Damaged, bent or twisted materials will be rejected.

Use steel shapes, plates and piles meeting the requirements of ASTM A36 and steel sheet piles meeting the requirements of Article 1084-2 of the *Standard Specifications*. Use timber lagging with a minimum allowable bending stress of 1000 psi (6.9 MPa) that meets the requirements of Article 1082-1 of the *Standard Specifications*.

#### **(A) Ground Anchors**

A ground anchor consists of a grouted steel bar or strands. Use high-strength steel bars meeting the requirements of AASHTO M275 or seven-wire strands meeting the requirements of ASTM A886 or Article 1070-5 of the *Standard Specifications*. Splice bars in accordance with Article 1070-10 of the *Standard Specifications*. Do not splice strands.

Fabricate centralizers from schedule 40 polyvinyl chloride (PVC) plastic pipe or tube, steel or other material not detrimental to bars or strands (no wood). Size centralizers to position the bar or strands within 1 inch (25 mm) of the drill hole center and allow a tremie to be inserted to the bottom of the hole. Use centralizers that do not interfere with grout placement or flow around bars or strands.

Use grout in accordance with the contract.

#### **(B) Helical Anchors**

A helical anchor consists of a lead section with a central steel shaft and at least one helix steel plate followed by extensions with only central shafts (no helixes). Use helical anchors with an ICC Evaluation Service, Inc. (ICC-ES) report. Helical anchors without an ICC-ES report may be approved at the discretion of the Engineer. Provide couplers, thread bar adapters and bolts for connecting anchors together and to piling in accordance with the anchor manufacturer’s recommendations.



**(C) Anchor Heads**

Anchor heads consist of bearing plates with hex nuts and washers for bars and wedge plates and wedges for strands. Provide bearing plates meeting the requirements of ASTM A36 and hex nuts, washers, wedge plates and wedges in accordance with the anchor manufacturer's recommendations.

**(D) Shoring Backfill**

Use shoring backfill meeting the requirements of Class II Type I, Class III, Class V or Class VI Select Material in accordance with Section 1016 of the *Standard Specifications* or AASHTO M145 for soil classification A-2-4 with a maximum plasticity index (PI) of 6.

**Design**

Before beginning design, survey Contractor designed shoring locations to determine existing elevations and actual design heights. Design anchored shoring in accordance with the plans and the *FHWA Geotechnical Engineering Circular No. 4 "Ground Anchors and Anchored Systems"* (Publication No. FHWA-IF-99-015).

Provide portable concrete barriers in accordance with the contract for barriers for temporary shoring. The top of shoring elevation is defined as the elevation where the grade intersects the back face of the anchored shoring. For traffic impact, apply 2 kips/ft (29.2 kN/m) to the anchored shoring 1.5 ft (5 m) above the top of shoring elevation. When designing for traffic impact, extend anchored shoring at least 32" (800 mm) above the top of shoring elevation. Otherwise, extend anchored shoring at least 6" (150 mm) above the top of shoring elevation.

Design anchored shoring for a 3-year design service life and a traffic surcharge equal to 240 psf (11.5 kPa). This surcharge is not applicable for construction traffic. If a construction surcharge will be present within a horizontal distance equal to the height of the shoring, design the anchored shoring for the required construction surcharge.

Do not extend anchors beyond right-of-way or easement lines. Extend the unbonded length for ground anchors or the shallowest helix for helical anchors at least 5 ft (1.5 m) behind the critical failure surface. If existing or future obstructions such as foundations, guardrail posts, pavements, pipes, inlets or utilities will interfere with anchors, maintain a minimum clearance of 6" (150 mm) between the obstruction and the anchors.

Determine anchor loads for ground and helical anchors in accordance with *Geotechnical Engineering Circular No. 4*. Size anchors such that design loads do not exceed 60% of bar, strand or central shaft tensile strengths. Also, size anchors such that maximum test loads do not exceed 80% of bar, strand or central shaft tensile strengths and lock-off loads do not exceed 70% of tensile strengths.

Submit anchored shoring designs including unit grout/ground bond strengths for ground anchors and installation torque requirements for helical anchors for review and acceptance in accordance with Article 105-2 of the *Standard Specifications*. Submit working drawings showing plan views, shoring profiles with anchor locations and typical sections with anchor, piling and shoring details. If necessary, include details on working drawings for obstructions interfering with anchors or extending through shoring. Submit design calculations for each anchored shoring section with different surcharge loads, shoring geometry or material parameters. A minimum of one analysis is required for each shoring section with different anchor lengths. Submit 3 hard copies of design calculations and 10 hard copies of drawings and an electronic copy (pdf or jpeg format on CD or DVD) of both the calculations and drawings. Have anchored shoring designed, detailed and sealed by a Professional Engineer registered in North Carolina.

### **Construction Methods**

When using an anchored NCDOT portable concrete barrier (PCB), anchor the barrier in accordance with Roadway Standard Drawing 1170.01 and Section 1170 of the *Standard Specifications*. Control drainage during construction in the vicinity of anchored shoring. Collect and direct run off away from anchored shoring and areas above and behind shoring.

Before starting anchored shoring construction, conduct a preconstruction meeting to discuss the construction, inspection and testing of the anchored shoring. Schedule this meeting after all anchored shoring submittals have been accepted. The Resident or Bridge Maintenance Engineer, Bridge Construction Engineer, Geotechnical Operations Engineer, Contractor and Anchored Shoring Contractor Superintendent and Project Manager will attend this preconstruction meeting.

Notify the Engineer before blasting in the vicinity of anchored shoring. Perform blasting in accordance with the contract. Install foundations located behind anchored shoring and within a horizontal distance equal to the longest anchor length before beginning anchored shoring construction.

Install and interlock sheet piling or install H piles as shown on the plans or accepted submittals with a tolerance of 1/2 inch per foot (42 mm per meter) from vertical. Contact the Engineer if the design embedment is not achieved. If piles are placed in drilled holes, perform pile excavation to the required elevations and backfill excavations with concrete and lean sand grout.

Remove grout as necessary to install timber lagging. Ensure at least 3" (75 mm) of contact in the horizontal direction between the lagging and pile flanges.

Backfill voids and fill sections behind lagging and piling with shoring backfill. Perform welding in accordance with the accepted submittals and Article 1072-20 of the *Standard Specifications*.

#### **(A) Pile Excavation**

Excavate a hole with a diameter that will result in at least 3" (75 mm) of clearance around the entire pile. Use equipment of adequate capacity and capable of drilling through soil and non-soil including rock, boulders, debris, man-made objects and any other materials

encountered. Blasting is not permitted to advance excavations. Blasting for core removal is permitted only when approved by the Engineer. Dispose of drilling spoils in accordance with Section 802 of the *Standard Specifications*. Drilling spoils consist of all excavated material including water removed from excavations by either pumping or drilling tools.

If unstable, caving or sloughing soils are encountered, stabilize excavations with clean watertight steel casing. Steel casings may be either sectional type or one continuous corrugated or non-corrugated piece. Provide casings of ample strength to withstand handling and driving stresses and the pressures imposed by concrete, earth or backfill. Use steel casings with an outside diameter equal to the hole size and a minimum wall thickness of 1/4 inch (6 mm).

Before placing concrete, check the water inflow rate in the excavation after any pumps have been removed. If the inflow rate is less than 6" (150 mm) per half hour, remove any water and free fall the concrete into the excavation. Ensure that concrete flows completely around the pile. If the water inflow rate is greater than 6" (150 mm) per half hour, propose and obtain approval of the concrete placement procedure before placing concrete.

Center the pile in the excavation and fill the excavation with Class A Concrete in accordance with Section 1000 of the *Standard Specifications* except as modified herein. Provide concrete with a slump of 6 to 8 inches (150 to 200 mm). Use an approved high-range water reducer to achieve this slump. Place concrete in a continuous manner to the bottom of shoring or the elevations shown on the accepted submittals. Fill the remainder of the excavation with a lean sand grout and remove all casings.

#### **(B) Anchor Installation**

Install anchors within 3 degrees and 12" (300 mm) of the inclination and location, respectively, shown in the accepted submittals. Install ground anchors in accordance with the accepted submittals and Section 6.5 of the *AASHTO LRFD Bridge Construction Specifications* with the exception of corrosion protection requirements.

Install helical anchors in accordance with the accepted submittals and the anchor manufacturer's instructions. Measure the torque during installation and do not exceed the torsion strength rating of the helical anchors. Satisfy the minimum installation torque and length requirements before terminating anchor installation. When replacing helical anchors, embed the last helix of the replacement anchor at least 3 helix plate diameters past where the first helix of the previous anchor was located.

#### **(C) Anchor Testing**

Proof test all anchors in accordance with the accepted submittals and Section 6.5.5 of the *AASHTO LRFD Bridge Construction Specifications* with the exception of the acceptance criteria in Section 6.5.5.5. For this provision and these AASHTO specifications, "ground

anchor” refers to a ground or helical anchor and “tendon” refers to a bar or strand for a ground anchor and a central shaft for a helical anchor.

**(D) Anchor Acceptance**

Anchor acceptance is based on the following criteria.

1. For ground and helical anchors, total movement is less than 0.04” (1 mm) between the 1 and 10 minute readings or less than 0.08” (2 mm) between the 6 and 60 minute readings.
2. For ground anchors, total movement at maximum test load exceeds 80 percent of the theoretical elastic elongation of the unbonded length.

**(E) Anchor Test Results**

Submit 2 original hard copies of anchor test records including load versus movement curves within 24 hours of completing each test. The Engineer will review the test records to determine if the anchor is acceptable.

If the Engineer determines an anchor is unacceptable, revise the anchored shoring design. Submit a revised anchored shoring design for review and acceptance and provide an acceptable anchor with the revised design and/or installation methods at no additional cost to the Department. If required, replace anchors and/or provide additional anchors with the revised design and/or installation methods at no additional cost to the Department.

After completing all anchor testing for each anchored shoring, submit electronic copies (pdf or jpg format on CD or DVD) of all corresponding test records.

**Measurement and Payment**

Anchored temporary shoring will be measured as the exposed face area and the anchored shoring height will be measured as the difference between the top and bottom of shoring elevation. The bottom of shoring elevation is defined as where the grade intersects the front face of the anchored shoring. The top of shoring elevation is defined as where the grade intersects the back face of the anchored shoring. No payment will be made for any extension of anchored shoring above the top of shoring or any embedment below the bottom of shoring.

If the Contractor elects to use anchored temporary shoring in lieu of temporary shoring, the anchored shoring will be paid for at the contract unit price bid for *Temporary Shoring*. Such price and payment will be full compensation for design, submittals, furnishing labor, tools, equipment and materials, excavating lifts, installing piling and anchors, grouting, providing timber lagging, backfill and any incidentals necessary to design and construct anchored shoring in accordance with this provision.

**CHANGEABLE MESSAGE SIGNS**

(11-21-06)

M11 R11

Revise the *2006 Metric Standard Specifications* as follows:

**Page 11-7, Article 1120-3**, Replace the 3rd sentence with the following:

Sign operator will adjust flash rate so that no more than two messages will be displayed and be legible to a driver when approaching the sign at the posted speed.

**PAVEMENT MARKING LINES:**

(11-21-06) (Rev. 9-18-07)

M12 R01

Revise the *2006 Metric Standard Specifications* as follows:

**Page 12-11, Subarticle 1205-10, Measurement and Payment**, delete the first sentence of the first paragraph and replace with the following:

*Pavement Marking Lines* will be measured and paid for as the actual number of linear meters of pavement marking lines per application that has been satisfactorily placed and accepted by the Engineer.

**PERMANENT SEEDING AND MULCHING:**

(7-1-95)

M16 R01

The Department desires that permanent seeding and mulching be established on this project as soon as practical after slopes or portions of slopes have been graded. As an incentive to obtain an early stand of vegetation on this project, the Contractor's attention is called to the following:

For all permanent seeding and mulching that is satisfactorily completed in accordance with the requirements of Section 1660, Seeding and Mulching, and within the following percentages of elapsed contract times, an additional payment will be made to the Contractor as an incentive additive. The incentive additive will be determined by multiplying the number of acres of seeding and mulching satisfactorily completed times the contract unit bid price per acre for Seeding and Mulching times the appropriate percentage additive.

<b>Percentage of Elapsed Contract Time</b>	<b>Percentage Additive</b>
0% - 30%	30%
30.01% - 50%	15%

Percentage of elapsed contract time is defined as the number of calendar days from the date of availability of the contract to the date the permanent seeding and mulching is acceptably completed divided by the total original contract time.

109-A

**MM PIPE LINER:**  
(6-15-04)

SPI

**Description**

Furnish, haul and install all pipe, fittings, couplings and other material; construct joint connections; and clean out the existing pipe for \_\_ MM Pipe Liner inside the existing \_\_ MM CS Pipe as shown in the plans.

**Materials**

<b>Item</b>	<b>Section</b>
Corrugated Steel Culvert Pipe	1032-3(A)

Alternate methods of pipe lining may be approved. Alternate methods shall provide increased structural capacity as well as increased protection from infiltration/exfiltration.

**Construction Methods**

Install the pipe liner in accordance with the applicable requirements of Section 310 of the *Standard Specifications*. Pipe liner size shall be verified in the field. Provide the largest diameter pipe liner that will fit inside the existing pipe.

**Measurement and Payment**

\_\_ MM Pipe Liner will be measured and paid as the actual number of linear meters of pipe, that has been installed and accepted. Measurement will be made by counting the number of joints used and multiplying the length of the joint. Where partial joints are used, measurement will be made along the longest length of the partial joint to the nearest 0.1 of a meter.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
__ MM Pipe Liner	Linear Meter

**GROUT FOR PIPE LINER:**  
(6-15-04)

SPI

**Description**

Furnish and install grout between the \_\_ MM Pipe Liner and the existing CS Pipe as shown in the plans.

**Materials**

Use a grout which has a minimum compressive strength of 3,000 psi at three days and which meets the applicable requirements of Subarticle 1054-6 of the *Standard Specifications*.

**Construction Methods**

Place the grout by pumping, pouring or other approved method.

**Measurement and Payment**

Grout will be measured and paid for as the number of cubic meters that has been acceptably placed in the pipe liner.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Grout	Cubic Meters

**ENDWALLS:**

(5-20-08)

M8 R25

Revise the *Standard Specifications* as follows:

**Page 8-23, Article 838-4 Replace the 1st and 2nd paragraph with the following:**

*Endwalls* will be measured and paid for in cubic meters of concrete or brick that have been completed and accepted. This quantity will be computed from the dimensions shown on the plans or from revised authorized dimensions. Where precast concrete units have been approved and are used in lieu of cast-in-place units the quantity to be paid for will be computed the same as if cast-in-place units were used, as no reduction in pay quantity will be made due to the use of precast in lieu of cast in place endwalls.

*Reinforced Endwalls* will be measured and paid for in cubic meters of concrete or brick that have been completed and accepted. This quantity will be computed from the dimensions shown on the plans or from revised authorized dimensions. Where precast concrete units have been approved and are used in lieu of cast-in-place units the quantity to be paid for will be computed the same as if cast-in-place units were used, as no reduction in pay quantity will be made due to the use of precast in lieu of reinforced cast in place endwalls.