

PROJECT SPECIAL PROVISIONS
Utilities

UTILITY CONFLICTS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. French Broad EMC
- B. Verizon
- C. Progress Energy
- D. Country Cable

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A. French Broad EMC
 - 1. See "Utility By Others Plans" for utility conflicts.
 - 2. The utility pole at station 109+14 -L- 18 rt (French Broad EMC pole #56) cannot be installed until grading is complete. The utility requires 14 calendar days notice to begin construction at this location, and 14 calendar days to complete construction.
 - 3. Overhead utility lines cross 3 culvert installations at stations 19+60 -L-, 11+90 -Y17-, and 82+60 -L-. The contractor shall coordinate with the utility companies to ensure the safety of the workers and utilities during construction.
 - 4. All facilities will be relocated by December 31, 2008.

- B. Verizon
 - 1. See "Utility By Others Plans" for utility conflicts.
 - 2. All power poles and facilities will be relocated by December 31, 2008.

PROJECT: R-2518A
COUNTIES: Madison/Yancey

C. Progress Energy

1. See "Utility By Others Plans" for utility conflicts.
2. All facilities will be relocated by Date of Availability.

D. Country Cable

1. See "Utility By Others Plans" for utility conflicts.
2. All power poles and facilities will be relocated by December 31, 2008.