

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	600 TON		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	9 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	12 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	64 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	8 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	125 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	115 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	13 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0019	2022000000-E	815	SUBDRAIN EXCAVATION	115 CY		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2253000000-E	840	PIPE COLLARS	1 CY		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0028	2556000000-E	846	SHOULDER BERM GUTTER	32 LF		
0029	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0033	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	305 SY		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	258 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0038	4430000000-N	1130	DRUMS	25 EA		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		
0040	4450000000-N	1150	FLAGGER	32 HR		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,000 LF		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	425 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
0046	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0048	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0049	6029000000-E	SP	SAFETY FENCE	175 LF		
0050	6030000000-E	1630	SILT EXCAVATION	135 CY		
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	210 SY		
0052	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	125 SY		
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0054	6071030000-E	SP	COIR FIBER BAFFLES	40 LF		
0055	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0056	6087000000-E	1660	MOWING	1 ACR		
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0058	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0059	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0060	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0061	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0062	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0063	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+25.50-L-)	Lump Sum	L.S.	
0064	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+25.50-L-)	Lump Sum	L.S.	
0065	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	50.4 CY		
0066	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+25.50-L-)	Lump Sum	L.S.	
0067	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,730 LB		
0068	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	360 LF		
0069	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	120 LF		
0070	8391000000-N	450	STEEL PILE POINTS	24 EA		
0071	8503000000-E	460	CONCRETE BARRIER RAIL	124.8 LF		
0072	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0073	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	624.01 LF		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" GALVANIZED STEEL SHEET PILES	2,820 SF		

0810/Jun11/Q21094.96/D312640330000/E74

Total Amount Of Bid For Entire Project :

Contract No **C201870**

County (ies): **McDowell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General