

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+00.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	650 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	850 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	259 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	1,500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	63 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	96 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	24 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	88 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	930 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	600 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	80 TON		
0018	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	38 EA		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	230 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	170 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0026	2253000000-E	840	PIPE COLLARS	1 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0028	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0030	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
0031	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	130 LF		
0032	2556000000-E	846	SHOULDER BERM GUTTER	142 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	575 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0037	3649000000-E	876	RIP RAP, CLASS B	286 TON		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,405 SY		
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	473 SF		
0040	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	183 SF		
0042	4430000000-N	1130	DRUMS	71 EA		
0043	4435000000-N	1135	CONES	25 EA		
0044	4445000000-E	1145	BARRICADES (TYPE III)	208 LF		
0045	4450000000-N	1150	FLAGGER	352 HR		
0046	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	19,660 LF		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	2,150 LF		
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	365 TON		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	230 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	240 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	9 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	350 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.25 TON		
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0055	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
0056	6029000000-E	SP	SAFETY FENCE	475 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6030000000-E	1630	SILT EXCAVATION	810 CY		
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,560 SY		
0059	6037000000-E	SP	COIR FIBER MAT	25 SY		
0060	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	925 SY		
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	550 LF		
0062	6071030000-E	SP	COIR FIBER BAFFLES	240 LF		
0063	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0064	6071050000-E	SP	*** SKIMMER (2")	2 EA		
0065	6084000000-E	1660	SEEDING & MULCHING	9.5 ACR		
0066	6087000000-E	1660	MOWING	5.5 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	150 LB		
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0069	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	250 LB		
0070	6108000000-E	1665	FERTILIZER TOPDRESSING	6.75 TON		
0071	6114000000-N	SP	SPECIALIZED HAND MOWING	4 HR		
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24 EA		
0073	6123000000-E	1670	REFORESTATION	0.5 ACR		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0074	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	380 LF		
------	--------------	-----	------------------------------------	-----------	--	--

AA1

*** OR ***

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	144 LF		
0076 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	236 LF		
*** OR ***						
0077 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	144 LF		
0078 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	236 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0079	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+25.50-L-)	Lump Sum	L.S.	
0080	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+20.00-L-)	Lump Sum	L.S.	
0081	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (12+25.50-L-)	Lump Sum	L.S.	
0082	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,198 SF		
0083	8161000000-E	420	GROOVING BRIDGE FLOORS	5,108 SF		
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	121.4 CY		
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+25.50-L-)	Lump Sum	L.S.	
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+20.00-L-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	18,220 LB		
0088	8259000000-E	430	36" PRESTRESSED CONCRETE GIRDERS	580.9 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8364000000-E	450	HP12X53 STEEL PILES	420 LF		
0090	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	360 LF		
0091	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	120 LF		
0092	8387000000-E	450	PP 18 X 0.50 GALVANIZED STEEL PILES	373 LF		
0093	8391000000-N	450	STEEL PILE POINTS	24 EA		
0094	8503000000-E	460	CONCRETE BARRIER RAIL	419.72 LF		
0095	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	186 TON		
0096	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	207 SY		
0097	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0098	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0099	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	624.01 LF		
0100	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" GALVANIZED STEEL SHEET PILES	2,820 SF		

1524/June12/O76385.03/D446369430000/E100

Total Amount Of Bid For Entire Project :

Contract No **C202117**

County (ies): **McDowell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General