

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19 + 60.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0007	0106000000-E	230	BORROW EXCAVATION	16,550 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	25 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	540 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	36 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	84 LF		
0016	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	76 LF		
0017	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
001E	0995000000-E	340	PIPE REMOVAL	27 LF		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0996000000-N	350	PIPE CLEAN-OUT	2		EA
0020	1220000000-E	545	INCIDENTAL STONE BASE	200		TON
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	600		TON
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	410		TON
0023	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	490		TON
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	80		TON
0025	2000000000-N	806	RIGHT OF WAY MARKERS	13		EA
0026	2253000000-E	840	PIPE COLLARS	1		CY
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3		EA
0028	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1		EA
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1		EA
0030	2556000000-E	846	SHOULDER BERM GUTTER	24		LF
0031	3030000000-E	862	STEEL BM GUARDRAIL	650		LF
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		EA
0034	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4		EA
0035	3635000000-E	876	RIP RAP, CLASS II	200		TON
0036	3649000000-E	876	RIP RAP, CLASS B	20		TON

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	775	SY	
003E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
003E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	41.4	SF	
004C	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	54.19	SF	
0041	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	75.31	SF	
0042	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	405	LF	
004E	4096000000-N	904	SIGN ERECTION, TYPE D	6	EA	
0044	4102000000-N	904	SIGN ERECTION, TYPE E	11	EA	
004E	4108000000-N	904	SIGN ERECTION, TYPE F	5	EA	
004E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	3	EA	
0047	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	19	EA	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	72	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144	SF	
005C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	52	SF	
0051	4430000000-N	1130	DRUMS	56	EA	
0052	4435000000-N	1135	CONES	30	EA	
005E	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4450000000-N	1150	FLAGGER	664 HR		
005E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
005E	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1 EA		
0057	4480000000-N	1165	TMIA	1 EA		
005E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	260 LF		
005E	4516000000-N	1180	SKINNY DRUM	56 EA		
006C	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	72 EA		
0061	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,180 LF		
0062	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,980 LF		
006E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	42 LF		
0064	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (3)	1,720 LF		
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,852 LF		
006E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	84 LF		
0067	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	5 EA		
006E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	13 EA		
006E	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
007C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	145 TON		
0072	6012000000-E	1610	SEDIMENT CONTROL STONE	280 TON		
0073	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0074	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0075	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0076	6024000000-E	1622	TEMPORARY SLOPE DRAINS	375 LF		
0077	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0078	6029000000-E	SP	SAFETY FENCE	475 LF		
0079	6030000000-E	1630	SILT EXCAVATION	850 CY		
0080	6036000000-E	1631	MATTING FOR EROSION CONTROL	825 SY		
0081	6037000000-E	SP	COIR FIBER MAT	25 SY		
0082	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	75 SY		
0083	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0084	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0085	6071030000-E	SP	COIR FIBER BAFFLES	175 LF		
0086	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0087	6071050000-E	SP	*** SKIMMER (2-1/2")	1 EA		
0088	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0089	6087000000-E	1660	MOWING	1.5 ACR		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0094	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0096	6123000000-E	1670	REFORESTATION	0.4 ACR		
<b>STRUCTURE ITEMS</b>						
0097	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (19+60.00 -L-)	Lump Sum	L.S.	
009E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+60.00 -L-)	Lump Sum	L.S.	
0099	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	60.5 LF		
010C	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	27 LF		
0101	8113000000-N	SP	SID INSPECTION	2 EA		
0102	8114000000-N	SP	SPT TESTING	2 EA		
0103	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0104	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	14,025 SF		
010E	8161000000-E	420	GROOVING BRIDGE FLOORS	12,293 SF		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	114.4 CY		
0107	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+60.00 -L-)	Lump Sum	L.S.	
0108	8217000000-E	425	REINFORCING STEEL (BRIDGE)	25,433 LB		
0109	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,183 LB		
0110	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	534,100 LS		
0111	8364000000-E	450	HP12X53 STEEL PILES	450 LF		
0112	8503000000-E	460	CONCRETE BARRIER RAIL	795.74 LF		
0113	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	590 TON		
0114	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	656 SY		
0115	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0116	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0117	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA ***** (19+60.00 -L-)	Lump Sum	L.S.	

0833/Jun09/Q638964.69/D531666550000/E117

Total Amount Of Bid For Entire Project :

**Contract No**     **C201815**

**County (ies):**   **Stokes**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General