



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY  
GOVERNOR

LYNDO TIPPETT  
SECRETARY

June 23, 2008

**Addendum No. 1**

RE: Contract ID: C202007

WBS# 34445.4.2 (Proposal No. 2)

**Yancey County (R-2518B)**

US-19 From 0.8 Kilometer East of Yancey County Line

To SR-1336 (Jack's Creek Road)

**July 15, 2008 Letting**

To Whom It May Concern:

Reference is made to the plans and proposal form recently furnished to you on this project.

The following revision has been made to the Roadway Plans:

Note "D" on Sheet No. TCP-2 has been revised. Please void Sheet No. TCP-2 in your plans and staple the revised Sheet No. TCP-2 thereto.

The following revision has been made to the Structure Subsurface Plans:

Sheet Nos. 1 of 20 thru 20 of 20 are being added. These sheets constitute the subsurface plans for the bridge over Cane River and were inadvertently omitted. Please staple Sheet Nos. 1 of 20 thru 20 of 20 to the back of the Structure Subsurface plans previously provided for this project.

The following revisions have been made to the proposal:

On Page No. 32, the Project Special Provision entitled "Delay in Right of Entry" has been added. Please void Page No.32 in your proposal and staple the revised Page No. 32 thereto.

The Table of Contents has been revised to reflect the above noted change. Please void the Table of Contents in your proposal and staple the revised Table of Contents thereto.

**MAILING ADDRESS:**  
NC DEPARTMENT OF TRANSPORTATION  
CONTRACTS & PROPOSALS  
1591 MAIL SERVICE CENTER  
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4124  
FAX: 919-250-4127

WEBSITE: [WWW.NCDOT.ORG](http://WWW.NCDOT.ORG)

**LOCATION:**  
CENTURY CENTER COMPLEX  
BUILDING B - ENTRANCE B15  
1020 BIRCH RIDGE DRIVE  
RALEIGH NC 27610


Page No. 2

RE: Contract ID: C202007

**Yancey County (R-2518B)**

On Page No.97, the Project Special Provision entitled "Utility Conflicts" has been revised. Please void Page No. 97 in your proposal and staple the revised Page No. 97 thereto. The Completion Date has been re-evaluated in light of these revised "Utility Conflicts" provisions and it has been determined that no change will be made.

Sincerely,



R. A. Garris, PE  
Contract Officer

RAG/jag/blr

Cc: Mr. W. S. Varnedoe, PE  
Mr. E. C. Powell, PE  
Mr. J. J. Swain, Jr., PE  
Ms. D.M. Barbour, PE  
Mr. Art McMillan, PE  
Mr. J. V. Barbour, PE  
Mr. G. R. Perfetti, PE  
Mr. Stuart Bourne, PE  
Mr. Mark Staley (2)  
Mr. Robert Memory  
Mr. R. E. Davenport, Jr., PE  
Ms. Norma Smith  
Ms. Marsha Sample  
Mr. Ronnie Higgins  
Mr. Larry Strickland  
Ms. Lori Strickland  
Project File (2)

**TABLE OF CONTENTS**

**COVER SHEET  
PROPOSAL SHEETS**

<b><u>PROJECT SPECIAL PROVISIONS</u></b> (GREEN SHEETS)	<i>PAGE No.</i>
Notice to Bidders.....	1
Contract Time and Liquidated Damages.....	2
Intermediate Contract Time(s).....	2-4
Construction Moratorium.....	4
Major Contract Items.....	4
Specialty Items.....	5
Fuel Price Adjustment (Metric).....	5-6
Schedule of Estimated Completion Progress.....	6
Minority and Women Business.....	7-18
Progress Schedule.....	18-19
Contractor Licenses Requirements.....	19
Submission of Bids – Alternates.....	19-20
Subsurface Information.....	20
Portable Concrete Barrier (Partial Payments for Materials).....	20
Maintenance of the Project.....	20-21
Cooperation Between Contractors.....	21
Bid Documentation.....	21-24
Twelve Month Guarantee.....	24-25
Outsourcing Outside U.S.A.....	25
Act of God.....	25
Erosion & Sediment Control / Storm Water Certification.....	25-30
Procedure for Monitoring Borrow Pit Discharge.....	30-32
Note to Contractor.....	32
Delay of Entry .....	32
Roadway.....	33-95
Traffic Control.....	96
Utility Conflicts.....	97-98
Erosion Control.....	99-141
Signals and Intelligent Transportation Systems.....	142-150
Project Special Provisions Structure / Culverts.....	151-224
<b><u>PERMITS</u></b> (WHITE SHEETS).....	225-331

**STANDARD SPECIAL PROVISIONS** (YELLOW SHEETS)

Availability of Funds – Termination of Contracts.....	1
General Seed Specification for Seed Quality.....	2-4
Errata.....	5
Plant and Pest Quarantines.....	6
Minimum Wage (State Funded).....	7
On the Job Training.....	8-10

**PROPOSAL ITEM SHEET AND SIGNATURE SHEET**

- Item Sheet (s)
- Signature Sheet (Bid Acceptance by Department)

noncompensatory and are options that may be needed for protection of rare or unique resources or where special environmental conditions exist at the site which have led to additional requirements being placed in the DWQ's 401 Certifications and approval letters, Isolated Wetland Permits, Riparian Buffer Authorization or a DOT Reclamation Plan's Environmental Assessment for the specific site. Should the Contractor exhaust all Tier I Methods on a site exclusive of rare or unique resources or special environmental conditions, Tier II Methods may be required by regulators on a case by case basis per supplemental agreement.

The Contractor may use cation exchange capacity (CEC) values from proposed site borings to plan and develop the bid for the project. CEC values exceeding 15 milliequivalents per 100 grams of soil may indicate a high potential for turbidity and should be avoided when dewatering into surface water is proposed.

No additional compensation for monitoring borrow pit discharge will be paid.

**NOTE TO CONTRACTOR:**

The Contractor's attention is directed to the Special Provision entitled "Contractor Requirements for Stream Relocations, Restorations and Enhancements", located in the Erosion Control Project Special Provisions.

The documents listed below are available to the Contractor on the NCDOT web site at the following address: <http://dotw-xfer01.dot.state.nc.us/dsplan/2008%20Highway%20Letting/>

- The Biological Opinion dated March 14, 2008
- Stream Mitigation Plan R-2518B
- Stream Mitigation Guidelines

**DELAY IN RIGHT OF ENTRY:**

(7-1-95)

M1 G22

The Contractor will not be allowed right of entry to the parcels listed below before September 15, 2008 unless otherwise permitted by the Engineer.

<b><u>Parcel No.</u></b>	<b><u>Property Owner</u></b>
034	Carl Penland
036	Dennis E. Robinson
050	Riverside Baptist Church
047	Richard Byrd

PROJECT: R-2518B  
COUNTY: Yancey

97

PROJECT SPECIAL PROVISIONS  
Utilities

UTILITY CONFLICTS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. French Broad EMC
- B. Verizon
- C. Country Cable
- D. Town Of Burnsville

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

A. French Broad EMC

- 1. See "Utilities By Others Plans" for utility conflicts.
- 2. Overhead utility lines cross 3 culvert installations at stations 138+00 -L-, 164+85 -L-, and 167+90 -L-. The contractor shall coordinate with the utility companies to ensure the safety of the workers and utilities during construction.
- 3. All facilities will be relocated by December 31, 2008.

B. Verizon

- 1. See "Utilities By Others Plans" for utility conflicts.
- 2. All facilities will be relocated by December 31, 2008.

C. Country Cable

- 1. See "Utilities By Others Plans" for utility conflicts.
- 2. All facilities will be relocated by December 31, 2008.