

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+22.30)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,660 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	2 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	12 LF		
0011	1121000000-E	520	AGGREGATE BASE COURSE	1,098 TON		
0012	1275000000-E	600	PRIME COAT	1,050 GAL		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	330 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	220 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	990 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	85 TON		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0018	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2556000000-E	846	SHOULDER BERM GUTTER	22 LF		
0020	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0021	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0022	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0023	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0024	3360000000-E	863	REMOVE EXISTING GUARDRAIL	721 LF		
0025	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	325 LF		
0026	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0027	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	5 EA		
0028	3635000000-E	876	RIP RAP, CLASS II	80 TON		
0029	3649000000-E	876	RIP RAP, CLASS B	500 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,720 SY		
0031	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0032	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	29 LF		
0033	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0034	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	88 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	32 SF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4430000000-N	1130	DRUMS	40	EA	
0039	4435000000-N	1135	CONES	25	EA	
0040	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
0041	4450000000-N	1150	FLAGGER	560	HR	
0042	4480000000-N	1165	TMIA	1	EA	
0043	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	16	EA	
0044	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	31,064	LF	
0045	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,920	LF	
0046	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	16	EA	
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,195	LF	
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50	TON	
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	170	TON	
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	40	TON	
0051	6015000000-E	1615	TEMPORARY MULCHING	3.5	ACR	
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	
0055	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0056	6029000000-E	SP	SAFETY FENCE	400	LF	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6030000000-E	1630	SILT EXCAVATION	720 CY		
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,275 SY		
0059	6037000000-E	SP	COIR FIBER MAT	50 SY		
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0061	6071030000-E	SP	COIR FIBER BAFFLES	330 LF		
0062	6071050000-E	SP	*** SKIMMER (1-1/2")	7 EA		
0063	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0064	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		
0065	6087000000-E	1660	MOWING	2.5 ACR		
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	2.75 TON		
0070	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0072	6123000000-E	1670	REFORESTATION	1.4 ACR		

STRUCTURE ITEMS

0073	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (16+22.30-L-)	Lump Sum	L.S.	
------	--------------	----	--	----------	------	--

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+22.30-L-)	Lump Sum	L.S.	
0075	8112730000-N	SP	PDA TESTING	1 EA		
0076	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0077	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+22.30-L-)	Lump Sum	L.S.	
0078	8156000000-E	SP	CONCRETE WEARING SURFACE	4,040 SF		
0079	8161000000-E	420	GROOVING BRIDGE FLOORS	5,289 SF		
0080	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	44.7 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+22.30-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,593 LB		
0083	8364000000-E	450	HP12X53 STEEL PILES	940 LF		
0084	8393000000-N	450	PILE REDRIVES	12 EA		
0085	8503000000-E	460	CONCRETE BARRIER RAIL	225.5 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	225 TON		
0087	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	245 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0089	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0090	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	1,464.125 LF		

Contract No **C201893**

County (ies): **Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General