

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	400 CY		
0003	0170000000-E	SP	REMOVAL OF EXISTING CONCRETE PAVEMENT SLABS	3,100 SY		
0004	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	400 CY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	92,000 SY		
0006	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,800 TON		
0007	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	22,130 TON		
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	13,300 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,117 TON		
0010	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	798 TON		
0011	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	667 TON		
0012	1702000000-E	657	SEALING EXISTING PAVEMENT CRACKS & JOINTS	40,000 LB		
0013	1737000000-E	SP	PATCHING CONCRETE PAVEMENT SPALLS	1,170 SF		
0014	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	6,439 TON		
0015	1839120000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE C	4,600 TON		
0016	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	368,000 SY		
0017	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	142,232 LF		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2022000000-E	815	SUBDRAIN EXCAVATION	100 CY		
0019	2033000000-E	815	SUBDRAIN FINE AGGREGATE	100 CY		
0020	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0022	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2473000000-N	SP	GENERIC DRAINAGE ITEM DROP INLET REPAIR	25 EA		
0025	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	600 SF		
0026	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0027	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0028	4430000000-N	1130	DRUMS	200 EA		
0029	4480000000-N	1165	TMIA	4 EA		
0030	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	176,910 LF		
0031	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	10,000 LF		
0032	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	6 EA		
0033	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	176,910 LF		
0034	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)	10,000 LF		
0035	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (HIGHLY REFLECTIVE ELEMENTS)	6 EA		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,000 EA		

1143/Jul11/Q1074541.0/D92593970000/E36

Total Amount Of Bid For Entire Project :

Contract No **C202015**

County (ies): **Halifax**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)