

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 95.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	128 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	188 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	108 LF		
0013	0995000000-E	340	PIPE REMOVAL	70 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	275 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	260 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	38 TON		
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
002C	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	4 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0022	3030000000-E	862	STEEL BM GUARDRAIL	175 LF		
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (BIC)	1 EA		
002E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
002E	3635000000-E	876	RIP RAP, CLASS II	30 TON		
003C	3649000000-E	876	RIP RAP, CLASS B	305 TON		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,010 SY		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	372 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,200 LF		
003E	6000000000-E	1605	TEMPORARY SILT FENCE	535 LF		
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150 TON		
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	105 TON		
004C	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0043	6029000000-E	SP	SAFETY FENCE	240 LF		
0044	6030000000-E	1630	SILT EXCAVATION	415 CY		
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	750 SY		
004E	6037000000-E	SP	COIR FIBER MAT	15 SY		
0047	6071030000-E	SP	COIR FIBER BAFFLES	60 LF		
004E	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
004E	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
005C	6087000000-E	1660	MOWING	0.5 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
005E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0057	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16 + 95.00-L-)	Lump Sum	L.S.	
005E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 95.00-L-)	Lump Sum	L.S.	
005E	8096000000-E	SP	PILE EXCAVATION IN SOIL	5 LF		
006C	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	53 LF		
0061	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16 + 95.00-L-)	Lump Sum	L.S.	
0062	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	44 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 95.00-L-)	Lump Sum	L.S.	
0064	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,101 LB		
006E	8364000000-E	450	HP12X53 STEEL PILES	285 LF		
006E	8387000000-E	450	PP 18 X 0.50 GALVANIZED STEEL PILES	200 LF		
0067	8392000000-N	450	PIPE PILE PLATES	7 EA		
006E	8503000000-E	460	CONCRETE BARRIER RAIL	214.5 LF		
006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	310 TON		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	345 SY		
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0072	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,179.75 LF		
0073	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" GALVANIZED STEEL SHEET PILES	510 SF		
0837/Jun30/Q21749.5/D337759580000/E73			Total Amount Of Bid For Entire Project :			

Contract No **C201899**

County (ies): **Iredell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General