

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 72.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	5 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	100 CY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	7 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	753 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	357 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	56 TON		
0016	2000000000-N	806	RIGHT OF WAY MARKERS	16 EA		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0018	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0020	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0021	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0022	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0025	2556000000-E	846	SHOULDER BERM GUTTER	44 LF		
0026	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0029	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0030	3649000000-E	876	RIP RAP, CLASS B	8 TON		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	260 SY		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	354 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0035	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,764 LF		
0036	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,764 LF		

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (3)	572 LF		
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	13 EA		
003E	6000000000-E	1605	TEMPORARY SILT FENCE	1,620 LF		
004C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
004E	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	120 LF		
0047	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
004E	6029000000-E	SP	SAFETY FENCE	240 LF		
004E	6030000000-E	1630	SILT EXCAVATION	85 CY		
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	290 SY		
0051	6037000000-E	SP	COIR FIBER MAT	15 SY		
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	220 LF		
005E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	90 SY		
0054	6071030000-E	SP	COIR FIBER BAFFLES	60 LF		

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0057	6087000000-E	1660	MOWING	1.5 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0062	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0064	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+72.00 -L-)	Lump Sum	L.S.	
006E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+72.00 -L-)	Lump Sum	L.S.	
006E	8156000000-E	SP	CONCRETE WEARING SURFACE	4,986 SF		
0067	8161000000-E	420	GROOVING BRIDGE FLOORS	6,109 SF		
006E	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	62.5 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+72.00 -L-)	Lump Sum	L.S.	
007C	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	10,090 LB		

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8333000000-E	450	16" PRESTRESSED CONC PILES	720 LF		
0072	8336000000-E	450	20" PRESTRESSED CONC PILES	400 LF		
0073	8503000000-E	460	CONCRETE BARRIER RAIL	280.52 LF		
0074	8590000000-E	876	RIP RAP, CLASS ** (I)	205 TON		
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	227 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0078	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,820 LF		
0846/Jul31/Q35954.52/D357934680000/E78				Total Amount Of Bid For Entire Project :		

Contract No **C201851**

County (ies): **Carteret**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General