

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (54 + 89.84)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1,350 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0106000000-E	230	BORROW EXCAVATION	30,500 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	390 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	2,200 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	3,000 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	580 SF		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	80 TON		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		
0015	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	252 LF		
0016	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	112 LF		
0017	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	148 LF		
0018	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	88 LF		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0020	0995000000-E	340	PIPE REMOVAL	151 LF		
0021	1121000000-E	520	AGGREGATE BASE COURSE	2,250 TON		
0022	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	500 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	600 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	980 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,120 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	140 TON		
0027	2209000000-E	838	ENDWALLS	4.5 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0029	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0030	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
0032	2710000000-N	854	CONCRETE BARRIER TRANSITION SECTION	2 EA		
0033	3030000000-E	862	STEEL BM GUARDRAIL	1,500 LF		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0035	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0037	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0039	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
004C	3578000000-N	SP	GENERIC FENCING ITEM RESET GATE	2 EA		
0041	3628000000-E	876	RIP RAP, CLASS I	225 TON		
0042	3642000000-E	876	RIP RAP, CLASS A	5,555 TON		
0043	3649000000-E	876	RIP RAP, CLASS B	15 TON		
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	565 SY		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	194 SF		
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	30 SF		
004E	4430000000-N	1130	DRUMS	70 EA		
004E	4435000000-N	1135	CONES	60 EA		
005C	4445000000-E	1145	BARRICADES (TYPE III)	78 LF		
0051	4455000000-N	1150	FLAGGER	66 MD		
0052	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0053	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0054	4485000000-E	1170	PORTABLE CONCRETE BARRIER	2,418 LF		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	70 LF		
005E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	8 EA		
0057	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (4)	512 LF		
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	38,348 LF		
005E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	66 LF		
006C	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,618 LF		
0061	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	31 EA		
0062	6000000000-E	1605	TEMPORARY SILT FENCE	2,835 LF		
006E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	280 TON		
0064	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	420 TON		
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	295 TON		
006E	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0067	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	445 LF		
007C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7 EA		
0071	6029000000-E	SP	SAFETY FENCE	2,336 LF		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6030000000-E	1630	SILT EXCAVATION	1,240 CY		
0073	6036000000-E	1631	MATTING FOR EROSION CONTROL	17,500 SY		
0074	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	280 SY		
0075	6042000000-E	1632	1/4" HARDWARE CLOTH	225 LF		
0076	6045000000-E	SP	*** TEMPORARY PIPE (15")	200 LF		
0077	6045000000-E	SP	*** TEMPORARY PIPE (18")	150 LF		
0078	6045000000-E	SP	*** TEMPORARY PIPE (36")	100 LF		
0079	6070000000-N	SP	SPECIAL STILLING BASINS	1 EA		
0080	6084000000-E	1660	SEEDING & MULCHING	10.5 ACR		
0081	6087000000-E	1660	MOWING	4 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	4.75 TON		
0086	6111000000-E	SP	IMPERVIOUS DIKE	36 LF		
0087	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0088	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0089	7060000000-E	1705	SIGNAL CABLE	1,360 LF		
0090	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8 EA		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	7264000000-E	1710	MESSENGER CABLE (3/8")	1,270 LF		
0092	7360000000-N	1720	WOOD POLE	10 EA		
0093	7372000000-N	1721	GUY ASSEMBLY	6 EA		
0094	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0095	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3 EA		
0096	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	560 LF		
0097	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	1,770 LF		
009E	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
009E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	2 EA		
<b>STRUCTURE ITEMS</b>						
010C	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (54 + 89.84)	Lump Sum	L.S.	
0101	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	81.9 LF		
0102	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	32 LF		
0103	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	90.6 LF		
0104	8113000000-N	SP	SID INSPECTION	1 EA		
010E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
010E	8126000000-N	414	CULVERT EXCAVATION, STA ***** (60 + 29.30)	Lump Sum	L.S.	

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	90 TON		
010E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,175 SF		
010E	8161000000-E	420	GROOVING BRIDGE FLOORS	8,467 SF		
011C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	183.3 CY		
0111	8196000000-E	420	CLASS A CONCRETE (CULVERT)	152.4 CY		
0112	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (54 + 89.84)	Lump Sum	L.S.	
0113	8217000000-E	425	REINFORCING STEEL (BRIDGE)	41,507 LB		
0114	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,308 LB		
0115	8245000000-E	425	REINFORCING STEEL (CULVERT)	24,365 LB		
0116	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	798.01 LF		
0117	8364000000-E	450	HP12X53 STEEL PILES	480 LF		
011E	8391000000-N	450	STEEL PILE POINTS	16 EA		
011E	8503000000-E	460	CONCRETE BARRIER RAIL	406.54 LF		
012C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	671.9 TON		
0121	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	746.4 SY		
0122	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0123	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

**Contract No**     **C201819**

**County (ies):**   **Cherokee**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General