

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #109)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #112)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #62)	Lump Sum	L.S.	
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #67)	Lump Sum	L.S.	
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	5,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	200 CY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	100 TON		
0010	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	800 LF		
0011	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	32 EA		
0012	0995000000-E	340	PIPE REMOVAL	100 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (0" TO 5")	4,000 SY		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,300 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	700 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	185 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	16 EA		
0019	2355000000-N	840	FRAME WITH GRATE, STD 840.29	16 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	240 LF		
0021	3030000000-E	862	STEEL BM GUARDRAIL	2,775 LF		
0022	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	16 EA		
0025	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	16 EA		
0026	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,692 LF		
0027	3566000000-E	867	WOVEN WIRE FENCE RESET	400 LF		
0028	3649000000-E	876	RIP RAP, CLASS B	32 TON		
0029	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	112 SY		
0030	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	2,250 SF		
0031	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	400 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	620 SF		
0033	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0034	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0035	4430000000-N	1130	DRUMS	350 EA		
0036	4445000000-E	1145	BARRICADES (TYPE III)	240 LF		
0037	4450000000-N	1150	FLAGGER	140 HR		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4480000000-N	1165	TMIA	2 EA		
0039	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	8,400 LF		
0040	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	8,200 LF		
0041	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	190 LF		
0042	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,100 LF		
0043	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	61 EA		
0044	6000000000-E	1605	TEMPORARY SILT FENCE	5,425 LF		
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200 TON		
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0047	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0048	6024000000-E	1622	TEMPORARY SLOPE DRAINS	800 LF		
0049	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	16 EA		
0050	6030000000-E	1630	SILT EXCAVATION	100 CY		
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,500 SY		
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	300 LF		
0053	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0054	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0055	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	98 CY		
0056	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #109)	Lump Sum	L.S.	
0057	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #112)	Lump Sum	L.S.	
0058	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #62)	Lump Sum	L.S.	
0059	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #67)	Lump Sum	L.S.	
0060	8217000000-E	425	REINFORCING STEEL (BRIDGE)	19,742 LB		
0061	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	38,300 LS		
0062	8678000000-E	SP	EPOXY RESIN INJECTION	100 LF		
0063	8685000000-E	SP	EPOXY MORTAR REPAIRS	12 SF		
0064	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0065	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE # 109)	Lump Sum	L.S.	
0066	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE # 112)	Lump Sum	L.S.	
0067	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE # 67)	Lump Sum	L.S.	
0068	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE #62)	Lump Sum	L.S.	
0069	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #109)	Lump Sum	L.S.	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #112)	Lump Sum	L.S.	
0071	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #62)	Lump Sum	L.S.	
0072	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #67)	Lump Sum	L.S.	
0909/Aug14/Q118619.0/D332074100000/E72			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202018**

**County (ies):**    **Johnston**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General