

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000950000-E	SP	GENERIC MISCELLANEOUS ITEM SLOPE STABILIZATION	4,000 SF		
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	2 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	150,600 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (137+86.34)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (138+03.66)	Lump Sum	L.S.	
0009	0036000000-E	225	UNDERCUT EXCAVATION	4,000 CY		
0010	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	2,500 TON		
0011	0106000000-E	230	BORROW EXCAVATION	62,600 CY		
0012	0134000000-E	240	DRAINAGE DITCH EXCAVATION	6,840 CY		
0013	0141000000-E	240	BERM DITCH CONSTRUCTION	2,200 LF		
0014	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	2,560 SY		
0015	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	34,000 SY		
0016	0192000000-N	260	PROOF ROLLING	20 HR		
0017	0195000000-E	265	SELECT GRANULAR MATERIAL	3,000 CY		
0018	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	6,000 SY		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0199000000-E	SP	TEMPORARY SHORING	1,320	SF	
0020	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,780	TON	
0021	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	224	LF	
0022	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	76	LF	
0023	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	836	LF	
0024	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	40	LF	
0025	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	268	LF	
0026	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	40	LF	
0027	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	28	EA	
0028	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2	EA	
0029	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6	EA	
0030	0809000000-E	310	30" BIT COAT CS PIPE ELBOWS, TYPE B 0.079" THICK	2	EA	
0031	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (24")	63	LF	
0032	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (72")	117	LF	
0033	0973300000-E	330	*** WELDED STEEL PIPE NOT IN SOIL (24")	21	LF	
0034	0973300000-E	330	*** WELDED STEEL PIPE NOT IN SOIL (72")	39	LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0995000000-E	340	PIPE REMOVAL	1,984 LF		
0036	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0037	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	56,480 SY		
0038	1066000000-E	501	LIME FOR LIME TREATED SOIL	570 TON		
0039	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0040	1121000000-E	520	AGGREGATE BASE COURSE	43,700 TON		
0041	1176000000-E	542	SOIL CEMENT BASE	18,830 SY		
0042	1187000000-E	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	518 TON		
0043	1198000000-E	SP	AGGREGATE FOR SOIL CEMENT BASE	290 TON		
0044	1209000000-E	543	ASPHALT CURING SEAL	11,300 GAL		
0045	1220000000-E	545	INCIDENTAL STONE BASE	10,000 TON		
0046	1275000000-E	600	PRIME COAT	15,295 GAL		
0047	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	24,300 SY		
0048	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (5")	1,400 SY		
0049	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	780 TON		
0050	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	12,940 TON		
0051	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	140 TON		
0052	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	24,710 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,340 TON		
0054	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	25,530 TON		
0055	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,840 TON		
0056	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,535 TON		
0057	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	440 TON		
0058	2000000000-N	806	RIGHT OF WAY MARKERS	117 EA		
0059	2022000000-E	815	SUBDRAIN EXCAVATION	504 CY		
0060	2033000000-E	815	SUBDRAIN FINE AGGREGATE	252 CY		
0061	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,500 LF		
0062	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	45 EA		
0063	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	3 EA		
0064	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	18 LF		
0065	2143000000-E	818	BLOTTING SAND	20 TON		
0066	2209000000-E	838	ENDWALLS	4.9 CY		
0067	2220000000-E	838	REINFORCED ENDWALLS	14.2 CY		
0068	2253000000-E	840	PIPE COLLARS	10.155 CY		
0069	2264000000-E	840	PIPE PLUGS	2.134 CY		
0070	2275000000-E	SP	FLOWABLE FILL	150 CY		
0071	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	113 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	44.2		
					LF	
0073	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	5		
					EA	
0074	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	11		
					EA	
0075	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	64		
					EA	
0076	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	7		
					EA	
0077	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	14		
					EA	
0078	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	12		
					EA	
0079	2396000000-N	840	FRAME WITH COVER, STD 840.54	3		
					EA	
0080	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	31,700		
					LF	
0081	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,000		
					LF	
0082	2556000000-E	846	SHOULDER BERM GUTTER	3,300		
					LF	
0083	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	400		
					LF	
0084	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	8		
					EA	
0085	2612000000-E	848	6" CONCRETE DRIVEWAY	200		
					SY	
0086	2619000000-E	850	4" CONCRETE PAVED DITCH	130		
					SY	
0087	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,875		
					SY	
0088	2752000000-E	SP	GENERIC PAVING ITEM TEMPORARY 9" X 12" ASPHALT CURBING	1,000		
					LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	2920000000-N	SP	CONVERT EXISTING DROP INLET TO CATCH BASIN	1 EA		
0090	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0091	2965000000-N	SP	CONVERT EXISTING JUNCTION BOX TO CATCH BASIN	4 EA		
0092	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING MANHOLE TO CATCH BASIN	1 EA		
0093	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0094	3030000000-E	862	STEEL BM GUARDRAIL	5,200 LF		
0095	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	150 LF		
0096	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0097	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0098	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0099	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0100	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	350 LF		
0101	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0102	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	28,400 LF		
0103	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	1,775 EA		
0104	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	475 EA		
0105	3557000000-E	866	ADDITIONAL BARBED WIRE	500 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	5,900 LF		
0107	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 16', 16')	4 EA		
0108	3575000000-E	SP	GENERIC FENCING ITEM TEMP 4 STRAND BARBED WIRE FENCE WITH POSTS	500 LF		
0109	3595000000-E	869	RELAPPING GUARDRAIL	325 LF		
0110	3628000000-E	876	RIP RAP, CLASS I	440 TON		
0111	3649000000-E	876	RIP RAP, CLASS B	880 TON		
0112	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,605 SY		
0113	4048000000-E	902	REINFORCED CONCRETE SIGN FOUN- DATIONS	1 CY		
0114	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	348 LB		
0115	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,410 LF		
0116	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		
0117	4102000000-N	904	SIGN ERECTION, TYPE E	93 EA		
0118	4108000000-N	904	SIGN ERECTION, TYPE F	3 EA		
0119	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	1 EA		
0120	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0121	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	1 EA		
0122	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	35 EA		
0123	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	688	SF	
0125	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	436	SF	
0126	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	143	SF	
0127	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0128	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4	EA	
0129	4430000000-N	1130	DRUMS	704	EA	
0130	4435000000-N	1135	CONES	115	EA	
0131	4445000000-E	1145	BARRICADES (TYPE III)	550	LF	
0132	4450000000-N	1150	FLAGGER	1,266	HR	
0133	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0134	4480000000-N	1165	TMIA	1	EA	
0135	4485000000-E	1170	PORTABLE CONCRETE BARRIER	368	LF	
0136	4510000000-N	SP	POLICE	40	HR	
0137	4516000000-N	1180	SKINNY DRUM	100	EA	
0138	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM WARNING FLAGS	17	EA	
0139	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	757	EA	
0140	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	34,322	LF	
0141	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	15,122	LF	
0142	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,771	LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0143	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	339	LF	
0144	4715000000-E	1205	THERMOPLASTIC RUMBLE STRIP (4" 240 MILS)	288	LF	
0145	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8	EA	
0146	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	103	EA	
0147	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,580	LF	
0148	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,140	LF	
0149	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	242,895	LF	
0150	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,296	LF	
0151	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,680	LF	
0152	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	16	EA	
0153	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	222	EA	
0154	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	39,231	LF	
0155	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	86	LF	
0156	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	679	EA	
0157	5325600000-E	1510	6" WATER LINE	16	LF	
0158	5325800000-E	1510	8" WATER LINE	162	LF	
0159	5326600000-E	1510	16" WATER LINE	2,266	LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0160	5540000000-E	1515	6" VALVE	1	EA	
0161	5546000000-E	1515	8" VALVE	1	EA	
0162	5672000000-N	1515	RELOCATE FIRE HYDRANT	4	EA	
0163	5801000000-E	1530	ABANDON 8" UTILITY PIPE	162	LF	
0164	5810000000-E	1530	ABANDON 16" UTILITY PIPE	2,244	LF	
0165	5900000000-E	SP	GENERIC UTILITY ITEM FOUNDATION CONDITIONING MATE- RIAL	150	TON	
0166	6000000000-E	1605	TEMPORARY SILT FENCE	5,300	LF	
0167	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	2,675	TON	
0168	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	3,875	TON	
0169	6012000000-E	1610	SEDIMENT CONTROL STONE	4,510	TON	
0170	6015000000-E	1615	TEMPORARY MULCHING	78.5	ACR	
0171	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	3,100	LB	
0172	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	13.25	TON	
0173	6024000000-E	1622	TEMPORARY SLOPE DRAINS	800	LF	
0174	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	17	EA	
0175	6029000000-E	SP	SAFETY FENCE	1,250	LF	
0176	6030000000-E	1630	SILT EXCAVATION	46,070	CY	
0177	6036000000-E	1631	MATTING FOR EROSION CONTROL	46,000	SY	
0178	6037000000-E	SP	COIR FIBER MAT	135	SY	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0179	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	3,590	SY	
0180	6042000000-E	1632	1/4" HARDWARE CLOTH	1,215	LF	
0181	6070000000-N	SP	SPECIAL STILLING BASINS	24	EA	
0182	6071010000-E	SP	WATTLE	360	LF	
0183	6071020000-E	SP	POLYACRYLAMIDE (PAM)	225	LB	
0184	6071030000-E	SP	COIR FIBER BAFFLES	5,235	LF	
0185	6071050000-E	SP	*** SKIMMER (1-1/2")	5	EA	
0186	6071050000-E	SP	*** SKIMMER (2")	14	EA	
0187	6071050000-E	SP	*** SKIMMER (2-1/2")	3	EA	
0188	6084000000-E	1660	SEEDING & MULCHING	84	ACR	
0189	6087000000-E	1660	MOWING	48.5	ACR	
0190	6090000000-E	1661	SEED FOR REPAIR SEEDING	700	LB	
0191	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.75	TON	
0192	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,950	LB	
0193	6108000000-E	1665	FERTILIZER TOPDRESSING	58	TON	
0194	6114000000-N	SP	SPECIALIZED HAND MOWING	12	HR	
0195	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	54	EA	
0196	6123000000-E	1670	REFORESTATION	0.25	ACR	
0197	7060000000-E	1705	SIGNAL CABLE	1,600	LF	
0198	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	13	EA	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0199	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	5 EA		
0200	7264000000-E	1710	MESSENGER CABLE (3/8")	1,170 LF		
0201	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	770 LF		
0202	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6 EA		
0203	7360000000-N	1720	WOOD POLE	4 EA		
0204	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0205	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0206	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0207	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,770 LF		
0208	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	5,410 LF		
0209	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	2 EA		
0210	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4 EA		
0211	7613000000-N	SP	SOIL TEST	4 EA		
0212	7614100000-E	SP	DRILLED PIER FOUNDATION	24 CY		
0213	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0214	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0215	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	7 EA		
0216	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
0217	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS LIGHTNING ARRESTORS	2 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0218	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEMS	1 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0219 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	10,612 LF		
0220 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,460 LF		
0221 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,096 LF		
0222 AA1	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	40 LF		
*** OR ***						
0223 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	6,060 LF		
0224 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,744 LF		
0225 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	972 LF		
0226 AA2	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	24 LF		
0227 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	4,552 LF		
0228 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	716 LF		
0229 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	1,124 LF		
0230 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	16 LF		
*** OR ***						
0231 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	6,060 LF		
0232 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,744 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0233 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	972 LF		
0234 AA3	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	24 LF		
0235 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	4,552 LF		
0236 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	716 LF		
0237 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	1,124 LF		
0238 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (36", 0.079")	16 LF		

***** END SCHEDULE AA *****

0263	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
------	--------------	-----	------------------------	----------	------	--

STRUCTURE ITEMS

0239	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (137+95.00 -L-LT)	Lump Sum	L.S.	
0240	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (137+95.00 -L-LT)	Lump Sum	L.S.	
0241	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	431.5 LF		
0242	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	74 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0243	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	238.1 LF		
0244	8113000000-N	SP	SID INSPECTION	6 EA		
0245	8114000000-N	SP	SPT TESTING	6 EA		
0246	8115000000-N	SP	CROSSHOLE SONIC LOGGING	6 EA		
0247	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	2,330 CY		
0248	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (137+95.00 -L-RT)	Lump Sum	L.S.	
0249	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	21,926 SF		
0250	8161000000-E	420	GROOVING BRIDGE FLOORS	21,534 SF		
0251	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	307.9 CY		
0252	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (137+95.00 -L-LT)	Lump Sum	L.S.	
0253	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (137+95.00 -L-RT)	Lump Sum	L.S.	
0254	8217000000-E	425	REINFORCING STEEL (BRIDGE)	81,335 LB		
0255	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	13,825 LB		
0256	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	2,749.16 LF		
0257	8364000000-E	450	HP12X53 STEEL PILES	1,190 LF		
0258	8503000000-E	460	CONCRETE BARRIER RAIL	1,117.32 LF		
0259	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,470 TON		
0260	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,632 SY		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0261	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0262	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1051/Sep04/Q1323591.319/D1003076782000/E263			Total Amount Of Bid For Entire Project :			

Contract No **C201932**

County (ies): **Rowan**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General