

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,750 CY		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15 + 34.93)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	6.5 TON		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
0012	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0013	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	422 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	227 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	33 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	21 EA		
0019	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
002C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	130 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	87.5 LF		
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	137.5 LF		
003C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0033	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0034	3649000000-E	876	RIP RAP, CLASS B	2 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,110 SY		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	400	SF	
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	100	SF	
003E	4445000000-E	1145	BARRICADES (TYPE III)	50	LF	
0039	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,000	LF	
004C	6000000000-E	1605	TEMPORARY SILT FENCE	3,300	LF	
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	495	TON	
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	80	TON	
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	50	TON	
0044	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	75	LF	
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1	EA	
0049	6029000000-E	SP	SAFETY FENCE	200	LF	
005C	6030000000-E	1630	SILT EXCAVATION	125	CY	
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,100	SY	
0052	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	425	SY	
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	50	LF	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6071010000-E	SP	WATTLE	50 LF		
0055	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
0056	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
0057	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0058	6087000000-E	1660	MOWING	0.5 ACR		
0059	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0060	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0063	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

**STRUCTURE ITEMS**

0065	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 34.93 -L-)	Lump Sum	L.S.	
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15 + 34.93 -L-)	Lump Sum	L.S.	
0067	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,870 SF		
0068	8161000000-E	420	GROOVING BRIDGE FLOORS	3,750 SF		
0069	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	34 CY		
0070	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 34.93 -L-)	Lump Sum	L.S.	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,578 LB		
0072	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	114,889 LS		
0073	8364000000-E	450	HP12X53 STEEL PILES	400 LF		
0074	8503000000-E	460	CONCRETE BARRIER RAIL	236.67 LF		
0075	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	307 TON		
0076	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	340 SY		
0077	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0721/Aug07/Q154114.82/D335332160000/E77

Total Amount Of Bid For Entire Project :

**Contract No**     **C201298**

**County (ies):**   **Rutherford**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General