

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0057000000-E	226	UNDERCUT EXCAVATION	25 CY		
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	100 TON		
0006	0106000000-E	230	BORROW EXCAVATION	8,200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	520 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	20 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	88 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	20 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	64 LF		
0014	0995000000-E	340	PIPE REMOVAL	83 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	160 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0017	1275000000-E	600	PRIME COAT	105 GAL		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	570 TON		
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	420 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	55 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	19 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	5.6 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	4.2 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	25 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	1 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	350 LF		
003C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3628000000-E	876	RIP RAP, CLASS I	125 TON		
0033	3649000000-E	876	RIP RAP, CLASS B	255 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	6,990 SY		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	223 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0037	4430000000-N	1130	DRUMS	10 EA		
003E	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,400	LF	
004C	6000000000-E	1605	TEMPORARY SILT FENCE	1,875	LF	
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	540	TON	
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	310	TON	
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	100	TON	
0044	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	375	LF	
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
004E	6029000000-E	SP	SAFETY FENCE	500	LF	
005C	6030000000-E	1630	SILT EXCAVATION	680	CY	
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,000	SY	
0052	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	150	SY	
0053	6069000000-E	1638	STILLING BASINS	40	CY	
0054	6071030000-E	SP	COIR FIBER BAFFLES	200	LF	
005E	6084000000-E	1660	SEEDING & MULCHING	5.5	ACR	
005E	6087000000-E	1660	MOWING	1.5	ACR	
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
006C	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0061	6111000000-E	SP	IMPERVIOUS DIKE	375 LF		
0062	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0064	6120000000-E	SP	CULVERT DIVERSION CHANNEL	350 CY		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		
CULVERT ITEMS						
006E	8049000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 85.64-L-)	Lump Sum	L.S.	
0067	8126000000-N	414	CULVERT EXCAVATION, STA ***** (16 + 85.64-L-)	Lump Sum	L.S.	
008E	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	152 TON		
008E	8196000000-E	420	CLASS A CONCRETE (CULVERT)	248.5 CY		
007C	8245000000-E	425	REINFORCING STEEL (CULVERT)	47,587 LB		
1335/Jul31/Q93802.65/D268608130000/E70						
				Total Amount Of Bid For Entire Project :		

Contract No **C201929**

County (ies): **Rutherford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General